Average Testing Performance Data for Components of Performance-Based Treatment Systems (PBTS)

- from innovative system testing in Florida (Table 1) or
- from test centers for evaluation of use in nutrient and fecal coliform-reducing PBTS (Table 2) or
- from test centers for NSF-certification as aerobic treatment units (ATUs) (Table 3)
- Innovative drainfield/disposal systems (Table 4)
- Other innovative systems (Table 5)

Construction permits for PBTS must comply with Part IV of Rule 64E-6, Florida Administrative Code (FAC) (for details, see memo <u>HSES-10-001</u>). For all PBTS, the engineer will establish performance levels, and design the system as a whole to meet them. To find treatment receptacles approved for use for a particular PBTS, refer to the septic tank design approval listings at http://www.floridahealth.gov/environmental-health/onsite-sewage/products/ documents/septic-tanks.pdf.

- **Table 1** summarizes **results of innovative systems testing under non-test-center** conditions in Florida. The components listed in table 1 have undergone innovative system testing and been reviewed by the Bureau as indicated in the column "innovative status" for use as a component of an engineer-designed PBTS.
- Table 2 summarizes test center testing results either associated with an NSF or ETV protocol or during the Big Pine Key study in Florida. These data have been used to evaluate treatment components that might be used as a component of a nutrient-reducing or fecal coliform reducing PBTS designed by engineers. These are systems that are designed to reduce nitrogen and/or phosphorus to specified levels. The components listed in table 2 below have previously been reviewed by the Bureau as indicated in the column "innovative status". Equipment series where "yes" is indicated in the "Innovative Status" column, are currently in innovative status, indicating that such approval has occurred in a limited fashion, providing for a limited number of permits and requiring additional testing. Note that construction permits for systems currently in innovative status require forms DH 3144 and DH 3145 and must be reviewed by the Onsite Sewage Program office for compliance with the innovative system permit. in addition to the regular county health department review. "Passed" indicates that components are not in innovative status (completed innovative testing in Florida); "n/a" indicates components are not in innovative status (use of previously approved ATUs in nutrient reducing systems accepted based on third party data).
- **Table 3** summarizes test center testing results where the objective was usually to achieve certification by NSF under standard NSF-40 (**waste strength reduction**). The components listed in table 3 below are treatment systems approved in Florida as ATUs under rule 64E-6.012, Florida Administrative Code, except for the last few as noted. Currently, the Department is accepting such data as a form of documentation of the "application of sound engineering principles" by engineers designing PBTS with the only goal of **reducing waste strength** (CBOD5, TSS) in order to qualify **for drainfield size reductions** under 64E-6.028(5), Florida Administrative Code.
- **Table 4** lists additional innovative systems that are evaluated as drainfield/disposal systems.
- **Table 5** lists additional innovative systems.

Table 1. Results of Innovative System Testing in Florida

Component/		СВОГ	05 (mg/L)	TSS (ı	ng/L)	TN (mg	/L)	TN (%)	TP (mg	/L)		Vendor Contac	ntac Inn	Innovative
Configuration	Type of testing	In	Out	In	Out	In	Out		In	Out	Vendor	t Phone		Status
EcoPure 300	Innovative in Florida (n=25/9 of 1 system)	327	7.7	421	6.2	58	31		11	5.1	Eco-Pure Waste-water Systems	888- 999- 0936	www.eco- purewastewatersy stems. com	Passed
EnviroFilter C	Innovative in Florida (n=26/24 of 5 systems)		7.6		5.3		21.7			5.8	Earthtek Environmental Systems			Passed
Fuji Clean CE	Innovative in Florida (13 systems, 50-52 data points total); average of system averages		4.4		4.3	45**	10.9	75.7			Fuji Clean USA, LLC		www. fujicleanusa.com	Passed
Zerolmpact	Innovative in Florida (n=33/29 of 5 systems)		10.5		16.6		23			1.4	Biotech Systems LLC	352- 376- 8016	www .biofilter. com	Yes*

Table 2. Test Center Testing Results, which have been used in evaluating components proposed for nutrient- and fecal coliform reducing

performance-based treatment systems.

Equipment Series	Equipment	type of test	in TN (mg/L)	out TN (mg/L)	TN removal (%)	in TP (mg/L)	out TP (mg/L)	in fecal coliforms (CFU/100mL)	out fecal coliforms (CFU/100mL)	Vendor	Innovative Status*
	Advantex 20x Mode 1	N-testing concurrently with NSF-40, Squamish, B.C.	33	12	64%	_	-	-	-	Orenco	Yes*
Advantex	Advantex 20x Mode 3	N-testing after NSF-40, Mode 3	-	Systems	Yes*						
Aerocell	Aerocell ATS SCAT-8- AC-C500	NSF+Nitrogen, Waco	40	9.3	77%	-	-	-	-	Quanics (Anua)	Yes*
Aqua Safe	Aqua Safe 500	~31 N-tests during NSF-40 test	30.78	14.9	52%	8.21	5.87	-	2200 median	Ecological Tanks, Inc.	Yes*
Clearstream Model D	Clearstream 500 D	NSF 245 Prairieville, LA (June- November 2012)	42	19	53%	_	_	2,601,272 colonies/100 ml (geomean)	243 colonies/100 ml (geomean)	Clearstream Wastewater Systems, Inc.	Yes*
		Prairieville, LA after NSF 245 (December 2013 – May 2014)	42.3	10.7	74.8%	_	-	-	-		
CE	Fuji Clean CE 5	NSF-40+Nitrogen, Waco	47.6	15.7	67%						Passed (se Table 1)
CEN	Fuji Clean CEN 5	Testing concurrent with NSF40 (for fecal coliform)				-	-	2.0E+6 to 1.2E+9 (30- day geomean)	2.7E+4 to 6.3E+5 (30-day geomean)	Fuji Clean USA, LLC	Yes*
CEN		NSF 245, Waco TX (June – December 2014)	40	10.4	74%						Yes*

TN = Total Nitrogen

^{*}Construction permits require filing of DH 3144 and DH3145 and must be reviewed by the Onsite Sewage Program office for compliance with the innovative system permit.

^{**}Assumed concentration

Page 3/6; 5/31/2021

Table 2 (continued). Test Center Testing Results, which have been used in evaluating components proposed for nutrient- and fecal coliform

reducing performance-based treatment systems.

Equipment Series	Equipment	type of test	in TN (mg/L)	out TN (mg/L)	TN removal (%)	in TP (mg/L)	out TP (mg/L)	in fecal coliforms (CFU/100mL)	out fecal coliforms (CFU/100mL)	Vendor	Innovative Status*
CEN +Salcor 3G	Fuji Clean CEN 5 + +Salcor 3G	testing concurrent with NSF40 (for fecal coliform)	_	_	_	_	_	2.7E+4 to 6.3E+5 (30- day geomean)	70 geomean (6 to 183 30-day geomean)	Fuji Clean USA, LLC	Yes*
EcoPure	EcoPure 300	25 (9 for N) samples, one installation Lee County	56.13	31.16	44%	11.12	5.11	101586	80.6	Eco-Pure Wastewater Systems	Passed
Enviro- Guard	Enviro-Guard 0.75	NSF+Nitrogen with reduced sampling	46	20	57%	_	_	_	-	Consolidated Treatment Systems	n/a
		Keys Study, Phase I (12 samples)	38.45	10.97	71%	8.39	5.38	-	-		
MicroFAST	MicroFAST 0.5	Keys Study, Phase II (13- 14 samples)	47.98	11.51	76%	8.72	6.62	144,500 (mean log)	269 (mean log); 1,510 max	Bio-Microbics	n/a
		NSF 245 testing, Waco TX (September 2006 – April 2007)	38	17	55%						
	FAST	NSF40+Nitrogen	34.5	9.4	73%	-	-	-	-		
НООТ	HOOT H-500 AND	N-testing (25 samples) concurrent with NSF-40	26.3	9.63	63%	8.8	3.12			Hoot Aerobic Systems	n/a
Hydro-		NSF245, Norwalk OH (June 2011-December 2011)	36	8.7	76%					Norweco, Inc.	
Kinetic	FEU	NSF/ANSI Standard 40 12 months test						1.50E+06	2.5E+4		Yes*
Hydro- Kinetic+UV	Hydro-Kinetic 600 FEU w/ AT-1500 UV	Within 12 months of NSF-40	-	-	_			2.5E+4	0.096	Norweco, Inc.	Yes*
Nitrex	Nitrex (after LAI- specified	NSF-load, MASSTC 10/2001- 03/2004	19.3	5.4	Additional 72%					Lombardo Associates,	Yes*
THEOX	pretreatment)	NSF-load, MASSTC 12/2004- 10/2005	22.6	7.1	Additional 69%					Inc.	103
Cin av dain	Singulair 960 w/ Biokinetics phase 1 w/ recirc	16 N-tests at NSF-testing facility (Chelsea, MI)	25	6.8	73%	_	_	_	-		n/a
Singulair	Singulair 960 w/ Biokinetics phase 2 no recirc	8 N-tests at NSF-testing facility (Chelsea, MI)	25	11.8	53%	-	-	-	-	Norweco, Inc.	n/a
Septitech	Septitech Model 400	ETV (MA)	39	14	64%	-	-	-	-	BioMicrobics	Yes*
	24" unsaturated crushed brick ~1	Keys Study, Phase I (11				0.04	0.00				,
<u>-</u>	gpd/sqft 24" unsaturated crushed brick ~1.7	samples)	-	-	-	6.04	0.60	-	-	-	n/a
-	gpd/sqft	Keys Study, Phase II (n=13/4)	-	-	-	8.72	2.65	-	-	-	n/a
-	24" unsaturated LECA ~1 gpd/sqft	Keys Study, Phase I (11 samples)	-	-	-	6.04	1.31	-	-	-	n/a
-	24" unsaturated filterlite ~1.7 gpd/sqft	Keys Study, Phase II (n=13/10)	_	_	-	8.72	0.53	_	_	_	n/a

TN = Total Nitrogen; *Construction permits require filing of DH 3144 and DH3145 and must be reviewed by the Onsite Sewage Program office for compliance with the system's innovative system permit.

Table 3. Test Center Testing Results, which have been used in evaluating components proposed for performance-based treatment systems designed for drainfield size reductions.

a) Treatment systems certified to NSF/ANSI standard 40 and ATUs approved in Florida according to 64E-6.012, Florida Administrative Code							
,		in BOD5	out CBOD5	in TSS	out TSS		
Equipment Series	Model_tested	(mg/L)	(mg/L)	(mg/L)	(mg/L)	Manufacturer	
Advantex	AX20N Mode 1	162	5	291	4	Orenco Systems	
Aerocell	ATS SCAT-8-AC-C500	240	2	290	2	Quanics (Anua)	
Aero-Tech	AT-500	230	5	210	6	Aero-Tech	
Alliance	500	137	6	140	15	Acquired Wastewater Technologies, LLC	
Aqua Aire	500	170	2.7	184	3.9	Ecological Tanks, Inc.	
Aqua Safe	500	170	2.4	183	2.1	Ecological Tanks, Inc.	
AquaKlear	AK6PT	200	8	180	9	Aquaklear, Inc.	
AquaKlear	AK500C	150	10	130	11	Aquaklear, Inc.	
B.E.S.T. 1 AWS 1	500	130	21	139	21	American Wastewater Systems, Inc.	
BioBarrier	MBR-0.5	220	<2	220	<2	Bio-Microbics	
Bio-Coir	ATS-SCAT-8-BC-C500	160	9	190	12	Quanics (Anua)	
Bionest	BN-400	210	2	240	2	Bionest Technologies	
Cajun Aire Advanced	500	170	13	60	19	Acquired Wastewater Technologies, LLC	
Cajun Aire Basic	500	189	9.5	214	10.2	Acquired Wastewater Technologies, LLC	
Clearstream Model D	500 D	278	4	258	7	Clearstream Wastewater Systems, Inc.	
Clearstream Model DA	500 DA	278	4	258	7	Clearstream Wastewater Systems, Inc.	
Clearstream Model N	500 N	171	6	222	9	Clearstream Wastewater Systems, Inc.	
Delta DF	DF40-M	173	6	189	7	Delta Treatment Systems, LLC	
Delta EA	EA50	190	12	190	16	Delta Treatment Systems, LLC	
Delta UC	UC50	181	6	159	8	Delta Treatment Systems, LLC	
Delta ECOPOD-N	E50-N	210	9	170	8	Delta Treatment Systems, LLC	
Ecoflo Biofilter	STB-500	140	2	170	2	Premier Tech Environment	
Enviro-Guard	0.75	220	5	220	5	Consolidated Treatment Systems	
Fuji Clean CEN	CEN 5	190	5	300	6	Fuji Clean USA	
Fuji Clean CE	CE 5	150	11	260	13	Fuji Clean USA	
HOOT	H-500 A	196.1	2.3	194.3	1.8	Hoot Systems LLC	
HOOT	H-600 A	110	<5	107	3	Hoot Systems LLC	

Page 5/6; 5/31/2021

Table 3 (continued). Test Center Testing Results, which have been used in evaluating components proposed for performance-based

treatment systems designed for drainfield size reductions.

-	igned for draining 3/20 reddetic	in CBOD5	out CBOD5	in TSS	out TSS	
Equipment Series	Model_tested	(mg/L)	(mg/L)	(mg/L)	(mg/L)	Manufacturer
HOOT ANR	Hoot ANR-450	240	6	310	4	Hoot Systems LLC
Hydro-Action	AP500	177	9	201	15	Hydro-Action Industries
Jet	J-500 (Model J-353)	172	15	194	12	Jet Inc.
Jet CF	J-500CF	204	11	192	10	Jet Inc.
MicroFAST	0.5	250	3	310	1.4	Bio-Microbics, Inc.
Multi-Flo	FTB-0.5	170	5	195	5	Consolidated Treatment Systems
Nayadic	M-6A	150	6	184	7	Consolidated Treatment Systems
Puraflo P150N	Puraflo P150N*3B	240	2	260	2	Anua
PuraSys	PekaSys CRB1 (PuraSys PS1-4)	180	11	120	20	Anua
Singulair 960	500 w/ Biokinetics	184	6	238	10	Norweco, Inc.
Singulair TNT	500	240	4	260	9	Norweco, Inc.
b) Treatment systems that are not ATUs per 64E-6.012, Florida Administrative Code (generally, innovative systems)						
Advantav	AX20N Mode 3	120	10	172	10	Oranga Sylatoma
Advantex Nitrex	Nitrex (after pretreatment) (note: for systems designed to meet 10/10 standard, innovative permit requires polishing filter)	139	26	173	5	Orenco Systems Lombardo Associates, Inc.
Septitech	Model 400	250 (BOD5)	5.4	150	3	Septitech (BioMicrobics)

Notes: Influent and effluent concentrations are averages unless otherwise noted.

Table 4. Innovative Systems that are evaluated as drainfield/disposal systems (construction permits require filing of DH 3144 and DH3145 and must be reviewed by the Onsite Sewage Program office for compliance with the innovative system permit).

Manufacturer	Equipment Series
Eljen Corporation	Geotextile Sand Filter (GSF)
Geomatrix	GeoMat Leaching Systems
NoMound Onsite Systems	NoMound

Table 5. Other Innovative Systems (construction permits require filing of DH 3144 and DH3145 and must be reviewed by the Onsite Sewage Program office for compliance with the innovative system permit).

Manufacturer	Equipment Series
Environmental Conservation Solutions	Passive Onsite Treatment System (POTS)