



Florida Department of Environmental Protection

Update on DEP Septic Tank Research Activities

October 20, 2017






Info Covered

- Wekiva area homeowner's septic tank study
- Ichetucknee experimental drainfield
- Apopka experimental drainfield



Wekiva Study

-typical gravity system





Key Activities

- Homeowner septic tank study
 - Homeowner meeting (March 2015)
 - Screening and selection of 11 study sites (June 2015)
 - Site instrumentation (July-August 2015)
 - Monitoring period, bi-monthly sampling (September 2015-October 2016)



Wekiva Homeowner Study Objectives

The results of the study help us better understand:


- Attenuation and leaching of nitrogen from existing septic systems into the soil and potentially to ground water
- Other sources of nitrogen in residential areas
- Conditions that may influence nitrogen attenuation in the Wekiva area
- Influence of septic tank pumping on treatment



Information on Study Sites

Site ID	City	No. residents	Drainfield repair/replacement history	Maintenance info	Fertilizer use	Soil
A	Sorrento	2	infiltrators (original)	pumped regularly	yes, self applied	Candler fine sand
B	Apopka	3	infiltrators (2009)	pumped in 2013	yes, self applied	Candler fine sand
C	Apopka	3	infiltrators (2010)	septic tank pumped in 2013	yes, self applied	Candler fine sand
D	Apopka	2	pipe in gravel (original)	not pumped out lately	yes, commercial service	Candler fine sand
E	Apopka	2	pipe in gravel (1989)	not pumped	yard mostly mulched beds	Candler fine sand
F	Apopka	4	infiltrators (2010)	pumped in 2014	not lately	Candler fine sand
G	Apopka	3	pipe in gravel (original)	pumped in 2014	yard mostly mulched beds	Candler fine sand
H	Apopka	2	pipe in gravel (original)	not pumped	yes, commercial service	Candler fine sand
I	Longwood	1-2	infiltrators (1989)	pumped in 2015	yes, commercial service	Urban land
J	Longwood	2	mounded pipe in gravel bed	pumped regularly	yes, commercial service	Urban land
K	Apopka	2	pipe in gravel (original)	pumped in 2015	yard mostly mulched beds	Candler fine sand

11 Study Site Locations





Types of drainfields in study





Figure 4 - Schematic of a Sand Mound System



Scope

- Install and sample lysimeters to monitor soil pore water below drainfields and at background locations
- Install risers for septic tank effluent monitoring
- Install and sample monitoring wells at two locations
- Attempt to collect data on water use to estimate loading



Soil Pore Water Monitoring


Site	Lysimeters Installed	Total Depth (ft below land surface)	Location
A	AL1S-AL4S	5	Drainfield
	AL5S	5	Background
	AL2D	10	Drainfield adjacent to AL2S
B	BL1S-BL4S	5	Drainfield
	BL5S	5	Background
	BL3D	10	Drainfield, adjacent to BL3S
C	CL1S-CL3S	5	Drainfield
	CL4S	5	Background
	DL1S-DL2S	5	Drainfield
D	DL3S	5	Background
	EL1S-EL3S	5	Drainfield
	EL4S	5	Background
F	FL1S-FL3S	5	Drainfield
	FL4S	5	Background
	FL2D	10	Drainfield, adjacent to FL2S
G	GL1S-GL2S	5	Drainfield
	GL3S	5	Background
	GL1D	10	Drainfield, adjacent to GL1S
H	GL1E	15	Drainfield, adjacent to GL1S
	HL1S-HL2S	5	Drainfield
	HL3S	5	Background
I	IL1S-IL3S	5	Drainfield
	IL4S	5	Background
J	JL1S-JL3S	5	Drainfield
	JL4S	5	Background
K	KL1S-KL4S	5	Drainfield
	KL5S	5	Background



Lysimeter Installation



Wekiwa Spring






Septic Tank Effluent Sampling

Septic tank effluent samples collected bimonthly at 8 sites.
Results in mg/L.

Site	Average Total Nitrogen	Average Chloride	TN/Chloride Ratio	Average Total Phosphorus
A	61	32	1.91	7.8
B	93	43	2.16	9.3
C	101	63	1.60	12
E	57	47	1.21	6.8
F	57	45	1.27	6.8
G	75	42	1.79	7.5
I	140	87	1.61	16
J	93	74	1.26	9.3
All Sites	85	54	1.57	9.4




Sources: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Wekiva Septic Study Site: C

0 5 10 20 30
Feet

L = Lysimeter • = Septic Tanks
S = Shallow ● = Sampling Site
D = Deep MW = Monitoring Well
E = Very Deep ■ = Drainfield







Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community




Wekiva Septic Study Site: E



L = Lysimeter
S = Shallow
D = Deep
E = Very Deep
MW = Monitoring Well

Septic Tanks
Sampling Site
Drainfield







Source: Esri, DataSides, GeoEye, Bluebeam Geographics, CNES/Airbus DS,
USDA, USGS, AeroGRID, IGN, and the GIS User Community

**Wekiva Septic Study
Site: A**




0 5 10 20 30
Feet


Map prepared 4/1/2017 by the Division of Environmental Assessment
and Restoration. This map is not for legal decision making purposes.
For more information or copies, contact David.Huggins@dep.state.fl.us


L = Lysimeter
S = Shallow
D = Deep
E = Very Deep
MW = Monitoring Well

Septic Tanks
Sampling Site
Drainfield









Wekiva Septic Study Site: F


0 5 10 20 30 Feet


Map prepared 4/12/2017 by the Division of Environmental Assessment and Restoration. This map is not for legal decision making purposes. For more information or copies, contact David.Huggins@dep.state.fl.us

L = Lysimeter
S = Shallow
D = Deep
E = Very Deep
MW = Monitoring Well

Septic Tanks
Sampling Site
Drainfield









Summary Findings for Lysimeter Samples

Site	Max TN	Min TN	Avg TN	Max Chloride	Min Chloride	Avg Chloride	Max TP	Min TP	Avg TP
A	132	0.96	37	81	0.04	26	3.6	0.034	0.89
B	254	1.5	49	180	1.6	33	3.6	0.008	0.32
C	67	0.83	19	67	6.5	30	1.2	0.033	0.38
D	22	1.3	6.0	28	2.7	13	2.1	0.053	1.2
E	103	0.74	22	94	2.9	37	1.9	0.11	0.77
F	112	7	42	56	1.3	18	6.1	0.047	1.8
G	152	2.2	49	2600	5.8	234	7.9	0.04	1.8
H	10	1.5	6.3	92	1.9	24	0.12	0.021	0.07
I	69	0.6	8.5	120	3.9	21	2.3	0.048	0.80
J	56	0.56	4.0	96	2.2	24	0.12	0.015	0.038
K	192	0.43	31	260	1.3	55	8.2	0.32	3.0



Information about drainfield-related N attenuation

Results from some of the sites where TN was mostly from drainfields during some portion of the monitoring period are summarized below.

- At Site E, 39 % of nitrogen was reduced with 10% due to dilution.
- At Site G, 42 to 46 % of nitrogen was reduced in shallow and deep lysimeters with no dilution.
- At Site J where there is a shallow water table, 35 % of the nitrogen was reduced in a shallow well with no dilution.
- At Site K, 44 % of nitrogen was reduced with no dilution.

Using data from multiple sites, it appears that attenuation of N by means other than dilution is about 42 % (based on assumed TN/Cl relationship)



Soil Attenuation Modeling



SSSA Onsite
Wastewater Conference
April 7-8, 2014

The Florida Onsite Sewage
Nitrogen Reduction Strategies
(FOSNRS) Project

FOSNRS 6: STUMOD-FL - A Tool for Predicting Fate and Transport of Nitrogen in Soil Treatment Units in Florida

April 7, 2014

Mengistu Geza¹, Kathryn S Lowe¹, Cliff Tonsberg¹, John McCray¹ and Eberhard Roeder²



¹Civil and Environmental Engineering, Colorado School of Mines, Golden, CO

²Division of Disease Control and Health Protection Bureau of Environmental Health,
Florida Department of Health, Tallahassee, FL







STUMOD runs for study sites






STUMOD runs for study sites








Potential application of STUMOD on regional scale





Septic Tank Effluent and Influence of Pumping

- Midway through the study, 4 septic tanks were pumped. Others left as control.
- Septic tanks at sites A, B, E and G were pumped in March 2016, between February and April monitoring events






General statistics for all sites

Site	TN Before	TN After	% Chg	Chloride Before	Chloride After	% Chg	TP Before	TP After	% Chg
A ¹	55	65	+18	30	34	+13	6	9	+5
B ¹	97	90	-7	43	42	-2	9	9	0
C	101	100	-1	63	60	-5	12	11	-8
E ¹	45	65	+44	46	48	+4	5	8	+60
F	56	65	+18	45	48	+7	6	8	+33
G ¹	79	73	-8	43	42	-2	8	7	-13
I	128	149	+16	83	90	+8	15	17	+13
J	77	106	+38	71	76	+7	5	12	+140

Notes: 1- septic tank pumped in March 2016. Other sites are controls.



TN Trends after pumping





Ichetucknee Drainfield Study

- Intentionally low-tech, low cost design (added approximately \$300 to the cost of a new drainfield)
- Ichetucknee Springs State Park manager's house
- With DOH construction and operating permits, and under a Memorandum of Understanding
- Installed a second drainfield underlain by wood chips
- Installed monitoring system and monitored
- Put in the ground in March 2014 and septic tank effluent diverted to new system



Figure 1. View East: First phase of lignocellulosic layer installation. ~11:20 am




Figure 6. Installation of deep lysimeters (buckets contain silica mix). ~1:55 pm



Figure 10. Installation of three rows of chambers at a slight angle to the length axis of the mulch bed. ~4:36 pm



Soil pore water sampling using lysimeters










Monitoring includes

- Pore water from lysimeters set above and below the mulch layer
- Shallow ground water from beneath the drainfield
- Septic tank effluent
- Water level in a shallow piezometer to measure mounding




Plan view






Cross section






Shallow Lysimeter Data

Shallow Lysimeters - Chloride mg/L




Shallow Lysimeters - Total Nitrogen mg/L






Deep lysimeter data

Deep Lysimeters - Chloride mg/L



Deep Lysimeters - Total Nitrogen mg/L





Groundwater monitoring

- Water table at about 20-24 ft below land surface
- Two wells installed between infiltrator rows
- Beneath active drainfield nitrate ranged from 18 to 26 mg/L over the past year, increasing from original background concentration of 3.3 mg/L



Evaluating subsidence




Figure 13. Land Surface Elevation (LSE) Survey of Drainfield July 2017



Evaluating mulch condition



Figure 15. Photographs of mulch from March 2014 (at installation), January 2015 and July 2017.




Apopka Lined Drainfield Site

- Experimental drainfield
 - Passive drainfield with mulch on liner
 - Recycled wood mulch
 - No pump
 - Installed August 2016
 - Monthly monitoring for 1 year followed by quarterly monitoring






Wood mulch and liner extend
3-5' beyond edge of drainfield





LEGEND

- ▲ shallow suction lysimeter
- ▲ deep suction lysimeter
- - - horizontal well point
- riser for effluent monitoring
- ⊕ monitoring well
- ◆ piezometer















Shallow Lysimeter Results for First Year




Figure 4. Shallow Lysimeters - Chloride mg/L






Figure 5. Shallow Lysimeters - Total Nitrogen mg/L



Horizontal Well Results for First Year





Deep Lysimeter Results for First Year




Figure 10. Deep Lysimeters - Chloride mg/L




Figure 11. Deep Lysimeters - Total Nitrogen mg/L



Groundwater Monitoring

- One well adjacent to active end of drainfield
- Nitrate increased from 3.5 mg/L pre-installation to 6.0 mg/L one year later
- Depth to groundwater about 30 feet below land surface



Questions?

