



**STATUS REPORT ON PHASE II AND PHASE III OF THE
FLORIDA ONSITE SEWAGE NITROGEN REDUCTION
STRATEGIES STUDY**

Bureau of Onsite Sewage Programs

May 16, 2012

Steven L. Harris, M.D., M.Sc.
Interim State Surgeon General

Rick Scott
Governor

Table of Contents

EXECUTIVE SUMMARY 3
1 INTRODUCTION..... 4
2 PROJECT STATUS 6
3 ANTICIPATED PROGRESS IN 2012-2014 9
4 FUNDING NEEDS 10
5 RECOMMENDATIONS..... 12
APPENDIX A. 2010 Legislative Language 13
APPENDIX B. 2011 Legislative Language 17
APPENDIX C. 2012 Legislative Language 20

List of Figures

Figure 1. Sign posted at the University of Florida’s Gulf Coast Research & Education Center’s test facility. 6
Figure 2. Test facility constructed at the University of Florida’s Gulf Coast Research & Education Center. 7

List of Tables

Table 1. Summary of Legislative Funding..... 4
Table 2. Field Work Status by County for Task B and Task C..... 8
Table 3. Summary of Funding Phase Tasks and Progress 11

STATUS REPORT ON PHASE II AND PHASE III OF THE FLORIDA ONSITE SEWAGE NITROGEN REDUCTION STRATEGIES STUDY – MAY 2012

EXECUTIVE SUMMARY

This report is submitted in compliance with Line Item 465 Section 3, Conference Report on Senate Bill 2000, General Appropriations Act for Fiscal Year 2011-2012. The Florida Legislature has provided a total of \$4.4 million (cash) for Phases I, II, and the first part of Phase III of a three phase project with a total estimated cost of \$5.1 million. This project is to develop cost-effective, passive strategies for nitrogen reduction for onsite sewage treatment and disposal systems (OSTDS). This project will require additional cash and budget authority in the amount of \$700,000 to complete the study.

This project is in its third of five years and is on schedule and within budget. Funds appropriated and expended to date have established necessary viable protocols and have been appropriately used to test, calibrate, and refine technologies and strategies to be tested in the field. Continued funding for the final Phase III of the project is necessary for extensive field testing to occur. Field testing is crucial, so that the project will yield results that can be used to develop viable, cost-effective alternative passive technologies for use by homeowners for nitrogen issues associated with onsite systems.

Regardless of the source, excessive nitrogen has negative effects on public health and the environment. This project has been endorsed by Florida TaxWatch as a good use of public funds (Wenner 2008). The Department's Research Review and Advisory Committee (RRAC) supports concluding this study as originally scoped. The tasks associated with the final phase include: continuation and completion of field monitoring of the performance and cost of technologies at home sites and of nitrogen fate and transport in the shallow groundwater; development of nitrogen fate and transport models that will be calibrated with the field sampling results; and final reporting on all tasks with recommendations on onsite sewage nitrogen reduction strategies.

During the 2012-2013 fiscal year efforts will be focused on installing, monitoring, and modeling various field sites at locations throughout the State of Florida to evaluate nitrogen reducing technologies and to gather information on how nitrogen moves through the soil and shallow groundwater. The final phase of funding, which will be required for the 2013-2014 fiscal year, will include completion of remaining field monitoring; completion of nitrogen fate and transport models that will be calibrated with the field sampling results; and final reporting on all tasks with recommendations on onsite sewage nitrogen reduction strategies.

The Research Review and Advisory Committee recommends that the Legislature:

1. During the 2013 legislative session, provide additional cash in the amount of \$700,000 for continuation and completion of the tasks associated with this legislatively mandated study.
2. Provide budget authority to DOH in the amount of \$700,000 for the fiscal year 2013-2014 for completion of the tasks associated with this legislatively mandated study.

Continued support for this project will ultimately benefit Florida's approximately 2.7 million onsite system owners by finding cost-effective nitrogen reduction strategies that will improve environmental and public health protection. When fully funded, the results of this project will assist with producing nitrogen reducing systems that protect groundwater through reduced life-cycle costs and lower energy demands.

1 INTRODUCTION

The Florida Legislature has provided a total of \$4.4 million (cash) for Phases I, II, and the first part of Phase III of a three phase project with a total estimated cost of \$5.1 million (Table 1). This project is to develop passive strategies for nitrogen reduction for onsite sewage treatment and disposal systems (OSTDS). This includes an initial appropriation of \$900,000 by the 2008 Legislature for the first phase of this study and an appropriation of \$2,000,000 by the 2010 Legislature for the second phase of this study, and an appropriation of \$1,500,000 by the 2012 Legislature for the first part of the third phase of this study. This project will require additional cash and budget authority in the amount of \$700,000 to complete the study. This report is submitted in compliance with Line Item 465 Section 3, Conference Report on Senate Bill 2000, General Appropriations Act for Fiscal Year 2011-2012, which appropriated the funding for the study.

Table 1. Summary of Legislative Funding

Total Project Budget	\$5,100,000
Total Funding To Date	(\$4,400,000)
Balance to Complete (2013-2014 Fiscal Year Projected Funding Need)	\$700,000

This study was based on budget language in 2008 (Line Item 1682, House Bill 5001, General Appropriations Act for Fiscal Year 2008-2009) that instructed:

...the Department of Health to further develop cost-effective nitrogen reduction strategies. The Department of Health shall contract, by request for proposal, for Phase I of an anticipated 3-year project to develop passive strategies for nitrogen reduction that complement use of conventional onsite wastewater treatment systems. The project shall be controlled by the Department of Health's Research Review and Advisory Committee and shall include the following components: 1) comprehensive review of existing or ongoing studies on passive technologies; 2) field testing of nitrogen reducing technologies at actual home sites for comparison of conventional, passive technologies and performance-based treatment systems to determine nitrogen reduction performance; 3) documentation of all capital, energy and life-cycle costs of various technologies for nitrogen reduction; 4) evaluation of nitrogen reduction provided by soils and the shallow groundwater below and down gradient of various systems; and 5) development of a simple model for predicting nitrogen fate and transport from onsite wastewater systems. A progress report shall be presented to the Executive Office of the Governor, the President of the Senate and the Speaker of the House of Representatives on February 1, 2009, including recommendations for funding additional phases of the study.

The 2010 legislative direction (included in Appendix A) specified that the existing contract for this project will remain in full force; that the Department, the Department's Research Review and Advisory Committee (RRAC), and the Florida Department of Environmental Protection (DEP) shall work together to provide technical oversight; that DEP will have maximum technical input; that the main focus and priority for work in Phase II shall be in developing, testing, and recommending cost-effective passive technologies for nitrogen reduction; that field installations for this project will be subject to significant testing and monitoring; and that no state agency shall implement any rule or policy that requires nitrogen reducing systems or increases their costs until the study is complete.

The 2011 and 2012 legislative direction (included in Appendix B and Appendix C respectively) specified that the existing contract for this project will remain in full force; that the Department, the Department's Research Review and Advisory Committee (RRAC), and the Florida Department of Environmental Protection (DEP) shall work together to provide technical oversight; that completion of Phase II and Phase III must be consistent with the terms of the existing contract; that the main focus and priority for Phase III be developing, testing, and recommending cost-effective passive technology design criteria for nitrogen reduction; the installed systems are experimental in nature and shall be installed with significant field testing and monitoring; and that no state agency shall implement any rule or policy that requires nitrogen reducing systems or increases their costs until the study is complete.

Regardless of the source, excessive nitrogen has negative effects on public health and the environment. The primary motivations for this study are the environmental impacts that the increased levels of nitrogen in water bodies can cause. Programs within DEP identify water bodies impaired by excessive nitrogen, establish targets for maximum nutrient loads, and develop management action plans to restore the water bodies. The relative impact of OSTDS on total nitrogen levels varies from watershed to watershed with estimates ranging from below five to more than 20 percent. There is widespread interest in the management of OSTDS and their nitrogen impacts. This project has been endorsed by Florida TaxWatch as a study that is a good use of public funds and that provides homeowners with cost-effective options for nitrogen reduction (email communication from Kurt Wenner to Jerry McDaniel June 2, 2008). The significance of this innovative project is that it evaluates and develops strategies to reduce nitrogen impacts from OSTDS regulated by the Florida Department of Health (DOH). The goal is to develop systems that complement the use of conventional OSTDS and are also affordable and ecologically protective with reduced engineering and installation costs that assist in sustainable development.

The study contract was awarded in January 2009 to a Project Team led by Hazen and Sawyer, P.C., and was based upon an anticipated budget of \$5 million over a 3 – 5 year project timeframe, with an additional \$100,000 budget to DOH for project management. As a result of the time required for contracting, unspent monies in fiscal year 2008-2009 were budgeted in 2009 to complete the initial tasks of the project. The contract identifies the following tasks:

Task A – Technology Evaluation for Field Testing: Review, Prioritization, and Development: This task includes literature review, technology evaluation, prioritization of technologies to be examined during field testing, and further experimentation with approaches tested in a previous DOH passive nitrogen removal study. Objectives of this task are to prioritize technologies for testing at actual home sites and to perform controlled tests at a test facility to develop design criteria for new passive nitrogen reduction systems.

Task B – Field Testing of Technologies and Cost Documentation: This task includes installation of top-ranked nitrogen reduction technologies at actual homes, with documentation of their performance and cost. Cost documentation for the systems will be broken down by permitting, design, materials and construction, and operation and maintenance.

Task C – Evaluation of Nitrogen Reduction Provided by Soils and Shallow Groundwater: This task includes several field evaluations of nitrogen reduction in Florida soils and shallow groundwater and also will provide data for the development of a simple planning model in Task D.

Task D – Nitrogen Fate and Transport Modeling: The objective of this task is to develop a simple fate and transport model of nitrogen from OSTDS that can be used for assessment, planning and siting of OSTDS.




Figure 1. Sign posted at the University of Florida’s Gulf Coast Research & Education Center’s test facility.

2 PROJECT STATUS

Funding for the first and second phases of this project has been appropriated. The 2012 Florida Legislature has approved funding for the first part of Phase III. A summary of the major project elements and their timing with funding phases is shown in Table 1. The contractor, in coordination with the RRAC and DOH, has successfully completed parts of Tasks A, B, C, and D, including literature reviews; ranking of nitrogen reduction technologies for field testing; design and construction of a test facility for further development of passive technologies; development of quality assurance documents for the test facility work, groundwater monitoring, field testing, and nitrogen fate and transport modeling; installation of a nitrogen reducing system at a home site; completion of several sampling events of passive systems at the test facility and field sites; design and construction of a soil and groundwater test facility; and field sampling of the soil and groundwater under OSTDS at residential homes throughout Florida and at the test facility.



Figure 2. Test facility constructed at the University of Florida's Gulf Coast Research & Education Center.

Current efforts and work remaining for the 2011-2012 fiscal year includes: installation and field sampling of additional field sites at residential homes throughout Florida for the testing of passive systems and to test the soil and groundwater under OSTDS; sampling at the soil and groundwater test facility; and initiating development of a nitrogen fate and transport model. RRAC supports concluding this study as originally scoped. The following work by task will proceed with the current funding level:

1. Task A. The technology evaluation included a total of 7 sample events at the passive nitrogen test facility, measuring 14 different analytes at over 40 sampling points in 11 systems, as well as a final report on the pilot passive nitrogen removal study at the Gulf Coast Research and Education Center (GCREC).
Current Status as of March 2012: All sample events at the test facility have been completed. Test results are encouraging after 12 months of testing, showing a reduction in total nitrogen of over 95%, with a final effluent concentration of 2.6 mg/L or less for several of the systems.
2. Task B. For field testing of technologies, the quality assurance project plan has been finalized. The research design proposes that seven onsite systems, utilizing various nitrogen removal technologies, will be installed at home locations throughout the State of Florida. It is anticipated that a total of seven field system performance monitoring events will be conducted on each these systems with the current funding level, measuring 16 different analytes at 2-8 different sampling points. A life cycle cost assessment template will also be completed.
Current Status as of March 2012: Eleven homeowners residing at locations across Florida have agreed to participate in the study to date for Task B (Table 2). Home sites have been identified in Wakulla County, the Wekiva area, and several other areas throughout the State. At least one of the home sites will have a gravity-fed system installed. Construction has been completed for one system and sampling has begun. A second system is currently in the design and permitting phase.

3. Task C. To evaluate nitrogen reduction provided by soils and shallow groundwater, a soil and groundwater test facility has been constructed to show how groundwater fate and transport of nitrogen occurs in multiple soil treatment unit regimes. Six sampling events will be completed with the current funding level, sampling six different locations at each site, and measuring multiple parameters in the effluent, soil, and groundwater. The existing OSTDS mound system at the University of Florida's Gulf Coast Research & Education Center (GCREC) in Wimauma, Florida will be instrumented to study how nitrogen behaves in the soil and groundwater. Four sampling events that examine multiple parameters have been completed at the existing OSTDS mound system at GCREC. At least three soil and groundwater monitoring events will occur at up to three home sites to evaluate nitrogen movement in the soil and groundwater in the field, measuring multiple parameters in the effluent, soil, and groundwater.

Current Status as of March 2012: Tasks that have been completed thus far are the testing of media components per 381.0065(4)(m) F.S., one tracer test to determine existing groundwater flow characteristics, and construction of the soil and groundwater test facility. Instrumentation of the existing OSTDS mound system at GCREC has been completed and four sample events have been conducted. Six homeowners have agreed to participate in the study to date for Task C (Table 2). Three home sites have been selected and two have been instrumented. One sample event has occurred at the first of these sites, however, the groundwater flow direction could not be delineated, and no additional sampling events will occur at that site. Three sample events have occurred at the second instrumented site, and the third site is being instrumented for monitoring. Monitoring will be conducted at four groundwater test areas at the soil and groundwater test facility to show how groundwater fate and transport of nitrogen occurs.

Table 2. Field Work Status by County for Task B and Task C

County	# Sites Evaluated	# Agreements	Sites in Progress
Charlotte	12	0	0
Hernando	1	0	0
Hillsborough	4	3	2
Lake	1	0	0
Lee	4	1	1
Marion	8	3	0
Orange	2	0	0
Polk	3	1	1
Sarasota	13	0	1
Seminole	8	6	3
Wakulla	4	4	2
TOTAL	60	18	10

4. Task D. To address nitrogen fate and transport modeling for, a final quality assurance project plan has been completed, and the first steps will include the development of a soil model to show how nitrogen is affected by treatment in Florida-specific soils.

Current Status as of March 2012: Work has focused primarily on soil modeling under the current budget. Development of a soil model is underway and will be utilized to generate a simple tool for prediction of nitrogen removal in the unsaturated zone of Florida soils.

3 ANTICIPATED PROGRESS IN 2012-2014

During the 2012-2013 fiscal year, the following progress is anticipated:

1. For Task A, analysis of the results from the passive nitrogen test facility research is underway.
2. For Task B, it is anticipated that four field sites will be installed, bringing the total installations to seven; at least four field system performance monitoring events will be conducted on each of the seven systems; a report providing a technical description of nitrogen reduction technologies will be written, as well as a report providing a template and user guidelines for system life cycle cost assessments.
3. For Task C, three final monitoring events at the soil and groundwater test facility will be conducted, and monitoring events at three home sites will be performed to evaluate nitrogen movement in the soil and groundwater in the field.
4. For Task D, soil models demonstrating performance evaluation will be developed and refined, as well as development of model demonstrating nitrogen movement in the shallow groundwater and soil.

During the 2013-2014 fiscal year, additional funding will be critical to complete the tasks associated with the final phase. These include: continuation and completion of field monitoring of performance and cost of technologies at home sites and of nitrogen fate and transport in the shallow groundwater; calibration and refinement of various nitrogen fate and transport models that will be calibrated with the field sampling results; and final reporting on all tasks with recommendations on onsite sewage nitrogen reduction strategies. In particular, the following work will occur with the final phase of funding being requested with this report:

1. For Task A, the final task report will be written. This report will include a summary of the accomplishments of the passive nitrogen removal test facility.
2. For Task B, it is anticipated that one final field system performance monitoring event will be conducted on each of the seven systems; and completion of final reporting on all of the field work associated with this task. Cost documentation for the systems will be broken down by permitting, design, materials and construction, and operation and maintenance.
3. For Task C, monitoring events at three home sites will be conducted to evaluate nitrogen movement in the soil and groundwater in the field. Final reporting for this task will be completed.
4. For Task D, the soil model will be completed and integrated with groundwater models which will be calibrated, and validated, utilizing the results of the field work collected in previous tasks, and a final task report will be written summarizing the results of this task.

4 FUNDING NEEDS

Activities in fiscal years 2008-2012 have prepared the framework for rapid implementation of all remaining project tasks in fiscal years 2013-2014. Cash and budget authorization in the amount of \$700,000 is required to reap the benefits of all previous work and to complete the goals of this project.

This project is in its third of five years and is on schedule and within budget. Funds appropriated and expended to date have established necessary viable protocols and have been appropriately used to test, calibrate, and refine technologies and strategies to be tested in the field. Continued funding for Phase III of the project is necessary for extensive field testing (the major portion of Task B) to be completed. Field testing is crucial, so that the project will yield results that can be used to develop viable, cost-effective alternative passive technologies for use by homeowners for nitrogen issues associated with onsite systems.

Project Tasks (described previously) are broken down further into funding phases as follows:

Initial Funding in 2008-2010 (Phase I): \$900,000 (cash and budget authority) appropriated (in 2008 and 2009 state budgets) – Status: Complete. The initial funding was targeted to prioritize systems for testing, summarize existing knowledge, develop testing protocols, and establish a test facility for detailed soil and groundwater monitoring and for preliminary testing of pilot scale passive nitrogen reduction systems.

Funding in 2010-2011: \$2 million (cash and budget authority) appropriated (in 2010 state budget) – Status: Ongoing. This funding is for field monitoring over at least a one-year monitoring period of performance and cost of technologies at home sites, and of nitrogen fate and transport. This funding will also continue the development and monitoring work at the test facility and continue the modeling work.

Funding in 2011-2012: Although \$2.75 million in budget authorization was appropriated in the 2011 state budget, no additional cash accompanied the budget authorization – Status: Ongoing. The remaining cash from the 2010-2011 appropriation is being used to continue the monitoring of systems and the soil modeling work. The preliminary results of the project are encouraging.

Funding in 2012-2013: \$1.5 million (cash and budget authority) appropriated (in 2012 state budget) – Status: Funding will not be released until the 2012-2013 fiscal year has begun. These funds will be used to continue to install and monitor nitrogen reducing systems, draft a life cycle cost assessment template report for systems evaluated in this study, monitor nitrogen in the groundwater under existing OSTDS, and to develop, validate, and refine the soil modeling work.

Funding in 2013-2014: To adequately fund the final phase of the project, \$700,000 cash is required to fund the completion of scheduled tasks. Further testing and analysis is required to confirm the results to date with field data and to provide data for development of the engineering specifications for full system designs. The funds will be used to complete monitoring and other field activities, perform additional testing as deemed appropriate by the Legislature, and for final reporting with recommendations on onsite sewage nitrogen reduction strategies for Florida's future.

Further information on this project, including previous legislative reports and detailed project reports, can be found on the Department's website:

<http://www.doh.state.fl.us/environment/ostds/research/Nitrogen.html>

Table 3. Summary of Funding Phase Tasks and Progress

Task	Status	Phase I	Phase II	Phase IIIa	Phase IIIb
A Task A: Technology Selection & Prioritization		\$352,144	\$336,514	\$0	\$35,480
Literature review	Complete				
Ranking of nitrogen reduction technologies for field testing	Complete				
Design and construction of test facility	Complete				
Quality assurance project plan	Complete				
Monitoring and sample events (7 events)	Complete				
Final test facility report	Underway				
Final task report	Funding required ¹				
B Task B: Field Testing of Technologies		\$50,202	\$599,610	\$265,408	\$263,834
Quality assurance project plan	Complete				
Installation of ranked nitrogen reduction technologies at 7 field sites	Underway				
System performance monitoring events at 7 sites	Underway				
Life cycle cost assessment template development	Not started				
Final life cycle cost assessment report (per system)	Funding required ¹				
Final task report	Funding required ¹				
C Task C: Evaluation of Nitrogen Reduction by Soils & Shallow Groundwater		\$216,164	\$1,095,977	\$436,220	\$162,640
Quality assurance project plan	Complete				
Design of test facility	Complete				
Construction of test facility	Complete				
Test facility monitoring and sample events (4 test areas sampled 6 times)	Not started, partially funded ²				
Instrumentation of existing OSTDS mound at GCREC facility	Complete				
GCREC mound sample events	Complete				
Field sites sample events (4 sites, 3 sites will be sampled 3 times, 1 site discontinued)	Underway, partially funded ²				
Final task report	Funding required ¹				
D Task D: Nitrogen Fate and Transport Models		\$74,357	\$292,021	\$251,334	\$190,310
Quality assurance project plan	Complete				
Soil model development(simple and complex)	Underway				
Performance evaluation and refinement of soil models	Not started				
Shallow groundwater/soil model development	Funding required ¹				
Performance evaluation and refinement of soil/groundwater model	Funding required ¹				
Decision making framework	Funding required ¹				
Final task report	Funding required ¹				
Project Management (sum of contractor and Department of Health)		\$119,953	\$149,003	\$105,407	\$103,422
Contractor project management	Underway	\$90,695	\$109,003	\$90,407	\$87,679
Department of Health project management	Underway	\$29,258	\$40,000	\$15,000	\$15,743
Total Project Budget		\$812,820	\$2,473,125	\$1,058,369	\$755,686
Total Spent as of March 18, 2012		\$812,820	\$1,109,427	\$0	\$0
Balance		\$0	\$1,363,698	\$0	\$0

1 A "funding required" subtask status indicates that the \$700,000 requested for fiscal year 2013-2014 is required to fund the subtask

2 A "partially funded" subtask status indicates that a subtask has received partial funding, but still requires a portion of the \$700,000 required to complete the funding for the project

GCREC – Gulf Coast Research & Education Center

OSTDS – Onsite Sewage Treatment and Disposal Systems

5 RECOMMENDATIONS

The Research Review and Advisory Committee recommends that the 2013 Legislature:

1. Provide additional cash in the amount of \$700,000 for continuation and completion of the tasks associated with this legislatively mandated study.
2. Provide budget authority to DOH in the amount of \$700,000 for the fiscal year 2013-2014 for completion of the tasks associated with this legislatively mandated study.

This final funding will be applied to the final phase of the project, primarily continuation and completion of field monitoring of performance and cost of technologies at home sites and of nitrogen fate and transport in the shallow groundwater, calibration and refinement of various nitrogen fate and transport models that will be calibrated with the field sampling results, and final reporting on all tasks with recommendations on onsite sewage nitrogen reduction strategies.

Continued support for this project will ultimately benefit Florida's approximately 2.7 million onsite system owners by finding cost-effective nitrogen reduction strategies that will improve environmental and public health protection. When fully funded, the results of this project will assist with producing nitrogen reducing systems that protect groundwater through reduced life-cycle costs and lower energy demands.

APPENDIX A. 2010 Legislative Language

SECTION 3 – HUMAN SERVICES

486 SPECIAL CATEGORIES

CONTRACTED SERVICES

FROM GENERAL REVENUE FUND	153,772
FROM ADMINISTRATIVE TRUST FUND . . .	337,765
FROM FEDERAL GRANTS TRUST FUND . . .	348,235
FROM GRANTS AND DONATIONS TRUST FUND	2,648,438
FROM RADIATION PROTECTION TRUST FUND	150,000

From the funds in Specific Appropriation 486, \$2,000,000 from the Grants and Donations Trust Fund is provided to the department to continue phase II and complete the study authorized in Specific Appropriation 1682 of chapter 2008-152, Laws of Florida. The report shall include recommendations on passive strategies for nitrogen reduction that complement use of conventional onsite wastewater treatment systems. The department shall submit an interim report of phase II on February 1, 2011, a subsequent status report on May 16, 2011, and a final report upon completion of phase II to the Governor, the President of the Senate, and the Speaker of the House of Representatives prior to proceeding with any nitrogen reduction activities.

Section 14. In order to implement Specific Appropriation 486 of the 2010-2011 General Appropriations Act, and for the 2010-2011 fiscal year only, the following requirements shall govern Phase 2 of the Department of Health's Florida Onsite Sewage Nitrogen Reduction Strategies Study:

(1) The underlying contract for which the study was let shall remain in full force and effect with the Department of Health and funding the contract for Phase 2 of the study shall be through the Department of Health.

(2) The Department of Health, the Department of Health's Research Review and Advisory Committee, and the Department of Environmental Protection shall work together to provide the necessary technical oversight of Phase 2 of the project, with the Department of Environmental Protection having maximum technical input.

(3) Management and oversight of Phase 2 shall be consistent with the terms of the existing contract; however, the main focus and priority for work to be completed for Phase 2 shall be in developing, testing, and recommending cost-effective passive technology design criteria for nitrogen reduction.

(4) The systems installed at actual home sites are experimental in nature and shall be installed with significant field testing and monitoring. The Department of Health is specifically authorized to allow installation of these experimental systems. In addition, before Phase 2 of the study is complete and notwithstanding any law to the contrary, a state agency may not adopt or implement a rule or policy that:

(a) Mandates, establishes, or implements any new nitrogen-reduction standards that apply to existing or new onsite sewage treatment systems or modification of such systems;

(b) Increases the cost of treatment for nitrogen reduction from onsite sewage treatment systems; or

(c) Directly requires or has the indirect effect of requiring, for nitrogen reduction, the use of performance-based treatment systems or any similar technology; provided the Department of Environmental Protection administrative orders recognizing onsite system modifications, developed

through a basin management action plan adopted pursuant to section 403.067, Florida Statutes, are not subject to the above restrictions where implementation of onsite system modifications are phased in after completion of Phase 2, except that no onsite system modification developed in a basin management action plan shall directly or indirectly require the installation of performance-based treatment systems.

APPENDIX B. 2011 Legislative Language

SECTION 3 – HUMAN SERVICES

465 SPECIAL CATEGORIES

CONTRACTED SERVICES

FROM GENERAL REVENUE FUND	97,489
FROM ADMINISTRATIVE TRUST FUND . . .	335,165
FROM FEDERAL GRANTS TRUST FUND . . .	643,776
FROM GRANTS AND DONATIONS TRUST FUND	3,401,038
FROM RADIATION PROTECTION TRUST FUND	150,000

From the funds in Specific Appropriation 465, \$2,725,000 in nonrecurring funds from the Grants and Donations Trust Fund is provided to the department to complete phase II and phase III and complete the study authorized in Specific Appropriation 1682 of chapter 2008-152, Laws of Florida. The report shall include recommendations on passive strategies for nitrogen reduction that complement use of conventional onsite wastewater treatment systems. The department shall submit an interim report of the completion of phase II and progress on phase III on February 1, 2012, a subsequent status report on May 16, 2012, and a final report upon completion of phase III to the Governor, the President of the Senate, and the Speaker of the House of Representatives prior to proceeding with any nitrogen reduction activities.

Section 7. In order to implement Specific Appropriation 465 of the 2011-2012 General Appropriations Act, and for the 2011-2012 fiscal year only, the following requirements govern the completion of Phase 2 and Phase 3 of the Department of Health's Florida Onsite Sewage Nitrogen Reduction Strategies Study:

(1) The Department of Health's underlying contract for the study remains in full force and effect and funding for completion of Phase 2 and Phase 3 is through the Department of Health.

(2) The Department of Health, the Department of Health's Research Review and Advisory Committee, and the Department of Environmental Protection shall work together to provide the necessary technical oversight of the completion of Phase 2 and Phase 3 of the project.

(3) Management and oversight of the completion of Phase 2 and Phase 3 must be consistent with the terms of the existing contract. However, the main focus and priority to be completed during Phase 3 shall be developing, testing, and recommending cost-effective passive technology design criteria for nitrogen reduction.

(4) The systems installed at homesites are experimental in nature and shall be installed with significant field testing and monitoring. The Department of Health is specifically authorized to allow installation of these experimental systems. Notwithstanding any other law, before Phase 3 of the study is completed, a state agency may not adopt or implement a rule or policy that:

(a) Mandates, establishes, or implements more restrictive nitrogen-reduction standards to existing or new onsite sewage treatment systems or modification of such systems; or

(b) Directly or indirectly requires the use of performance-based treatment systems or similar technology, such as through an administrative order developed by the Department of Environmental Protection as part of a basin management action plan adopted pursuant to s. 403.067, Florida Statutes. However, the implementation of more restrictive nitrogen-reduction standards for onsite systems may be required through a basin management action plan if such plan is phased in after completion of Phase 3.

APPENDIX C. 2012 Legislative Language

SECTION 3 – HUMAN SERVICES

512 SPECIAL CATEGORIES

CONTRACTED SERVICES

FROM GENERAL REVENUE FUND	2,047,489
FROM ADMINISTRATIVE TRUST FUND	335,165
FROM FEDERAL GRANTS TRUST FUND	643,776
FROM GRANTS AND DONATIONS TRUST FUND	676,038
FROM RADIATION PROTECTION TRUST FUND	150,000

From the funds in Specific Appropriation 512, \$1,500,000 in nonrecurring funds from the General Revenue Fund is provided to the department to complete phase II and phase III of the study authorized in Specific Appropriation 1682 of chapter 2008-152, Laws of Florida. The funds will be spent for installing field systems and sampling, installing and sampling the soil and groundwater at various sites throughout Florida to determine how nitrogen moves, and developing various models to show how nitrogen is affected by treatment in Florida-specific soils. The department shall submit a status report before October 1, 2012, a subsequent status report before February 1, 2013, and a final report upon completion of phase III to the Governor, the President of the Senate, and the Speaker of the House of Representatives prior to proceeding with any nitrogen reduction activities.

Section 5. (1) In order to implement Specific Appropriation 512 of the 2012-2013 General Appropriations Act, and for the 2012-2013 fiscal year only, the following requirements govern the completion of Phase 2 and Phase 3 of the Department of Health's Florida Onsite Sewage Nitrogen Reduction Strategies Study:

(a) The Department of Health's underlying contract for the study remains in full force and effect and funding for completion of Phase 2 and Phase 3 is through the Department of Health.

(b) The Department of Health, the Department of Health's Research Review and Advisory Committee, and the Department of Environmental Protection shall work together to provide the necessary technical oversight of the completion of Phase 2 and Phase 3 of the project.

(c) Management and oversight of the completion of Phase 2 and Phase 3 must be consistent with the terms of the existing contract. However, the main focus and priority to be completed during Phase 3 shall be developing, testing, and recommending cost-effective passive technology design criteria for nitrogen reduction.

(d) The systems installed at homesites are experimental in nature and shall be installed with significant field testing and monitoring. The Department of Health is specifically authorized to allow installation of these experimental systems. Notwithstanding any other law, before Phase 3 of the study is completed, a state agency may not adopt or implement a rule or policy that:

1. Mandates, establishes, or implements more restrictive nitrogen-reduction standards to existing or new onsite sewage treatment systems or modification of such systems; or

2. Directly or indirectly requires the use of performance-based treatment systems or similar technology, such as through an administrative order developed by the Department of Environmental Protection as part of a basin management action plan adopted pursuant to s. 403.067, Florida Statutes.

However, the implementation of more restrictive nitrogen-reduction standards for onsite systems may be required through a basin management action plan if such plan is phased in after completion of Phase 3.

(2) This section expires July 1, 2013.