



# Florida Onsite Sewage Nitrogen Reduction Strategies Study

## Evaluation of Full Scale Prototype Passive Nitrogen Reduction Systems (PNRS) and Recommendations for Future Implementation - Volume I of II

August 2015

Volume I – Report  
Volume II - Appendices

412-571-001

**HAZEN AND SAWYER**  
Environmental Engineers & Scientists

In association with:



**AET**  
Advanced Environmental Technology

**Otis Environmental  
Consultants, LLC**

# **Florida Onsite Sewage Nitrogen Reduction Strategies Study**

## **TASK B FINAL REPORT**

### **Evaluation of Full Scale Prototype Passive Nitrogen Reduction Systems (PNRS) and Recommendations for Future Implementation**

#### **Prepared for:**

Florida Department of Health  
Division of Disease Control and Health Protection  
Bureau of Environmental Health  
Onsite Sewage Programs  
4042 Bald Cypress Way Bin #A-08  
Tallahassee, FL 32399-1713

FDOH Contract CORCL

**August 2015**

#### **Prepared by:**

**HAZEN AND SAWYER**  
Environmental Engineers & Scientists

In Association With:

**AET**  
Applied Environmental Technology





## Table of Contents

Acknowledgements .....	i-1
Professional Engineer Certification .....	ii
Executive Summary .....	ES-1
Section 1     Introduction .....	1-1
1.1     Project Background .....	1-1
1.2     Previous Passive Nitrogen Reduction Study .....	1-2
1.3     Prioritization and Pilot Testing of Treatment.....	1-2
Technologies	
1.4     Full Scale Prototype PNRS Evaluation at .....	1-2
Florida Homes	
Section 2     Objectives and Scope .....	2-1
Section 3     Selection of Treatment Processes .....	3-1
3.1     Task A Ranking and Prioritization.....	3-1
3.2     PNRS Pilot Testing .....	3-3
3.2.1     Groups 1 & 2 Results .....	3-9
3.2.2     Group 3 Results.....	3-16
3.2.3     Group 4 Results.....	3-16
3.2.4     Summary .....	3-17
3.3     Recommended PNRS for Full Scale Evaluation.....	3-18
3.3.1     Two-Stage Process .....	3-18
3.3.2     Stage 1 Nitrification .....	3-18
3.3.3     Stage 1 Pre-Denitrification with .....	3-19
Recirculation	
3.3.4     Stage 2 Denitrification .....	3-20
3.4     Full Scale Prototype Design Concept.....	3-20
3.4.1     Surface Hydraulic Loading Rates .....	3-23
3.4.2     Media Type .....	3-23
3.4.3     Tankage.....	3-24



Section 4	Full Scale Prototype PNRS Evaluations: Materials and Methods .....	4-1
4.1	Full Scale PNRS Demonstration Sites.....	4-1
4.2	System Types and Configurations.....	4-3
4.3	Monitoring .....	4-8
4.3.1	Flowrate Measurement.....	4-8
4.3.2	Water Quality .....	4-9
4.3.3	Energy Consumption .....	4-11
4.3.4	Operation and Maintenance .....	4-12
Section 5	Full Scale Prototypes PNRS Evaluations: Results .....	5-1
5.1	Flowrates .....	5-1
5.2	Wastewater Temperature .....	5-3
5.3	Water Quality .....	5-3
5.4	Operation and Maintenance .....	5-21
5.5	Energy and Media Consumption .....	5-24
Section 6	Data Analyses and Discussion .....	6-1
6.1	Stage 1 Performance.....	6-1
6.2	Stage 2 Performance.....	6-3
6.2.1	Sulfur Performance .....	6-10
6.2.2	Estimates of Media Life.....	6-15
6.3	Overall System Performance.....	6-19
Section 7	Life Cycle Cost Analysis .....	7-1
7.1	Life Cycle Cost Analysis Tool (PNRS LCCA) .....	7-1
7.2	Application of PNRS LCCA.....	7-2
7.3	PNRS LCCA Results .....	7-5
7.4	Comparison of Life Cycle Costs of PNRS .....	7-15
7.4.1	PNRS System Total Present Worth and ..... Construction Costs	7-15
7.4.2	Task B System Construction Costs and ..... PNRS LCCA Estimates	7-17
7.4.3	PNRS Present Worth per Mass Nitrogen..... Removed	7-19
7.5	Comparison of Life Cycle Costs to Other Studies .....	7-20

7.6	Summary .....	7-23
Section 8	Recommended Framework for Onsite Wastewater Nitrogen Reduction in Florida .....	8-1
8.1	Low Level Onsite Wastewater Nitrogen Removal .....	8-2
8.1.1	Expected Performance .....	8-2
8.1.2	Operation and Maintenance.....	8-4
8.1.3	Permitting and Monitoring Requirements.....	8-4
8.1.4	Life Cycle Cost Analysis .....	8-4
8.2	Medium Level Onsite Wastewater Nitrogen Removal ....	8-6
8.2.1	Expected Performance .....	8-6
8.2.2	Operation and Maintenance.....	8-7
8.2.3	Permitting and Monitoring Requirements.....	8-7
8.2.4	Life Cycle Cost Analysis .....	8-7
8.3	High Level Onsite Wastewater Nitrogen Removal.....	8-10
8.3.1	Expected Performance .....	8-10
8.3.2	Operation and Maintenance .....	8-11
8.3.3	Permitting and Monitoring Requirements .....	8-11
8.3.4	Life Cycle Cost Analysis .....	8-12
8.4	Comparison of Recommended Nitrogen Removal System Costs .....	8-15
Section 9	Conclusions and Recommendations .....	9-1
9.1	PNRS Technologies and Performance.....	9-1
9.2	PNRS Cost .....	9-5
9.3	Recommended Treatment Process Framework and Level of Treatment Expectations .....	9-6
9.4	Technical Recommendations .....	9-7
9.5	Recommendations for PNRS Implementation .....	9-8
Section 10	References .....	10-1
Appendix A	System Installation Reports.....	A-1
Appendix B	Final Field System Monitoring Reports.....	B-1

## **List of Tables**

Table 3-1	Process Systems Recommended for Task B Full Scale Testing .....	3-1
Table 3-2	PNRS Pilot Biofilter Characteristics.....	3-8
Table 3-3	Effluent Sulfate .....	3-14
Table 3-4	Preliminary Recommendations Used for Full Scale Prototype.....	3-22
	PNRS Design	
Table 4-1	Site Evaluation by County .....	4-1
Table 4-2	Test Site Characteristics .....	4-2
Table 4-3	Summary of Prototype PNRS Design Characteristics.....	4-4
Table 4-4	Flow Measurement Devices .....	4-9
Table 4-5	Water Quality Monitoring Locations .....	4-10
Table 4-6	Field Parameter Analyses .....	4-10
Table 4-7	Laboratory Analyses Methods.....	4-11
Table 4-8	Energy Consumption Monitoring Location.....	4-12
Table 4-9	General Operation & Maintenance .....	4-12
Table 5-1	Test System Operating Periods .....	5-1
Table 5-2	Flowrate.....	5-2
Table 5-3	Hydraulic Loading Rate .....	5-2
Table 5-4	Summary of Effluent Total Nitrogen (mean $\pm$ SD).....	5-21
Table 5-5	System Operation.....	5-22
Table 5-6	System Operation and Maintenance .....	5-23
Table 5-7	Energy Consumption .....	5-25



Table 6-1	Stage 1 Biofilters Mean Removal Efficiencies (%) .....	6-2
Table 6-2	Stage 2 Lignocellulosic Biofilter Characteristics .....	6-5
Table 6-3	Stage 2 Lignocellulosic Biofilter NO <sub>x</sub> N Removal .....	6-6
Table 6-4	Summary of Literature Values for Lignocellulosic Denitrification.....	6-7
Table 6-5	Stage 2 Sulfur Biofilter NO <sub>x</sub> N Removal .....	6-11
Table 6-6	Summary of Literature Values for Sulfur Denitrification.....	6-14
Table 6-7	Effluent Sulfate .....	6-15
Table 6-8	Lignocellulosic Media Life .....	6-16
Table 6-9	Sulfur Media Life .....	6-18
Table 6-10	Summary of Mean Effluent Water Quality Constituents of Interest .....	6-19
Table 6-11	Overall Performance of Prototype PNRS .....	6-21
Table 6-12	Total Nitrogen Mass Balance for Prototype PNRS.....	6-24
Table 7-1	Seven PNRS Evaluated .....	7-3
Table 7-2	PNRS LCCA Results Output for BHS-1 PNRS .....	7-6
Table 7-3	PNRS LCCA Results Output for BHS-2 PNRS .....	7-7
Table 7-4	PNRS LCCA Results Output for BHS-3 PNRS .....	7-8
Table 7-5	PNRS LCCA Results Output for BHS-4 PNRS .....	7-9
Table 7-6	PNRS LCCA Results Output for BHS-5 PNRS .....	7-10
Table 7-7	PNRS LCCA Results Output for BHS-6 PNRS .....	7-11
Table 7-8	PNRS LCCA Results Output for BHS-7 PNRS .....	7-12
Table 7-9	Summary of Construction Costs for Full Scale PNRS LCCA .....	7-13
	Tool vs. As-built Cost	



Table 7-10	Summary of Estimated Construction Costs by Treatment.....	7-14
	Component	
Table 7-11	Key Life Cycle Cost Statistics for Prototype PNRS .....	7-15
Table 7-12	Summary of Comparison of Life Cycle Costs.....	7-22
Table 8-1	Performance References for Low Level Nitrogen Removal Option.....	8-3
Table 8-2	PNRS LCCA Result for Low Level Nitrogen Removal Option (30%) .....	8-5
Table 8-3	Performance References for Medium Level Nitrogen .....	8-6
	Removal Option (results prior to STU)	
Table 8-4	PNRS LCCA Result for Medium Level In-Tank Nitrogen Removal .....	8-8
	Option (70%)	
Table 8-5	PNRS LCCA Result for Medium Level In-Ground Nitrogen Removal ....	8-9
	Option (70%)	
Table 8-6	Performance References for High Level Nitrogen Removal Option.....	8-11
	(results prior to STU)	
Table 8-7	PNRS LCCA Result for High Level In-Tank Nitrogen Removal.....	8-13
	Option (95%)	
Table 8-8	PNRS LCCA Result for High Level In-Ground Nitrogen Removal.....	8-14
	Option (95%)	
Table 8-9	Comparison of PNRS LCCA Results for Recommended Nitrogen .....	8-15
	Removal Systems	

## **List of Figures**

Figure 3-1	GCREC Pilot Test Facility Groups.....	3-3
Figure 3-2	Flow Schematic for a Single Pass Stage 1 Biofilter Directly..... Coupled to Upflow Stage 2 Biofilter	3-4
Figure 3-3	Flow Schematic for a Recirculating Stage 1 Biofilter and..... Horizontal Stage 2 Biofilter	3-5
Figure 3-4	Flow Schematic for an In-tank Vertically Stacked Stage 1/Stage 2..... Biofilter System	3-6
Figure 3-5	Flow Schematic for an In-Ground Vertically Stacked Stage 1/..... Stage 2 Biofilter System	3-7
Figure 3-6	Unsaturated Biofilter Effluent TKN Nitrogen (Stage 1) .....	3-10
Figure 3-7	Saturated Biofilter Effluent NO <sub>x</sub> -N (Stage 2).....	3-11
Figure 3-8	Stage 2 Lignocellulosic Biofilters NO <sub>x</sub> -N Reduction with Time .....	3-12
Figure 3-9	Saturated Biofilter Effluent Total Nitrogen (Stage 2) .....	3-13
Figure 3-10	Total Nitrogen Removal Efficiency of Various 2 Stage Biofilter..... Systems, Organized by Stage 2 Biofilter	3-14
Figure 3-11	Solute Profile for Stage 2 Biofilter 8-SU-80 .....	3-16
Figure 3-12	Biological Removal of Wastewater Nitrogen .....	3-18
Figure 3-13	Stage 1 Single Pass Process Flow Diagram.....	3-19
Figure 3-14	Stage 1 Recirculation Process Flow Diagram .....	3-20
Figure 4-1	Map of Evaluated Field Sites.....	4-2
Figure 4-2	BHS-1 Process Flow Diagram.....	4-5
Figure 4-3	BHS-2 Process Flow Diagram (R tank).....	4-6
Figure 4-4	BHS-3 Process Flow Diagram.....	4-6



Figure 4-5	BHS-4 Process Flow Diagram.....	4-7
Figure 4-6	BHS-5 Process Flow Diagram (R Internal).....	4-7
Figure 4-7	BHS-6 Process Flow Diagram.....	4-8
Figure 4-8	BHS-7 Process Flow Diagram.....	4-8
Figure 5-1	Temperature Cumulative Frequency Diagram .....	5-3
Figure 5-2	BHS-1 Graphical Representation of Water Quality Results .....	5-5
	(mean $\pm$ SD)	
Figure 5-3	BHS-1 Total Nitrogen Time Series Graph .....	5-6
Figure 5-4	BHS-2 (R Tank) Graphical Representation of Water Quality Overall .....	5-7
	Results (mean $\pm$ SD)	
Figure 5-5	BHS-2 (R Internal) Graphical Representation of Water Quality .....	5-8
	Overall Results (mean $\pm$ SD)	
Figure 5-6	BHS-2 Total Nitrogen Time Series Graph .....	5-9
Figure 5-7	BHS-3 Graphical Representation of Water Quality Results .....	5-10
	(mean $\pm$ SD)	
Figure 5-8	BHS-3 Total Nitrogen Time Series Graph .....	5-11
Figure 5-9	BHS-4 Graphical Representation of Water Quality Results .....	5-12
	(mean $\pm$ SD)	
Figure 5-10	BHS-4 Total Nitrogen Time Series Graph .....	5-13
Figure 5-11	BHS-5 (Single Pass) Graphical Representation of Water Quality .....	5-14
	Overall Results (mean $\pm$ SD)	
Figure 5-12	BHS-5 (R Internal) Graphical Representation of Water Quality .....	5-15
	Overall Results (mean $\pm$ SD)	
Figure 5-13	BHS-5 Total Nitrogen Time Series Graph .....	5-16
Figure 5-14	BHS-6 Graphical Representation of Water Quality Results .....	5-17
	(mean $\pm$ SD)	

Figure 5-15	BHS-6 Total Nitrogen Time Series Graph .....	5-18
Figure 5-16	BHS-7 Graphical Representation of Water Quality Results ..... (mean $\pm$ SD)	5-19
Figure 5-17	BHS-7 Total Nitrogen Time Series Graph .....	5-20
Figure 5-18	Time Series of Energy Use per 1000 Gallons Treated.....	5-26
Figure 6-1	Stage 1 Biofilters Total Nitrogen Removal Efficiencies .....	6-3
Figure 6-2	Stage 2 Lignocellulosic Biofilter Effluent NO <sub>x</sub> -N.....	6-8
Figure 6-3	Stage 2 Lignocellulosic Biofilter NO <sub>x</sub> -N Cumulative Frequency..... Diagram	6-9
Figure 6-4	In-tank Lignocellulosic Biofilter NO <sub>x</sub> -N Removal Rate vs HRT .....	6-10
Figure 6-5	Sulfur Biofilter Effluent NO <sub>x</sub> -N Box.....	6-12
Figure 6-6	Sulfur Biofilter Effluent NO <sub>x</sub> -N Cumulative Frequency Diagram .....	6-13
Figure 6-7	Solute Profiles for Stage 2 Sulfur Biofilters.....	6-17
Figure 6-8	Overall PNRS Total Nitrogen Removal Efficiency Time Series.....	6-22
Figure 6-9	Overall PNRS Mean Total Nitrogen Removal Performance.....	6-23
Figure 6-10	Overall Prototype Systems Mean cBOD <sub>5</sub> Removal Performance .....	6-26
Figure 6-11	Overall Prototype Systems Mean TSS Removal Performance .....	6-27
Figure 6-12	Overall Prototype Systems Mean Total Phosphorus Removal..... Performance	6-28
Figure 6-13	Overall Prototype Systems Geomean Fecal Coliform.....	6-29
Figure 6-14	Overall Prototype Systems Mean Sulfate for Systems using Sulfur..... in Stage 2	6-30
Figure 6-15	Overall Prototype Systems Mean Total Alkalinity.....	6-31
Figure 7-1	Total Present Worth of Life Cycle Costs and Estimated..... Construction Cost of PNRS from PNRS LCCA	7-16



Figure 7-2	PNRS Construction Cost as Percentage of Present Worth.....	7-17
Figure 7-3	Comparison of PNRS As-built Construction Costs and PNRS..... LCCA Construction Cost Estimates	7-18
Figure 7-4	Trend Line for As-built Construction Costs and PNRS LCCA ..... Estimates	7-19
Figure 7-5	PNRS Present Worth per Mass of Nitrogen Removal.....	7-20
Figure 7-6	Comparison of Present Worth per Pound Nitrogen Removed..... and Percent TN Reduction	7-23
Figure 8-1	Total Present Worth of Life Cycle Costs and Construction Costs ..... for Three Recommended Nitrogen Removal Systems	8-16



## **Acronyms and Abbreviations**

ATU	Aerobic Treatment Unit
BHS	FOSNRS Task B Home Site
BMAPs	Basin Management Action Plans
BRF	Bay Restoration Fund
CBOD	Carbonaceous Biochemical Oxygen Demand
CL	Clinoptilolite
COD	Chemical Oxygen Demand
cont.	Continued
D-Box	Distribution Box
DFT	Denite Feed Tank
DO	Dissolved Oxygen
EC	Expanded Clay
E.S.	Effective Size
FDOH	Florida Department of Health
Fecal	Fecal Coliform
FOSNRS	Florida Onsite Sewage Nitrogen Reduction Strategies
FT <sup>2</sup>	Square Feet
GCREC	Gulf Coast Research and Education Center
GL	Glycerol
GPD	Gallons Per Day
HRT	Hydraulic Retention Time
H <sub>2</sub> S	Hydrogen Sulfide Unioinized
kWh	Kilowatt-hours
LCCA	Life Cycle Cost Analysis
LP	Low Pressure Distribution
LS	Lignocellulose
MBR	Membrane Bioreactor
NA	Not Analyzed
NH <sub>3</sub> -N	Ammonia Nitrogen
NO <sub>2</sub> -N	Nitrite Nitrogen
NO <sub>3</sub> -N	Nitrate Nitrogen
NO <sub>x</sub> -N	Nitrate and Nitrite Nitrogen
NPV	Net Present Value
O&M	Operation & Maintenance
ORP	Oxidation-Reduction Potential
Ortho P	Orthophosphate as P
OSTDS	Onsite Sewage Treatment and Disposal Systems
PNRS	Passive Nitrogen Reduction Systems
PW	Present Worth

Q	Forward Flow
R	Recirculation Flow
R internal	Recirculation to top of Stage 1 media
R Tank	Recirculation Tank
RRAC	Research Review and Advisory Committee
SA	Sand
SD	Standard Deviation
SO <sub>4</sub>	Sulfate
SP	Single Pass
STE	Septic Tank Effluent
STUs	Soil Treatment Units
SU	Elemental Sulfur
Temp	Temperature
TKN	Total Kjeldahl Nitrogen
TMDLs	Total Maximum Daily Loads
TN	Total Nitrogen
TOC	Total Organic Carbon
TP	Total Phosphorus
TSS	Total Suspended Solids
U.C.	Uniformity Coefficient
VSS	Volatile Suspended Solids
YRS.	Years



## **Acknowledgements**

The authors would like to acknowledge all the Hazen staff, sub consultants, and support personnel that worked so hard to make this project a success. We thank the Research Review and Advisory Committee of the Florida Department of Health for supporting this project from beginning to end, without whose support the project would have not been possible. Elke Ursin and Eberhard Roeder of the Onsite Sewage Programs office in Tallahassee managed the Administrative and Technical aspects of the project for FDOH and were very helpful in keeping things on track despite numerous obstacles along the way. We thank the University of Florida Gulf Coast Research and Education Center for their cooperation on the project and for allowing us use of the site for the pilot test facility. And last but not least, we sincerely thank the volunteer property owners for providing use of their property for the experimental systems and groundwater monitoring, without their cooperation the study would not have been nearly as successful.





-THIS PAGE INTENTIONALLY LEFT BLANK-

## Professional Engineer Certification

The engineering features of the *Evaluation of Full Scale Prototype Passive Nitrogen Reduction Systems (PNRS) and Recommendations for Future Implementation* for Florida Department of Health, August 2015 were prepared by, or reviewed by a Licensed Professional Engineer in the State of Florida.



Darriann L. Anderson, P.E.  
Principal Investigator

August 28, 2015

Date

8/28/15

Florida PE # 37157

License Number

*Daniel P. Smith*

Daniel P. Smith, Ph.D., P.E., DEE  
Co-Principal Investigator

August 28, 2015

Date

Florida PE # 58388

License Number



Josefin E. Hirst, P.E.  
Lead Engineer

August 28, 2015

Date

8/28/15

Florida PE # 69835

License Number



-THIS PAGE INTENTIONALLY LEFT BLANK-

## Executive Summary

The Florida Department of Health (FDOH) estimates that over 2.7 million onsite sewage treatment and disposal systems (OSTDS) are currently operating in the State of Florida. Nitrogen loading from onsite systems is a potential concern in the state, depending on the number and density of onsite installations, their proximity to receiving waters, nitrogen removal processes in subsurface soils, and the sensitivity of receiving waters. The great majority of Florida onsite systems are comprised of a septic tank for primary treatment followed by dispersal into the environment using soil treatment units (STUs) commonly referred to as drainfields. Provided these typical systems meet current code requirements, they provide significant treatment of primary effluent, but their ability to remove nitrogen prior to the renovated effluent reaching groundwater is limited relative to other parameters.

In 2008, the Florida legislature provided funding to FDOH to develop cost-effective, passive strategies for nitrogen reduction that complement the use of conventional OSTDS, and the Florida Onsite Sewage Nitrogen Reduction Strategies (FOSNRS) project was initiated in 2009. The FOSNRS project implemented a multi-pronged approach to address nitrogen loading from OSTDS to the Florida environment.

The FOSNRS project incorporated four primary study areas:

- Task A: Technology evaluation for field testing, test facility design and construction and pilot testing of passive nitrogen reduction systems (PNRS);
- Task B: Field testing of full scale treatment technologies, performance evaluation and cost analyses;
- Task C: Evaluation of nitrogen reduction provided by Florida soils and shallow groundwater;
- Task D: Nitrogen fate and transport modeling and the development of decision support tools for OSTDS planning and management.

A central component of the FOSNRS project was the development, design, and field evaluation of both pilot and full scale onsite wastewater nitrogen reduction technologies. The goal of Task B of the FOSNRS project was to develop, design, install and evaluate prototype treatment technologies that are appropriate for residential onsite deployment, are relatively passive in operation, and which substantially increase nitrogen reduction over that of conventional OSTDS. Because of the flat topography common to the state, the definition of “passive” included the use of up to 1 pump as the only mechanical input to the system.

This report provides a summary of the full scale passive nitrogen reduction system (PNRS) prototype development, design, installation and testing under Task B of the Florida Onsite Sewage Nitrogen Reduction Strategies (FOSNRS) Project. It provides a summary background of the FOSNRS project and the goals and objectives of the full scale prototype evaluations (Sections 1 & 2). Section 3 provides the background leading to the selection of the passive nitrogen reduction system treatment processes that were tested, and the basic design concepts that were used to design the full scale prototype systems. The prototype PNRS that were designed, constructed and tested are described in Section 4, along with the test sites chosen and monitoring methods used. Section 5 presents the results of the full scale prototype PNRS testing and evaluations based on the monitoring reports developed earlier in Task B. An analysis of the monitoring data collected and discussion of the results is provided in Section 6. Section 7 presents the Life Cycle Cost Analysis of full scale PNRS based on the PNRS LCCA tool developed earlier in Task B (Hazen & Sawyer and AET, 2015). Based on the results and experience gained from the full scale testing of prototype PNRS, recommended treatment processes for residential onsite wastewater nitrogen reduction in Florida are presented in Section 8. The recommended PNRS are organized by technologies that can provide low, medium or high levels of nitrogen removal from residential onsite wastewater, depending on the nitrogen sensitivity of the receiving waters. Section 9 summarizes conclusions drawn from the prototype PNRS evaluations and provides recommendations for next steps in moving forward with PNRS in Florida.

## **i.1 PNRS Technologies and Performance**

Based on a review, prioritization and ranking of available onsite wastewater nitrogen removal technologies in Task A of the FOSNRS project, nitrogen removal by two-stage biofiltration was selected as the most operationally simple, effective and applicable nitrogen removal process for development of PNRS for onsite wastewater treatment (Hazen & Sawyer, AET and OEC, 2009b). A unique pilot scale test facility was therefore designed and constructed at the UF Gulf Coast Research and Education Center to test numerous design concepts for two-stage biofiltration and to develop further design criteria for implementation of full scale PNRS for testing in FOSNRS Task B. Based on approximately two years of pilot study results (Hazen & Sawyer and AET, 2014), seven full scale prototype two-stage biofilter based PNRS were designed and constructed for evaluation at existing homes in Florida.

The seven prototype single family home PNRS evaluated in FOSNRS Task B (BHS) encompassed a variety of designs of passive two-stage biofiltration systems for onsite nitrogen removal as summarized in Table ES-1. Construction of each PNRS was evaluated for cost and ease of construction, and the systems were subsequently monitored over an approximately 2 year period with water quality sampling conducted bi-monthly over 18 months. The prototype systems performed very well over multiple years in real onsite conditions. Nitrogen removal performance of the full scale PNRS confirmed the results of



previous PNRS pilot testing and established the two-stage biofiltration process as an effective and viable technology for onsite nitrogen removal. The prototype system demonstrations provide valuable guidance for future PNRS design for individual home sites and for planning level analysis to achieve nitrogen reduction goals in Florida. The prototype PNRS performance was such that, with relatively minor design refinements, several of the system designs could be configured for innovative systems permitting. Several other systems showed considerable potential as PNRS, but need further design refinements and testing.



**Table ES-1: Summary of Prototype PNRS**

<b>System</b>	<b>System Description</b>	<b>Hydraulics</b>	<b>64E-6<sup>1</sup> Design Flow (gpd)</b>
BHS-1	Proprietary: Stage 1 Aerocell™ Stage 2 Nitrex™	Pumped with Stage 1 internal recirculation	300
BHS-2	In-tank two stage biofilter with stage 1 recirculation, dual media stage 2; lignocellulosic (2a) followed by elemental sulfur (2b)	Pumped with both Stage 1 recirculation to tank and Stage 1 internal recirculation tested	400
BHS-3	In-ground stacked biofilter, single pass stage 1 over stage 2a with supplemental stage 2b tank; stage 2a lignocellulosic/sand mixture; stage 2b elemental sulfur tank	Pumped with subsurface drip irrigation STE application	580
BHS-4	In-tank two stage biofilter with single pass stage 1, dual media stage 2; lignocellulosic (2a) followed by elemental sulfur (2b)	Gravity	400
BHS-5	In-tank two stage biofilter with single pass stage 1, dual media stage 2; lignocellulosic (2a) followed by elemental sulfur (2b)	Pumped with both Stage 1 internal recirculation and single pass tested	500
BHS-6	In-tank vertically stacked biofilter, single pass stage 1 over stage 2a with supplemental stage 2b tank; stage 2a lignocellulosic; stage 2b elemental sulfur tank	Pumped with spray nozzle application (no recirculation)	300
BHS-7	In-ground stacked biofilter, single pass stage 1 over stage 2 lignocellulosic	Pumped low pressure distribution	300

<sup>1</sup>per FAC 64E-6.008 Table I

The prototype PNRS Stage 1 biofilters were all very effective in nitrifying organic and ammonia nitrogen to nitrate+nitrite (NO<sub>x</sub>) nitrogen (Table ES-2). Mean ammonia removal efficiencies for the seven prototype PNRS Stage 1 biofilters ranged from 88 to 100%, which provided a Stage 1 effluent (Stage 2 influent) suitable for denitrification and high total nitrogen removal efficiency. All seven Stage 1 biofilters also achieved some level of denitrification and total nitrogen (TN) removal (Table ES-2). Mean TN removal efficiency by the Stage 1 biofilters ranged from 18 to 61%, with the highest efficiency achieved in system BHS-2 by recycling a portion of the nitrified effluent to a recirculation tank for significant pre-denitrification.

**Table ES-2: Stage 1 Biofilters Mean Removal Efficiencies (%)**

	System	Stage 1 Operation <sup>2</sup>	TSS	CBOD <sub>5</sub>	TN	TKN	Organic N	NH <sub>3</sub> -N
Single Pass	BHS-3	Drip SP	91%	90%	48%	96%	72%	100%
	BHS-4	SP	85%	94%	35%	83%	49%	88%
	BHS-5	SP	94%	86%	30%	91%	60%	95%
	BHS-6	SP	-207% <sup>1</sup>	72%	25%	88%	69%	92%
	BHS-7	SP	90%	91%	47%	94%	74%	99%
Recirculating	BHS-1	R tank	90%	75%	47%	86%	83%	90%
	BHS-2	R tank	4%	86%	61%	94%	76%	98%
	BHS-2	R internal	98%	97%	33%	92%	79%	98%
	BHS-5	R internal	97%	96%	18%	94%	50%	100%

<sup>1</sup>The Stage 1 samples from this vertically stacked system were taken from pan lysimeters placed at the expanded clay/lignocellulosic interface. It is suspected that pumping samples up from these pans included some fines from the expanded clay media, thus the increase in TSS over the influent value.

<sup>2</sup>R tank = recirculation to tank

The PNRS Stage 2 biofilters were very effective in denitrifying NO<sub>x</sub> nitrogen to gaseous N forms, thus reducing Total Nitrogen in the system effluent. Mean NO<sub>x</sub>-N removal efficiency for the Stage 2 lignocellulosic biofilters ranged from 41 to 100%, with the lower performance from system BHS-6 which experienced hydraulic problems and malfunctioned on several occasions (Table ES-3).

**Table ES-3: Stage 2 Lignocellulosic Biofilter NO<sub>x</sub>-N Removal**

System	Stage 1 Operation <sup>2</sup>	Influent Mean NO <sub>x</sub> -N, mg N/L	Effluent Mean NO <sub>x</sub> -N, mg N/L	Mean NO <sub>x</sub> -N Removal Efficiency (%)	Mean NO <sub>x</sub> -N Removal Rate (g N m <sup>-3</sup> d <sup>-1</sup> )
BHS-1	R tank	32.33	0.09	100%	2.48
BHS-2	R tank	16.72	0.02	100%	1.93
	R internal	34.00	3.96	88%	3.58
BHS-3	Drip SP	23.92	5.77	76%	1.28 <sup>1</sup>
BHS-4	SP	33.58	3.15	91%	9.59
BHS-5	SP	43.44	4.10	91%	4.76
	R internal	57.25	32.25	44%	3.28
BHS-6	SP	42.26	24.87	41%	5.30

<sup>1</sup>The BHS-3 lignocellulosic media mixture was 50% reactive media, the mean NO<sub>x</sub>-N removal rate is calculated using the total mixed media volume.

<sup>2</sup>R tank = recirculation to tank

R internal = recirculation to top of Stage 1 media

SP = single pass

Mean NO<sub>x</sub>-N removal efficiency for the Stage 2 elemental sulfur biofilters ranged from 74 to 100% (Table ES-4). Since all Stage 2 sulfur biofilters were preceded by a lignocellulosic biofilter, there was often very little NO<sub>x</sub> reaching the sulfur media, which influenced the efficiency. Mean NO<sub>x</sub>-N concentrations in sulfur biofilter effluents ranged from below detection limits (0.02 mg N/L) to 4.4 mg NO<sub>x</sub>-N/L for the Stage 2 biofilters containing sulfur media. Excluding system BHS-6 (hydraulic malfunctions), mean Stage 2 effluent from sulfur biofilters was less than 1 mg NO<sub>x</sub>-N/L.

**Table ES-4: Stage 2 Sulfur Biofilter NO<sub>x</sub>-N Removal**

System	Percent Reactive Media	Stage 1 Operation <sup>2</sup>	Mean Influent Flow (m <sup>3</sup> /day)	Media Volume (m <sup>3</sup> )	Hydraulic Retention Time <sup>1</sup> (days)	Influent Mean NO <sub>x</sub> -N, mg N/L	Effluent Mean NO <sub>x</sub> -N, mg N/L	Mean NO <sub>x</sub> -N Removal Efficiency (%)
BHS-2	90%	R tank	0.413	1.02	2.5	0.02	0.02	NA
		R internal	0.426	1.02	2.4	3.96	0.02	99%
BHS-3	90%	Drip SP	0.548	1.09	2.0	5.77	0.61	89%
BHS-4	90%	SP	1.124	0.76	0.7	3.15	0.82	74%
BHS-5	90%	SP	0.432	0.76	1.8	4.10	0.04	99%
		R internal	0.468	0.76	1.6	32.25	0.03	100%
BHS-6	90%	SP	0.578	0.57	1.0	24.87	4.41	82%

<sup>1</sup>Calculated as empty bed residence time

<sup>2</sup>R tank = recirculation to tank

R internal = recirculation to top of Stage 1 media

SP = single pass

The mean Total Nitrogen (TN) removal efficiency for seven full scale prototype passive two-stage nitrogen removal systems ranged from 65 to 98% with an overall mean of 90% for all systems (Table ES-5). However, the nitrogen removal efficiency of the three most refined and best performing prototype systems (BHS-2, BHS-3 and BHS-5) averaged over 95% TN removal. The two lowest performing PNRS (BHS-6 and BHS-7) showed the potential to achieve similar TN removal efficiencies at times, but their performance was hampered by less than optimal design or construction issues.

The mean CBOD<sub>5</sub> removal efficiency for the seven full scale prototype passive two-stage nitrogen removal systems ranged from 36 to 91% with an overall mean of 79% for all systems. The mean Stage 2 effluent in most of the systems showed an increase in CBOD<sub>5</sub> concentration as compared to the Stage 1 effluent which may be attributed to CBOD<sub>5</sub> release from the lignocellulosic media itself. The BHS-2 system which incorporated a sawdust lignocellulosic media is associated with the highest concentration of Stage 2 CBOD<sub>5</sub>. The mean TSS removal efficiency for the seven full scale prototype passive two-stage nitrogen removal systems ranged from 76 to 97% with an overall mean of 89% for all systems. The mean effluent TSS concentration for all seven systems was below 10 mg/L.

The mean Total Phosphorus (TP) removal efficiency for the seven full scale prototype passive two-stage nitrogen removal systems ranged from 12 to 96% with an overall mean of 64% for all systems. The best performing PNRS were the in-ground systems (BHS-3 and BHS-7). An evaluation of the long term phosphorus adsorption capacity of the evaluated media was not conducted as part of this study, and phosphorus removal may decline at some future point when P adsorption sites become limiting.

The geomean of effluent fecal coliform concentration for the seven prototype PNRS ranged from 1 to 1,838 ct/100 mL. The highest geomean fecal coliform count can be attributed to the BHS-6 design issues previously discussed. The most refined and best performing prototype systems (BHS-2, BHS-3 and BHS-5) produced an effluent fecal coliform concentration below 60 ct/100 mL. The mean effluent sulfate concentration for the five full scale prototype passive two-stage nitrogen removal systems that utilized sulfur media ranged from 37 to 248 mg/L. Therefore, the mean effluent sulfate levels were below the secondary drinking water guideline of 250 mg/L for all systems utilizing sulfur media.

**Table ES-5: Overall Performance of Prototype PNRS Systems**

<b>System</b>	<b>Stage 1 Operation<sup>3</sup></b>	<b>Mean TN Removal Efficiency, %</b>	<b>Mean CBOD<sub>5</sub> Removal Efficiency, %</b>	<b>Mean TSS Removal Efficiency, %</b>	<b>Mean TP Removal Efficiency, %</b>
BHS-1	R tank	91%	75%	93%	12%
BHS-2	R tank	93%	36%	76%	40%
	R internal	97%	78%	97%	51%
BHS-3	Drip SP	96%	80%	81%	96%
BHS-4	SP	89%	91%	93%	72%
BHS-5	SP	97%	87%	94%	85%
	R internal	98%	86%	90%	83%
BHS-6 <sup>1</sup>	SP	81%	90%	87%	49%
BHS-7 <sup>2</sup>	In-ground LP	65% <sup>2</sup>	87% <sup>2</sup>	88% <sup>2</sup>	90% <sup>2</sup>

<sup>1</sup>Clogging of internal drainage and distribution pipes within this system caused flooding of the Stage 1 media on several occasions, which hampered performance. Different construction materials for drains and a revised design would eliminate these problems.

<sup>2</sup>The reported values are calculated using the mean perimeter monitoring samples. Since it is believed that the hydraulics of the system as designed did not allow most flow to pass through the liner media, this reduction is most likely not attributed to lignocellulosic media, but to reductions in the Stage 1 media. A revised liner design could solve this problem.

<sup>3</sup>R tank = recirculation to tank

R internal = recirculation to top of Stage 1 media

SP = single pass

LP = low pressure distribution

The mean effluent Total Nitrogen (TN) concentration for the seven prototype PNRS ranged from 1.8 to 19.1 mg/L (Table ES-6). The highest mean TN effluent concentrations can be attributed to the BHS-7

design issues. Once again, the most refined and best performing prototype systems (BHS-2, BHS-3 and BHS-5) produced a mean effluent TN concentration of 2.6 mg/L.

**Table ES-6: Summary of Effluent Total Nitrogen (mean  $\pm$  SD)**

System	System Description <sup>1</sup>	Mean Influent TN, mg/L	Mean Effluent TN, mg/L	Mean TN Reduction, %
BHS-1	Proprietary: Stage 1 Aerocell™ Stage 2 Nitrex™	82.7 $\pm$ 11.0	7.1 $\pm$ 5.7	91
BHS-2	In-tank Stage 1 with R tank, dual-media Stage 2	50.5 $\pm$ 5.4	3.5 $\pm$ 2.4	93
BHS-2	In-tank Stage 1 with R internal, dual-media Stage 2	57.8 $\pm$ 7.5	1.8 $\pm$ 1.2	97
BHS-3	In-ground stacked Stage 1 over Stage 2a ligno with supplemental Stage 2b sulfur	50.5 $\pm$ 8.8	1.9 $\pm$ 1.7	96
BHS-4	In-tank SP Stage 1, dual-media Stage 2	70.1 $\pm$ 10.0	7.4 $\pm$ 4.9	89
BHS-5	In-tank SP Stage 1, dual-media Stage 2	70.8 $\pm$ 7.8	2.3 $\pm$ 1.8	97
BHS-5	In-tank Stage 1 with R internal, dual-media Stage 2	75.0 $\pm$ 11.6	1.8 $\pm$ 0.4	98
BHS-6	In-tank stacked Stage 1 over Stage 2a ligno with supplemental Stage 2b sulfur	66.3 $\pm$ 17.9	12.4 $\pm$ 8.5	81
BHS-7	In-ground LP stacked SP Stage 1 over Stage 2 ligno	54.9 $\pm$ 9.8	19.1 $\pm$ 10.9	65

<sup>1</sup>R tank = recirculation to tank

R internal = recirculation to top of Stage 1 media

SP = single pass

LP = low pressure distribution

Mean electrical consumption of the prototype PNRS was 4.5 kw-hour per 1000 gallons of wastewater flow from the home and ranged from 0 to 28.7 kw-hr/1000 gallon (Table ES-7). The highest energy usages were for BHS-1 due to a Stage 1 biofilter with a very high recirculation ratio and BHS-3 which included pumping to drip dispersal zones for both Stage 1 STE and final effluent irrigation. Operation of single pass in-tank systems ranged from 0 to 3.2 kw-hour per 1000 gallons, while operation of recirculating in-tank systems (with a 3:1 R ratio) ranged from 1.2 to 2.8 kw-hour per 1000 gallons. This electrical use would equate to a cost of less than \$1.00 per month for a PNRS similar to the single pass or recirculating Stage 1 systems tested.

**Table ES-7: Energy Consumption**

System	Mode of Operation <sup>3</sup>	Power Use		Electrical Use vs Treated Flow	
		Mean (kWh/day)	Standard Deviation (kWh/day)	Mean (kWh/1000 gallon)	Standard Deviation (kWh/1000 gallon)
BHS-1 <sup>1</sup>	R tank	3.21	0.57	28.72	4.85
BHS-2	R tank	0.31	0.07	2.80	0.23
	R internal	0.26	0.13	2.36	0.34
	mean	0.28	0.1	2.59	0.36
BHS-3	Drip SP	0.98	0.56	7.83	5.99
BHS-4 <sup>2</sup>	Gravity SP	0	0	0	0
BHS-5	SP	0.04	0.02	0.42	0.5
	R internal	0.14	0.02	1.15	0.04
	mean	0.07	0.05	0.61	0.54
BHS-6 <sup>4</sup>	SP	0.48	0.17	3.20	1.16
BHS-7	In-ground LP	0.04	0.02	0.31	0.12

<sup>1</sup>After replacement of split flow recirculation device

<sup>2</sup>For system BHS-4 to test the total household wastewater volume, 0.14 kWh/day was used by a small transfer pump to get flow from the second OSTDS to the PNRS.

<sup>3</sup>R tank = recirculation to tank

R internal = recirculation to top of Stage 1 media

SP = single pass

LP = low pressure distribution

<sup>4</sup>Higher energy use at BHS-6 due to use of the pump from BHS-1, which was designed for high recirculation rate and higher head for sprayers.

Operation and maintenance (O&M) of the prototype PNRS reflected system complexity. The simplest system O&M was the BHS-7 in-ground PNRS, which has O&M requirements similar to a conventional OSTDS with pressure dosed STU. Slightly more complex were the in-tank PNRS with single pass Stage 1 biofilters. O&M of these PNRS was also relatively simple, adding only the Stage 1 STE distribution system to the O&M requirements. The O&M of the in-tank PNRS with Stage 1 recirculation is only slightly more complex than the single pass systems, in that timed dosing is added to the controls, and the recirculation ratio must be checked and adjusted occasionally. The most complex system was BHS-3, and this complexity was due to the use of drip dispersal for both STE application in Stage 1 and irrigation of final treated effluent to turf grass, all with one pump. This system had O&M requirements similar to more complex PBTS or STE drip systems. However, without the irrigation component, and with STE low pressure distribution instead of drip, this system would be similar to the single pass Stage 1 in-tank systems in O&M complexity.



The longevity of the PNRS reactive media could not be determined directly in the seven prototype PNRS evaluations due to the very low use of media over the approximately 2 year observation period. Theoretical calculations and literature experience with both lignocellulosic and sulfur Stage 2 biofilters suggests that it would not be difficult to design systems for media life of 25 years or longer. It would also be relatively easy to add reactive media to the in-tank Stage 2 biofilters, and sizing of these systems could potentially be reduced if routine media additions were made during the life of the system.

## **i.2 PNRS Cost**

A life cycle cost analysis (LCCA) tool for PNRS (PNRS LCCA) was developed as part of the FOSNRS project. The PNRS LCCA can be used as a planning level tool using default performance parameters or for evaluation of specific treatment technologies incorporating known performance data. In addition, the PNRS LCCA can be used to evaluate a user defined nitrogen removal efficiency for non-PNRS systems. The PNRS LCCA was used to develop life cycle costs based on the seven prototype PNRS and for other advanced onsite wastewater treatment systems for comparison purposes (Section 7). The PNRS LCCA tool provides an output report summarizing the life cycle cost analysis.

A comparison of estimated construction costs between PNRS LCCA and the actual construction costs for the seven prototype systems showed good agreement, with a relative percent error between the two costs of approximately 11% (Table ES-8). The mean estimated as-built construction cost for seven PNRS home systems was \$17,726 and ranged from \$10,399 to \$32,116. One of the lowest estimated construction cost was for the BHS-7 in-ground PNRS, which was also the simplest system. While this system's performance was less than optimal, design revisions to the Stage 2 liner module could potentially make it the most cost effective of all systems. Highest construction cost was for BHS-3, a dual drip dispersal PNRS with turf grass irrigation. Construction costs of in-tank two-stage biofilter PNRS were in the middle of the range with construction costs of \$18,000 to \$20,000. It should be noted that all seven prototype PNRS were installed at existing homes, which required additional construction time and restoration of property, increasing costs as compared to a new home installation. Additionally, these were prototype systems (with the exception of the proprietary BHS-1) that were unfamiliar to contractors and which had not been designed and constructed in Florida previously. Costs for PNRS would most likely come down with more standard designs and widespread implementation.

**Table ES-8: Summary of Construction Costs for Full Scale PNRS, LCCA Tool vs. As-built Cost**

System ID	System Description	PNRS LCCA Estimated Total System Costs		Total System As-built Construction Cost for Task B Systems		
		Total PW, \$	Total Construction Cost, \$	Task B Total Construction Cost, \$	Adjustment for permitting, monitoring, and other costs, \$	Task B Total Construction Cost, \$
BHS-1	Proprietary: Stage 1 Aerocell™ Stage 2 Nitrex™	38,269.71	19,748.84	23,600.00	4,994.00	18,606.00
BHS-2	In-tank Stage 1 with R, dual-media Stage 2	33,167.46	18,446.83	19,142.18	1,085.84	18,056.34
BHS-3	In-ground stacked Stage 1 over Stage 2a ligno with supplemental Stage 2b sulfur	53,253.23	33,154.65	40,129.79	8,014.05	32,115.74
BHS-4	In-tank SP Stage 1, dual-media Stage 2	33,373.71	19,350.49	22,030.34	5,933.17	16,097.17
BHS-5	In-tank Stage 1 with R, dual-media Stage 2	37,796.79	20,920.13	22,361.55	4,066.24	18,295.31
BHS-6	In-tank stacked Stage 1 over Stage 2a ligno with supplemental Stage 2b sulfur	30,155.22	12,926.12	13,727.12	3,327.88	10,399.24
BHS-7	In-ground stacked SP Stage 1 over Stage 2 ligno	24,838.19	13,133.85	13,836.66	3,320.81	10,515.86

The average total present worth of PNRS LCCA for the seven prototype PNRS was \$35,836 and ranged from \$24,838 to 53,253 (Table ES-9). Highest Present Worth was for the BHS-3 dual drip dispersal system, while the simpler designs had lower Present Worth. Of key importance is that non-construction

costs accounted for 38 to 57% of the total Present Worth of the prototype PNRS (46% mean). In general order of higher to lower cost, these items included annual inspection and maintenance fees, water quality monitoring, primary tank solids removal, operating permit fees, energy costs and media and equipment replacement.

The average Present Worth cost per pound of nitrogen removal for the seven prototype PNRS was \$41.95 /lb. N, and ranged from \$29 to \$52 /lb. N (Table ES-9). A comparison with the Maryland Bay Restoration Fund (BRF) data indicated that the prototype PNRS operated at a lower present worth cost per pound of nitrogen removal than the PBTS evaluated by Maryland BRF, and at significantly greater effluent TN removal efficiencies.

**Table ES-9: Key Life Cycle Cost Statistics for Prototype PNRS**

Metric	PNRS LCCA Statistics for the Seven PNRS Evaluated			
	Mean	Standard Deviation	Minimum	Maximum
Total PW, \$	35,836	8,940	24,838	53,253
Total Construction Cost, \$	19,669	6,748	12,926	33,155
lb. N removed per year	29.73	10.32	17.56	43.67
\$ PW/ lb. N removed	41.95	7.86	28.85	51.89

### **i.3 Recommended Treatment Process Framework and Level of Treatment Expectations**

The nutrient sensitivity of Florida watersheds varies greatly, and includes areas of extremely high sensitivity to nitrogen loading and other areas where nitrogen loading from OSTDS may be less critical. To accommodate this variability, three operational levels of nitrogen removal efficiency were established as part of an onsite nutrient reduction strategy related to treatment technologies (Section 8):

- Low level residential onsite wastewater nitrogen removal was defined as a system which achieves a 25 to 35 percent reduction in total nitrogen reaching the water table below the OSTDS. Assuming primary treatment followed by a STU, a 30% reduction is used as the basis for planning level nitrogen load reduction calculations at the low level.
- Medium level residential onsite wastewater nitrogen removal was defined as a wastewater treatment system which achieves a 50 to 70 percent reduction in total nitrogen prior to discharge to a STU. Assuming discharge of the effluent to a STU, a 70% reduction in total nitrogen reaching the water table below the OSTDS is used as the basis for planning level nitrogen load reduction calculations at the medium level. Technologies for medium level nitrogen removal include in-tank

Stage 1 biofilters with recirculation for pre-denitrification or an in-ground single pass Stage 1 unsaturated biofilter over a Stage 2 lignocellulosic/fine sand media mix contained in a liner.

- High level residential onsite wastewater nitrogen removal was defined as a wastewater treatment system which achieves an 85 to 95 percent reduction in total nitrogen prior to discharge to a STU. Assuming discharge of the effluent to a STU, a 95% reduction in total nitrogen reaching the water table below the OSTDS is used as the basis for planning level nitrogen load reduction calculations at the high level. Technologies for high level nitrogen removal include:
  - single pass unsaturated biofilters followed by denitrification biofilters with lignocellulosic media
  - single pass unsaturated biofilters followed by denitrification biofilters with sulfur media
  - single pass unsaturated biofilters followed by denitrification biofilters with lignocellulosic and sulfur media (dual media)
  - recirculating unsaturated biofilters followed by denitrification biofilters with sulfur media
  - recirculating unsaturated biofilters followed by denitrification biofilters with lignocellulosic and sulfur media (dual media)

#### **i.4 Technical Recommendations**

The FOSNRS project has demonstrated that passive nitrogen removal systems (PNRS) can provide effective and resilient nitrogen removal from onsite wastewater. Prior to moving ahead with PNRS implementation however, further technical refinements will be required of the prototype systems developed and tested in this project. The following technical recommendations are made based on the experience and results obtained during the FOSNRS project.

- The prototype PNRS installed as part of this study have operated for approximately 2 years. While this period was long enough to establish the treatment performance of the systems, long term performance and reliability of the systems is unknown. Therefore, it is recommended that FDOH establish long term monitoring of these home systems. This would provide invaluable knowledge of continued system performance, the longevity of media, further guidance for system designs and the long term needs for maintenance and monitoring.
- The prototype systems installed were designed and constructed based on available equipment and materials, to establish the process and performance basis for PNRS designs. Some of the

equipment, tanks and media required for the PNRS were not readily available and existing materials were customized to meet the needs of the project, adding difficulty and expense. Therefore, the systems as currently designed and constructed are not ready for widespread implementation.

- Prior to implementation at the State level, detailed PNRS design criteria need to be developed. To kick start PNRS implementation, several standardized PNRS designs could be established with technical specifications for system sizing and for all system components. Innovative system permits (or other new type of permit) should be developed for these initial PNRS. Other designs would eventually evolve if widespread implementation of onsite nitrogen removal was required.
- Specifications should be established for biofilter tankage and other system tankage to be used in PNRS, including tanks spaced across a range of sizes pertinent to single home PNRS. Specifications should include specific tank designations, source, materials, dimensions, strength requirements and pre-approved suppliers.
- Specifications should be established for tank lids and covers that provide full and easy access to media within PNRS biofilters, including pre-approved suppliers, specific tank designations, source, materials, dimensions and technical specifications.
- Specifications should be established for liners used for in-ground PNRS including pre-approved suppliers, specific liner designations, source and technical specifications.
- Specifications should be established for PNRS media including pre-approved suppliers, specific media size designations, media description, source and technical specifications.

## **i.5 Recommendations for PNRS Implementation**

Passive nitrogen removal systems (PNRS) can provide effective nitrogen removal from onsite wastewater and are a practical and resilient technology. Substantial benefits can accrue to the State of Florida through proper and judicious application of PNRS where necessary. There are also challenges to PNRS implementation that must be addressed. If the benefits of PNRS are to be realized in practice, the State must prepare for the implementation of PNRS by addressing several issues:

- Watershed/water body sensitivity to nitrogen varies widely across the state. Determination of necessary nutrient reductions to protect or improve water quality by watershed and GIS mapping of nutrient sensitive zones would allow determination of which level of nitrogen reduction is required for implementation in a given location. Nitrogen load reductions from onsite wastewater

should not be required everywhere, and in many locations upgrading existing OSTDS to current standards may be enough.

- Uniform guidance for regulation and permitting specific to PNRS need to be established, and should be streamlined. The existing permitting structure as applied to the new PNRS technology may become cumbersome, leading to lack of implementation, delay and administrative burden. Generic permitting of the initial pre-approved designs for several PNRS could speed implementation of PNRS while insuring the effective performance of installed systems.
- Uniform requirements for inspecting and maintaining PNRS should be established and updated as necessary. FDOH should establish a uniform policy for inspection and maintenance of PNRS through private or public maintenance entities.
- Uniform requirements for performance and performance monitoring of PNRS should be established and updated as necessary. FDOH should establish a uniform policy for treatment requirements and performance monitoring of PNRS.
- FDOH should implement technology transfer and training on PNRS implementation for state personnel, county regulators, industry contractors, environmental engineers and scientists.
- Sufficient staffing by FDOH is crucial for PNRS implementation. Review and permitting of PNRS should be conducted by engineers with education and experience in onsite wastewater treatment and by or under the supervision of a licensed Professional Engineer with similar experience.



-THIS PAGE INTENTIONALLY LEFT BLANK-



# 1 INTRODUCTION

## 1.1 Project Background

The Florida Department of Health (FDOH) estimates that over 2.7 million onsite sewage treatment and disposal systems (OSTDS) are currently operating in the State of Florida. Nitrogen loading from onsite systems is a potential concern in the state, depending on the number and density of onsite installations, their proximity to receiving waters, nitrogen removal processes in subsurface soils and the sensitivity of receiving waters. The great majority of Florida onsite systems are comprised of a septic tank for primary treatment followed by dispersal into the environment using soil treatment units (STUs) commonly referred to as drainfields. Provided these typical systems meet current code requirements, they provide significant treatment of primary effluent, but their ability to remove nitrogen prior to the renovated effluent reaching groundwater is limited relative to other parameters. In 2008, the Florida legislature provided funding to FDOH to develop cost-effective, passive strategies for nitrogen reduction that complement the use of conventional OSTDS, and the Florida Onsite Sewage Nitrogen Reduction Strategies (FOSNRS) project was initiated in 2009. The FOSNRS project implemented a multi-pronged approach to address nitrogen loading from OSTDS to the Florida environment. The FOSNRS project incorporated four primary study areas:

- Task A: Technology evaluation for field testing, test facility design and construction and pilot testing of passive nitrogen reduction systems (PNRS);
- Task B: Field testing of full scale treatment technologies, performance evaluation and cost analyses;
- Task C: Evaluation of nitrogen reduction provided by Florida soils and shallow groundwater;
- Task D: Nitrogen fate and transport modeling and the development of decision support tools for OSTDS planning and management.

A central component of the FOSNRS project was the development, design and field evaluation of both pilot and full scale onsite wastewater nitrogen reduction technologies. The goal of Task B of the FOSNRS project was to develop, design, install and evaluate prototype treatment technologies that are appropriate for residential onsite deployment, are relatively passive in operation and which substantially increase nitrogen reduction over that of conventional OSTDS.

## **1.2 Previous Passive Nitrogen Reduction Study**

FDOH had commissioned an earlier bench scale passive nitrogen removal study to investigate alternative methods to reduce nitrogen from onsite systems. A primary objective was to evaluate systems which operated with limited reliance on pumping, controls and forced aeration (Smith et al., 2008; Smith, 2009a; Smith, 2012). The operational definition for a passive system was established by FDOH in this study, and defined a PNRS as an OSTDS that contains at most only a single liquid pump, no mechanical aerators or other mechanical devices and that uses reactive media for denitrification. The bench scale study provided proof-of concept for a two-stage biofiltration process that met the FDOH criteria for a passive system and removed over 95% of Total Nitrogen from septic tank effluent (Smith et al., 2008; Smith, 2009a; Smith, 2009b; Smith, 2012).

## **1.3 Prioritization and Pilot Testing of Treatment Technologies**

The FOSNRS project started in early 2009 with an evaluation of nitrogen reduction options for OSTDS. FOSNRS Task A included a literature review and classification of nitrogen removal technologies (Hazen & Sawyer, AET and OEC, 2009a), ranking of nitrogen removal systems and prioritization of technologies for testing (Hazen & Sawyer, AET and OEC, 2009b). Two-stage biofiltration received a high ranking and recommendation. A pilot scale passive nitrogen reduction study was therefore undertaken. Multiple pilot scale two-stage biofilters were designed, constructed and tested to further document performance and to develop preliminary design criteria for application of the two-stage process to full scale prototype onsite wastewater systems. The pilot study was conducted over a period of 18 months and indicated that two-stage biofiltration was a relatively simple process that was effective in reducing nitrogen concentrations from onsite wastewater primary effluent. Over 22 biofilters were operated in the pilot work and produced definitive track performance data for multiple design variants of the two-stage biofiltration process. Total nitrogen removals of over 95% were continuously achieved in several of the pilot two-stage biofiltration units treating primary effluent (Hazen & Sawyer and AET, 2014; Hirst, et al., 2014).

## **1.4 Full Scale Prototype PNRS Evaluation at Florida Homes**

The results of FOSNRS Task A and the pilot scale testing provided guidance for the design and performance testing of full scale prototype PNRS at individual Florida home sites, which was the objective of FOSNRS Task B and the subject of this report. The overall goal of FOSNRS Task B was to perform field evaluations of full scale PNRS under actual operating conditions to critically assess nitrogen reduction technologies that were identified in FOSNRS Task A. FOSNRS Task B included a Quality Assurance Project Plan for field testing (Hazen & Sawyer and AET, 2010), field system installation, monitoring and a PNRS Life Cycle Cost Analysis template (Hazen & Sawyer and AET, 2015). This report summarizes the results of the full scale PNRS evaluations conducted under FOSNRS Task B and the Life



Cycle Cost Analysis (LCCA) of the various treatment systems studied. Finally, the report provides summary recommendations for deploying PNRS treatment technologies as one component of a Florida Onsite Sewage Nitrogen Reduction Strategy.



-THIS PAGE INTENTIONALLY LEFT BLANK-

## 2 OBJECTIVES AND SCOPE

The overall goal of FOSNRS Task B was to perform field evaluations of full scale PNRS under actual operating conditions to critically assess nitrogen reduction technologies that were identified for testing in FOSNRS Task A. To accomplish this goal several objectives were identified and met during the study through a series of tasks and subtasks:

- Development of a Quality Assurance Project Plan for field testing of PNRS
- Identification of residential test sites and establishment of homeowner agreements allowing use and access to the site
- Detailed design of a prototype PNRS specific to each test site, or identification of any specific proprietary technology vendors and establishment of vendor agreements as necessary
- Permitting and installation of prototype or proprietary treatment systems at test sites and documentation of any installation issues
- Documentation of installation costs of each prototype or proprietary PNRS
- Monitoring of the performance of each treatment system for nitrogen and other water quality parameters to assess performance
- Monitoring of the energy used and other operational costs associated with PNRS operation
- Monitoring of routine and non-routine maintenance costs to support life cycle economic analysis of each PNRS
- Transfer of PNRS ownership and responsibility to the homeowner for future operation and maintenance or removal of system and restoration of the site, as desired by the homeowner
- Development of this Task B report summarizing the results of the prototype PNRS evaluations, life cycle cost analysis and providing summary recommendations for deploying PNRS as one component of a Florida Onsite Sewage Nitrogen Reduction Strategy.



-THIS PAGE INTENTIONALLY LEFT BLANK-

### 3 SELECTION OF TREATMENT PROCESSES

The selection of treatment processes for full scale evaluation in Task B resulted from a culmination of FOSNRS Task A activities, which included a multistep process to classify, rank and prioritize candidate nitrogen reduction processes followed by pilot evaluations of the top ranked PNRS technologies and processes.

#### 3.1 Task A Ranking and Prioritization

Task A included a literature review of nitrogen reduction processes and technologies and a workshop conducted with the FDOH Research Review and Advisory Committee (RRAC) to classify, rank and prioritize treatment technologies. The workshop presented the nitrogen reduction technology and process classifications, ranking criteria and weighting factors recommended by the project team and solicited input from the stakeholder members of the RRAC. The objective of the workshop was to gain consensus on the ranking and prioritization methodology to be used for subsequent field testing. The outcome was the recommendations presented in the FOSNRS Task A report (Hazen & Sawyer, AET and OEC, 2009b) which are summarized in Table 3-1. Treatment process selection in Task B was guided by the Table 3-1 rankings.

**Table 3-1: Process Systems Recommended for Task B Full Scale Testing  
(Hazen & Sawyer, AET and OEC, 2009b)**

System Rank	Technology/Process	Comments
1	Two-stage (segregated biomass) system: Stage 1: Biofiltration with recycle (nitrification) Stage 2: Autotrophic denitrification with reactive media biofilter	<ul style="list-style-type: none"> <li>• Top ranked system capable of meeting the lowest TN concentration standard</li> <li>• Suitable for new systems or retrofit</li> </ul>
2	Two-stage (segregated biomass) system: Stage 1: Biofiltration with recycle (nitrification) Stage 2: Heterotrophic denitrification with reactive media biofilter	<ul style="list-style-type: none"> <li>• Top ranked system capable of meeting the lowest TN concentration standard</li> <li>• Suitable for new systems or retrofit</li> </ul>
3	Natural system: Septic tank/STU (Drainfield) with in-situ reactive media layers	<ul style="list-style-type: none"> <li>• Lower cost natural system that is untested but appears capable of achieving 75-78% TN removal before reaching groundwater</li> <li>• Suitable for new systems or replacing existing systems at end of useful life</li> </ul>




**Table 3-1 (cont.): Process Systems Recommended for Task B Full Scale Testing (Hazen & Sawyer, AET and OEC, 2009b)**

System	Technology	Comments
4	Natural system: Primary or secondary effluent with drip dispersal	<ul style="list-style-type: none"> <li>• Suitable for reducing TN impacts on groundwater through enhanced TN removal and reduced TN loading on soil</li> <li>• Suitable for new systems or retrofit</li> </ul>
5	Mixed biomass fixed film system with recycle followed by heterotrophic denitrification with reactive media biofilter	<ul style="list-style-type: none"> <li>• High performance aerobic treatment with anoxia for enhanced TN removal followed by second stage heterotrophic denitrification for high nitrogen removal</li> <li>• Suitable for new systems or nitrogen reduction upgrades</li> </ul>
6	Mixed biomass fixed film system with recycle followed by an autotrophic denitrification with reactive media biofilter	<ul style="list-style-type: none"> <li>• High performance aerobic treatment with anoxia for enhanced TN removal followed by second stage autotrophic denitrification for meeting low TN concentration standard</li> <li>• Suitable for new systems or nitrogen reduction upgrades</li> </ul>
7	Mixed biomass integrated fixed film activated sludge system: Suspended growth with recycle	<ul style="list-style-type: none"> <li>• High performance aerobic treatment with recycle for denitrification</li> <li>• Suitable for new systems or nitrogen reduction upgrades</li> </ul>
8	Mixed biomass integrated fixed film activated sludge system: Moving bed bioreactor	<ul style="list-style-type: none"> <li>• High performance aerobic treatment with simultaneous denitrification</li> <li>• Suitable for new systems or nitrogen reduction upgrades</li> </ul>
9	Mixed biomass suspended growth system: Suspended growth sequencing batch reactor	<ul style="list-style-type: none"> <li>• Aerobic treatment</li> <li>• Suitable for new systems or nitrogen reduction upgrades</li> </ul>
10	Membrane process system: Membrane bioreactor (MBR)	<ul style="list-style-type: none"> <li>• Suitable for new systems or nitrogen reduction upgrades</li> </ul>
11	Source separation system: Dry toilet (evaporative or composting)	<ul style="list-style-type: none"> <li>• Eliminates liquid disposal of toilet wastes, eliminating 70-80% of TN from wastewater stream</li> </ul>
12	Source separation system: Urine separating (recovery) toilet	<ul style="list-style-type: none"> <li>• Innovative system that is capable of removing 70-80% of the household TN</li> <li>• Provides potential for sustainable recovery of nutrients</li> </ul>

### 3.2 PNRS Pilot Testing


A pilot test facility was established to evaluate the top ranked PNRS technologies/processes and to develop preliminary design criteria for Task B full scale system prototypes. The pilot facility was located at the University of Florida Gulf Coast Research and Education Center (GCREC) in Wimauma, Florida. Twenty-four in-tank and two in-ground pilot scale biofilters were operated and monitored over a period of 18 months to evaluate nitrogen removal from wastewater primary effluent. The pilot test facility included four groups of two-stage biofiltration systems, with each group encompassing multiple variants of unsaturated biofiltration (Stage 1) followed by saturated biofiltration with reactive media (Stage 2). An overview of the pilot biofilter configuration is shown in Figure 3-1. The results of the pilot testing are summarized here; further details can be found in Hazen & Sawyer and AET (2014).

**Figure 3-1: GCREC Pilot Test Facility Groups**  
(See Table 3-2 for biofilter characteristics)




The first group (Group 1) consisted of in-tank single pass Stage 1 biofilters directly coupled to upflow Stage 2 biofilters as depicted in Figure 3-2. Five single pass Stage 1 biofilters were directly connected to five upflow Stage 2 denitrification biofilters. Target hydraulic loading to Stage 1 biofilters was a surface loading of 3 gallons per square feet per day ( $\text{gal}/\text{ft}^2\text{-day}$ ), which provided a  $5.7 \text{ gal}/\text{ft}^2\text{-day}$  surface loading to Stage 2 biofilters. The monitoring points for Group 1 included influent (STE), Stage 1 effluent and Stage 2 (final effluent).

**Figure 3-2: Flow Schematic for a Single Pass Stage 1 Biofilter Directly Coupled to Upflow Stage 2 Biofilter**



The second group (Group 2) consisted of four in-tank recirculating Stage 1 biofilters where the combined Stage 1 biofilter effluents were collected in a denite feed tank (DFT) which fed four horizontal Stage 2 biofilters (Figure 3-3). The setup allowed parallel testing of various media in Stage 2 biofilters which received the same nitrified influent. Target hydraulic loading to the four Stage 1 recirculating biofilters was a surface loading of  $3 \text{ gal}/\text{ft}^2\text{-day}$  forward flow with a 3:1 recycle ratio of nitrified biofilter effluent to wastewater forward flow. This provided a  $12 \text{ gal}/\text{ft}^2\text{-day}$  surface loading to the Stage 1 biofilters based on total flow. The four horizontal Stage 2 biofilters received composite effluent from the recirculating Stage 1 biofilters, dosed from the DFT. Target hydraulic loading to the horizontal Stage 2 biofilters was a surface loading of  $10 \text{ gal}/\text{ft}^2\text{-day}$ . The monitoring points for Group 2 included the influent (STE), recirculation tank effluent, Stage 1 effluent, DFT and Stage 2 effluent (final effluent).


**Figure 3-3: Flow Schematic for a Recirculating Stage 1 Biofilter and Horizontal Stage 2 Biofilter**



The third group (Group 3) consisted of in-tank vertically stacked Stage 1/Stage 2 biofilters which consisted of single pass biofilters with an upper unsaturated Stage 1 media underlain by Stage 2 media as depicted in Figure 3-4. The vertically stacked biofilters were configured with an upper unsaturated Stage 1 layer, a middle mixed media layer of Southern yellow pine and expanded clay and a saturated lower layer with elemental sulfur media. Three of the vertically stacked biofilters received primary effluent and the fourth (22-VS-SA-12) received nitrified effluent from a Group 1, Stage 1 biofilter. Target hydraulic loading to the four vertically stacked biofilters was a surface loading of 1.1 to 1.2 gal/ft<sup>2</sup>-day. Monitoring points for Group 3 included the influent (STE), middle layer effluent and sulfur effluent (final effluent).




**Figure 3-4: Flow Schematic for an In-tank Vertically Stacked Stage 1/Stage 2 Biofilter System**



The fourth group (Group 4) consisted of in-ground vertically stacked Stage 1/Stage 2 biofilters followed by an additional in-tank Stage 2 biofilter. The single pass in-ground biofilters consisted of an upper unsaturated Stage 1 sand media underlain by Stage 2 lignocellulosic media mixed with sand on an HDPE liner as depicted in Figure 3-5. The effluent collected on the liner was directed to an in-tank saturated Stage 2 sulfur media tank for additional treatment. The denitrified effluent was discharged to the natural soil via an infiltrator trench system. One of the in-ground vertically stacked biofilters received primary effluent and the other received the effluent from an aerobic treatment unit (ATU). Target hydraulic loading to the in-ground vertically stacked biofilters was a surface loading of 0.8 gal/ft<sup>2</sup>-day. Monitoring points for Group 4 included the influent (STE or ATU), Stage 1 layer effluent, liner effluent and sulfur effluent (final effluent).

**Figure 3-5: Flow Schematic for an In-Ground Vertically Stacked Stage 1/Stage 2 Biofilter System**



The twenty-six biofilters in the pilot study consisted of nine in-tank unsaturated Stage 1 biofilters, eleven in-tank saturated Stage 2 biofilters, four in-tank vertically stacked biofilters and two in-ground vertically stacked biofilters characterized in Table 3-2. The unsaturated nitrification (Stage 1) biofilter media tested included expanded clay (EC), clinoptilolite (CL) and sand (SA) in four media depths of 12, 15, 18 and 30 inches. In the Group 1 and 2 tank systems a larger media particle size was used in the upper one third of media depth and smaller particle size in the lower two thirds. The Stage 1 biofilter IDs as summarized in Table 3-2 indicate the biofilter ID (number) type of media (EC, CL or SA) and media depth (12, 15 or 30 inches). The saturated (Stage 2) denitrification biofilters reactive media tested included lignocellulose (LS), from Southern Yellow Pine sawmill waste and elemental sulfur (SU) in various percentages. In addition, one horizontal Stage 2 biofilter was dosed glycerol (GL) as a liquid electron donor. The Stage 2 biofilter IDs as summarized in Table 3-2 indicate the ID (number) type of electron donor (LS, SU or GL) and reactive media percentage (varies). Other media components included oyster shell and limestone as slow release alkalinity supply (Sengupta et al., 2006) and gravel.

**Table 3-2: PNRs Pilot Biofilter Characteristics**

Description	Biofilter & Process Designations							
	Biofilter ID	Media Depth (inches)	Surface Loading Rate (gal/ft <sup>2</sup> -day)	Biofilter ID	Reactive Media (percent)	Media Depth (inches)	Surface Loading Rate (gal/ft <sup>2</sup> -day)	
Group 1: In-tank Single Pass Stage 1 directly connected to Upflow Stage 2	Single Pass Stage 1 Biofilters			Upflow Stage 2 Biofilters				
	1-EC-15	15	3	6-SU-30	30	24	5.6	
	2-EC-30	30		7-LS-50	50			
	3-CL-15	15		8-SU-80	80			
	4-CL-30	30		9-LS-25	25			
	5-CL-30	30		10-LS-30	30			
Group 2: In-tank Recirculating Stage 1 with composited ST1 effluent to Horizontal Stage 2	Recirculating Stage 1 Biofilters			Horizontal Stage 2 Biofilters				
	11-SA-30	30	12	15-SU-80	80	72	10	
	12-EC-30	30		16-SU-30	30			
	13-CL-15	15		17-LS-50	50			
	14-CL-30	30		18-GL	N/A			
Group 3: In-tank Vertically Stacked Single Pass Stage 1 underlain by Stage 2	Single Pass Stage 1 Biofilters			Underlying Stage 2 Biofilters				
	19-VS-SA-12	12	1.1		LS-40	12	1.1	
					SU-100	4		
	20-VS-EC-12				LS-40	12		1.2
					SU-100	4		
	21-VS-CL-12		1.2		LS-40	12		
					SU-100	4		
	22-VS-SA-12	LS-40			12			
		SU-100			4			
Group 4: In-ground Vertically Stacked Singe Pass Stage 1 underlain by Stage 2	Single Pass Stage 1 Biofilters			Stage 2 Biofilters				
	23-VS-SA-18	18	0.8 (STE)		LS-50	9	0.8	
				24-SU-80	80	20		
	25-VS-SA-18	18	0.8 (ATU)		LS-50	9	0.8	
				26-SU-80	80	20		


Note: EC= expanded clay; CL = clinoptilolite; SA= sand; LS = lignocellulose; SU = elemental sulfur; GL = glycerol

### 3.2.1 Groups 1 & 2 Results

**Stage 1 Performance:** The primary effluent supplied to the pilot systems had an average Total Nitrogen of 52.5 mg/L. Nitrogen in primary wastewater effluent is predominately in the form of reduced nitrogen. Total Kjeldahl Nitrogen (TKN) measures reduced nitrogen and is the sum of the two forms of reduced nitrogen: organic nitrogen and ammonia. Aerobic biofilters (Stage 1) convert organic nitrogen to ammonia through ammonification and oxidize ammonia through nitrification. Effluent reduced nitrogen is therefore a good measure of Stage 1 performance. The reduced nitrogen in Stage 1 biofilter effluents are shown in Figure 3-6. Mean TKN levels varied from 2.4 to 4.0 mg/L, with standard deviations of approximately 1 mg/L indicating limited variability in effluent quality. The exception is the 30 inch clinoptilolite recirculating biofilter (14-CL-30), for which the high mean TKN and standard deviation were caused by one TKN result which was possibly a sampling artifact. Mean effluent ammonia nitrogen levels ranged from 0.01 to 0.5 mg/L, with many analyses at or below method detection limits. It is important to achieve low effluent ammonia in the Stage 1 biofilter because ammonia is not expected to be degraded in the anoxic environments of the saturated Stage 2 biofilters. Ammonia in Stage 1 effluent could pass through an anoxic Stage 2 biofilter and contribute to the total nitrogen in the final two-stage biofiltration effluent. Organic nitrogen as well as ammonia in Stage 1 effluent would therefore limit the removal efficiency of total nitrogen in the two-stage system. Verifying low levels of reduced nitrogen species in Stage 1 biofilter effluents is a first step in establishing effective total nitrogen removal with two-stage biofiltration.




**Figure 3-6: Unsaturated Biofilter Effluent TKN Nitrogen (Stage 1)**  
**Mean Influent TN=TKN=52.5 mg/L**




**Stage 2 Performance:** Saturated denitrification biofilters (Stage 2) contain electron donor media to remove oxidized nitrogen. Oxidized nitrogen is the sum of nitrate and nitrite ( $\text{NO}_x\text{-N}$ ), although nitrate typically dominates in biofilter effluents. Effective denitrification biofilters will have low levels of  $\text{NO}_x\text{-N}$  in their effluent. Stage 2 biofilter effluent  $\text{NO}_x\text{-N}$  levels are shown in Figure 3-7. Mean effluent  $\text{NO}_x\text{-N}$  in sulfur biofilter effluents ranged from 0.04 to 0.11 mg/L with standard deviations of similar magnitude. Fluctuations in effluent  $\text{NO}_x\text{-N}$  from the sulfur denitrification process were very limited. The glycerol biofilter provided similar  $\text{NO}_x\text{-N}$  removal performance to the sulfur biofilters. Highly effective  $\text{NO}_x\text{-N}$  removal was also achieved by the horizontal biofilter (17-LS-50) that used Southern Yellow Pine sawmill waste as a lignocellulosic electron donor, producing mean effluent  $\text{NO}_x\text{-N}$  of 0.02 mg N/L. Two upflow lignocellulosic saturated (7-LS-50 and 9-LS-25) biofilters exhibited incomplete  $\text{NO}_x\text{-N}$  removal, with mean effluent  $\text{NO}_x\text{-N}$  of 6.2 and 14.2 mg/L based on three monitoring events. Possible explanations for limited  $\text{NO}_x\text{-N}$  removal in the two upflow lignocellulosic biofilters include low media reactivity, insufficient retention time and biofilter design. Overall, the pilot results verified denitrification biofilter designs that were highly effective in removing  $\text{NO}_x\text{-N}$ .

Figure 3-7: Saturated Biofilter Effluent  $\text{NO}_x\text{-N}$  (Stage 2)




The lignocelulosic biofilter that achieved very effective  $\text{NO}_x\text{-N}$  removal (17-LS-50) used similar lignocelulosic media as the other lignocelulosic biofilters but had a longer retention time. Other investigators have reported highly successful use of *Pinus radiata* (pine softwood) media in denitrification biofilters (Cameron and Schipper, 2010; Schmidt and Clark, 2013; Schmidt and Clark, 2012; Schipper et al., 2010). To further evaluate the effect of retention time,  $\text{NO}_x\text{-N}$  reduction as a function of hydraulic retention time (HRT) for the various saturated lignocelulosic-containing biofilters was plotted to examine any trends (Figure 3-8). While data is limited and the linear correlation is not extremely high, the percent  $\text{NO}_x\text{-N}$  reduction does appear to increase as residence time in the Stage 2 lignocelulosic biofilter increases. These results suggest that lignocelulosic material could be a potential media for saturated anoxic denitrification biofilters, but that designs using the media should incorporate a longer HRT than used in the pilot systems.

**Figure 3-8: Stage 2 Lignocellulosic Biofilters NO<sub>x</sub>-N Reduction with Time**




Total nitrogen in the denitrification biofilter effluents (Stage 2) are shown in Figure 3-9. The effluent from the Stage 2 biofilters is the final effluent of a two-stage system. Stage 2 effluents include organic nitrogen, ammonia and oxidized nitrogen (NO<sub>x</sub>-N). For a two-stage biofiltration system with effective first and second stages, effluent total nitrogen is dominated by dissolved organic nitrogen.

Figure 3-9: Saturated Biofilter Effluent Total Nitrogen (Stage 2)



**Overall Performance of Group 1 and 2 Biofilters:** The mean total nitrogen removal efficiencies of two-stage biofiltration are shown in Figure 3-10. Mean total nitrogen removal efficiencies of two-stage biofilters employing sulfur media and glycerol were greater than 90%, with effluent nitrogen dominated by dissolved organic nitrogen (Figure 3-10). Total nitrogen removal efficiencies of several lignocellulosic biofilters were limited by incomplete  $\text{NO}_x\text{-N}$  removal, resulting in effluent nitrogen dominated by  $\text{NO}_x\text{-N}$ . The pilot testing results verified that several two-stage biofiltration designs could consistently achieve 95 percent total nitrogen removal.

**Figure 3-10: Total Nitrogen Removal Efficiency of Various 2 Stage Biofilter Systems, Organized by Stage 2 Biofilter**




A concern associated with the use of the sulfur biofilters is the effluent sulfate concentration. The U.S. Environmental Protection Agency has established National Secondary Drinking Water Regulations that set non-mandatory water quality guidelines for 15 drinking water contaminants. Secondary standards were established as guidelines to assist public water systems in managing their drinking water for aesthetic considerations. The secondary standard for sulfate is 250 mg/L, and is based on taste. Effluent sulfate levels in the four sulfur-containing biofilters are summarized in Table 3-3. Mean effluent sulfate levels were 325 to 482 mg/L and exceeded the secondary drinking water standard.

**Table 3-3: Effluent Sulfate**

Biofilter	Effluent Sulfate, mg/L				Change in Sulfate Across Biofilter, mg/L			
	Mean	Standard Deviation	Min	Max	Mean	Standard Deviation	Min	Max
15-SU-80	325	33.8	230	450	266	33.7	184	398
16-SU-30	343	55.1	140	490	284	53.7	94	426
8-SU-80	482	46.9	340	650	427	45.1	303	589
6-SU-30	453	46.0	260	560	396	44.5	214	499




Autotrophic denitrification with elemental sulfur can be represented with the following biochemical reaction (Batchelor and Lawrence, 1978; Smith, 2009a):



Based on this equation, for each gram of  $\text{NO}_3\text{-N}$  removed approximately 2.29 grams of sulfur are oxidized and 6.87 grams of sulfate are generated. Sample ports were installed along the length of the Stage 2 biofilters to enable longitudinal profiling of nitrogen species and other water quality parameters. Solute profiles of the Stage 2 sulfur-containing denitrification biofilters showed a significant decline in  $\text{NO}_x\text{-N}$  concentration and increase in sulfate concentration at the entrance region (see Figure 3-11, 3 inches from inlet). It is significant that the sulfate concentration in the biofilter does not increase substantially after the depletion of  $\text{NO}_x\text{-N}$  (and presumably DO). In addition, as depicted in Figure 3-11, applying a lower  $\text{NO}_3\text{-N}$  concentration (red, Day 242 as compared to green, Day 305) to the sulfur biofilter results in a lower sulfate concentration in the final effluent.

Figure 3-11: Solute Profile for Stage 2 Biofilter 8-SU-80



### 3.2.2 Group 3 Results

The performance of the in-tank vertically stacked Stage 1/Stage 2 biofilters was highly variable. Three of the systems treated primary effluent: 19-VS-SA, 20-VS-EC and 21-VS-CL (Table 3-2). The vertically stacked biofilters had variable effectiveness in treating primary effluent, with mean effluent CBOD<sub>5</sub> of 2.5 to 13 before the sulfur layer and 4.5 to 62 mg/L in final effluent. Mean TN was 10 to 27 mg/L before the sulfur layer and 2.6 to 21 mg/L in final effluent. Mean NH<sub>3</sub>-N was 0.28 to 0.55 mg/L before the sulfur layer and 1 to 20 mg/L in final effluent. Reduced nitrogen forms comprised the most significant components of effluent TN in the vertically stacked Stage 1/Stage 2 biofilters treating primary effluent, indicating incomplete nitrification in the unsaturated upper media. Mean NO<sub>x</sub>-N was 7 to 24 mg/L before the sulfur layer and 0.1 to 2.8 mg/L in final effluent. The sulfur layer was highly significant to NO<sub>x</sub>-N reduction in the in-tank vertically stacked Stage 1/Stage 2 biofilters testing both primary effluent and nitrified effluent.

### 3.2.3 Group 4 Results

The in-ground vertically stacked Stage 1/Stage 2 biofilters with additional denitrification tanks were operated separately from the Group 1, 2 and 3 biofilters, as part of a soil and groundwater monitoring task of the FOSNRS project (Task C). These systems were installed and monitored for 523 days. The primary

effluent and aerobic treatment unit effluent which were the influent to the systems had mean total nitrogen concentrations of 65.4 mg/L and 37.3 mg/L, respectively. The system that treated primary effluent produced a mean effluent total nitrogen concentration of 3.5 mg/L,  $\text{NO}_x\text{-N}$  of 0.06 mg/L,  $\text{CBOD}_5$  of 14.3 mg/L and sulfate of 293 mg/L. Mean  $\text{NO}_x\text{-N}$  was 3.6 mg/L from the in-ground stacked Stage 1/Stage 2 biofilter prior to the sulfur tank. The system that treated aerobic treatment unit effluent had mean effluent total nitrogen concentration of 2.6 mg/L,  $\text{NO}_x\text{-N}$  of 0.07 mg/L,  $\text{CBOD}_5$  of 6.2 mg/L and sulfate of 151 mg/L. Mean  $\text{NO}_x\text{-N}$  was 1.4 mg/L from the stacked Stage 1/Stage 2 biofilter prior to the sulfur tank. Both systems indicated that the lignocellosic and sand mixture underlying the Stage 1 biofilter significantly removed nitrogen prior to the denitrification tank containing the sulfur media.

### 3.2.4 Summary

Two-stage biofiltration is aerobic biofiltration followed by anoxic biofiltration. The pilot study results indicated that the two-stage biofiltration process was effective in nitrogen removal from wastewater primary effluent. Ammonia nitrogen was consistently reduced to less than 1 mg/L by the unsaturated in-tank (Stage 1) biofilters in single pass and recirculation mode using expanded clay, clinoptilolite and sand media. Anoxic in-tank (saturated Stage 2) biofilters were operated in upflow and horizontal modes using elemental sulfur and lignocellulose (Southern Yellow Pine sawmill waste) media and glycerol as electron donors. Oxidized nitrogen ( $\text{NO}_x\text{-N}$ ) was consistently reduced to less than 1 mg/L in sulfur containing biofilters, however sulfate concentration in the final effluent in these biofilters at times exceeded the recommended secondary drinking water guideline. Anoxic biofilters with lignocellulosic media did not consistently remove  $\text{NO}_x\text{-N}$  under the conditions of this study, however hydraulic retention time in some of these biofilters appeared to be insufficient. In several of the pilot units, two-stage biofiltration continuously achieved total nitrogen removals of over 95% from primary effluent. The performance of the in-tank vertically stacked Stage 1/Stage 2 biofilters was variable but also demonstrated capability of achieving high total nitrogen reductions in some configurations. The in-ground vertically stacked Stage 1/Stage 2 biofilters with supplemental denitrification tank were effective in nitrogen removal. Oxidized nitrogen ( $\text{NO}_x\text{-N}$ ) was consistently reduced to less than 1 mg/L, and the sulfate concentration in the final effluent was very close to the recommended secondary drinking water guideline.

Overall, the pilot study indicated that two-stage biofiltration appeared to be a viable technology for nitrogen reduction at individual home sites. The results of this pilot study provided guidance for the design of full scale prototype systems at individual Florida home sites, discussed below.



### 3.3 Recommended PNRS for Full Scale Evaluation

#### 3.3.1 Two-Stage Process

“Two-stage biofiltration”, utilizing Stage 1 and Stage 2 biofilters have their basis in the general sequence of biochemical reactions that are utilized for biological reduction of wastewater nitrogen in the classical context: i.e., nitrification followed by denitrification as shown in Figure 3-12.





Figure 3-12: Biological Removal of Wastewater Nitrogen

#### 3.3.2 Stage 1 Nitrification

In the two-stage biofilter process, a Stage 1 porous media biofilter is unsaturated (pore spaces not filled with water) for nitrification. Nitrification is the term used to describe the two-step biological process in which ammonia is oxidized to nitrite and nitrite is oxidized to nitrate. Septic tank effluent (primary effluent) is applied to the top of the first stage media, resulting in a downward percolation of wastewater over and through the porous media biofilter bed. The unsaturated pore spaces in the first stage media allow air to reach microorganisms attached to the media surfaces, enabling aerobic biochemical reactions to occur. The significant target reactions in Stage 1 are hydrolysis of particulate matter, aerobic oxidation (by heterotrophic microorganisms that oxidize organic material and reduce biochemical oxygen demand), ammonification of organic nitrogen (releasing ammonia) and nitrification (biochemical conversion of ammonia to nitrite and nitrate by autotrophic bacteria). The goal of Stage 1 biofiltration is to oxidize the reduced forms of nitrogen (i.e. organic nitrogen and ammonia); the concentrations of organic and

ammonia nitrogen in Stage 1 effluent are the primary metric by which to assess performance. The goal of Stage 1 is to produce an effluent where most of the wastewater nitrogen has been converted to nitrate, and where organic nitrogen and ammonia levels are low. The Stage 1 effluent with its high nitrate concentration is then passed on to the Stage 2 biofilter as shown in Figure 3-13.


**Figure 3-13: Stage 1 Single Pass Process Flow Diagram**



### 3.3.3 Stage 1 Pre-Denitrification with Recirculation

Stage 1 biofilters with recirculation provide an opportunity for pre-denitrification. As discussed in the previous section, most of the wastewater nitrogen has been converted to nitrate in the Stage 1 effluent. With recirculation of Stage 1 effluent, nitrified effluent produced in the Stage 1 biofilter is recirculated back to an anoxic holding tank where it is mixed with incoming wastewater (Figure 3-14) providing an opportunity for biological denitrification to occur. The organic substrate in the influent wastewater provides the electron donor (organic carbon) for oxidation reduction reactions using nitrate. The biological reduction of nitrate to nitrogen gas is termed denitrification. The removal of oxidized nitrogen (nitrate and nitrite) in the recirculated nitrified effluent by biological denitrification contributes to the removal of nitrogen prior to Stage 2.

**Figure 3-14: Stage 1 Recirculation Process Flow Diagram**



### 3.3.4 Stage 2 Denitrification

The goal of the Stage 2 biofilter is to remove oxidized nitrogen (nitrate and nitrite) by biological denitrification. The Stage 2 biofilter contains “reactive media” which provides the electron donor needed for denitrification, and it is saturated (pore space is filled with water) to prevent oxygen ingress and promote anoxic conditions. Denitrification in the Stage 2 biofilter occurs by two general biochemical classifications, depending on the electron donor and the microorganisms involved. Autotrophic denitrifying bacteria utilize inorganic electron donors such as iron or sulfur for denitrification, while heterotrophic denitrifying bacteria utilize organic carbon as the electron donor. Stage 2 media must satisfy numerous objectives including: reactivity, longevity, physical integrity, availability and cost. Literature reviews identified candidate media that were well suited for Stage 2 media as elemental sulfur and lignocellulosic materials from growth of woody plants (Hazen & Sawyer, AET and OEC, 2009a; Smith et al., 2008).

Various process designs for Stage 2 biofilters were evaluated based on the pilot work including: simultaneous nitrification/denitrification in unsaturated or partially unsaturated biofilters, use of denitrification biofilters with mixed heterotrophic and autotrophic media, use of sequential heterotrophic and autotrophic denitrification biofilters, use of vertically stacked single pass biofilter systems with upper unsaturated layers, underlying saturated layers with denitrification media and partially saturated intermediate layers containing denitrification media.

## 3.4 Full Scale Prototype Design Concepts

The results of the pilot work provided a preliminary basis for the design of the full scale prototype biofiltration systems to be evaluated at individual home sites in Task B. Design recommendations for the single family home prototype biofiltration systems generally followed the applied loading rates, media

types, media particle sizes, media depth and media size configurations of the most successful biofilters used in the pilot work. Several modifications were recommended based on the pilot scale results, including:

- Stage 1 media grain size recommendations were increased due to the clogging experienced at the end of the pilot study at the higher applied hydraulic loading rates;
- Biofilter volume was increased for Stage 2 lignocellulosic biofilters to increase water residence time and denitrification performance; and
- A dual media Stage 2 biofilter design with lignocellulosic preceding the sulfur media was recommended to lower effluent sulfate concentrations.

The recommendations are process based and focus on factors and parameters that provide effective biological treatment in varied biofilter configurations. The pilot work results were also used to evolve prototype system designs to address secondary treatment objectives. The effluent sulfate levels in elemental sulfur-containing denitrification biofilters may be of concern in some locations. Therefore, the concept of using combined media in Stage 2, with lignocellulosic media preceding sulfur, evolved in an attempt to lower effluent sulfate levels. The design recommendations can also be used to derive hybrid designs that couple biofilters in a manner not specifically tested in the pilot study. Table 3- 4 provides the basic design recommendations used for the full scale prototype PNRS designs.

**Table 3-4: Preliminary Recommendations Used for Full Scale Prototype PNRS Design**

**Stage 1 Unsaturated Recirculating Biofilters**

Media	Hydraulic Loading Rate, gal/ft <sup>2</sup> -day		Recycle Ratio R:Q	Total Media Depth, inch	Media Stratification and Particle Size Distribution		
	Metered Flow	Code Flow			Layer	Depth, inch	Particle Size Spec, mm
Expanded Clay	≤ 3.0	≤ 6.0	3:1	≥ 24	Upper	≥ 10	≥6 (1/4")
					Lower	≥ 14	≥4 (3/16")
Sand	≤ 3.0	≤ 6.0	3:1	≥ 24	Upper	≥ 10	E.S. ≥ 2 U.C.≤3
					Lower	≥ 14	E.S. ≥ 1 U.C.≤3
Oyster shell	Mixed with expanded clay or sand as needed for alkalinity adjustment						0.5 - 5

**Stage 1 Unsaturated Single Pass Biofilters**

Media	Forward Flow Hydraulic Loading Rate, gal/ft <sup>2</sup> -day		Total Media Depth, inch	Media Stratification and Particle Size Distribution		
	Metered Flow	Code Flow		Layer	Depth, inch	Particle Size Spec, mm
Expanded Clay	≤ 3.0	≤ 4.0	≥ 24	Upper	≥ 10	≥6 (1/4")
				Lower	≥ 14	≥4 (3/16")
Sand	≤ 3.0	≤ 4.0	≥ 24	Upper	≥ 10	E.S. ≥ 2 U.C.≤3
				Lower	≥ 14	E.S. ≥ 1 U.C.≤3
Oyster shell	Mixed with expanded clay or sand as needed for alkalinity adjustment					0.5 - 5

**Stage 2 Saturated Biofilters**

Media	%	Total Media Depth, inch	Empty Bed Residence Time, hour	Media Particle Size Distribution
				Particle Size Spec, mm
Elemental Sulfur	≥ 50	≥ 24	≥ 30	2.0 - 3.36 <0.5% fines
Oyster shell	0-20 <sup>1</sup>			0.5 - 5
Lignocellulosic media	50-100	≥ 24	≥ 120	1 - 30

**Table 3-4 (cont.): Preliminary Recommendations Used for Full Scale Prototype PNRs Design**

**Vertically Stacked Biofilters**

Influent	Hydraulic Loading Rate, gal/ft <sup>2</sup> -day		Media Layer	Media Layer Depth, inch	Media	Media Stratification and Particle Size
	Metered Flow	Code Flow				Particle Size Spec, mm
Septic tank effluent		In-ground 0.8 - 1.2 (depending on soil)	Upper	≥ 18	Slightly Limited Sand	Clean sand < 1% fines
			Lower	≥ 8	50% Ligno 50% Sand	Ligno = 1 - 30
	In-tank ≤ 3.0	In-tank ≤ 4.0	Upper	≥ 24	Expanded Clay or filter sand	≥6 (1/4") E.S. ≥ 2 U.C. ≤3
			Lower	≥ 8	100% Ligno	1-30

<sup>1</sup> As needed for alkalinity adjustment

Note: E.S. = effective size; U.C. = uniformity coefficient

### 3.4.1 Surface Hydraulic Loading Rates

Two-stage biofiltration conducted in the pilot work demonstrated the capability to consistently achieve total nitrogen removals of over 95 percent from primary effluent at the tested design loading rates which were used as the basis for design of the full scale systems. The rates in the pilot studies were actual measured wastewater flows, so a hydraulic loading rate adjustment was recommended when using flows derived from Florida code, which are typically higher than actual flows. Table 3-4 lists recommended loading rates for both metered flows and code flows for the prototype Stage 1 biofilters.

### 3.4.2 Media Type

The pilot work demonstrated the capability of Stage 1 aerobic biofilters to continuously achieve TKN removals of over 95% from primary effluent using expanded clay, clinoptilolite and sand media. Expanded clay was the least expensive and most readily available Stage 1 media evaluated and was recommended for in-tank Stage 1 biofilters, either as a separate Stage 1 biofilter or as the top layer of in-tank vertically stacked Stage 1/Stage 2 biofilters.

Anoxic biofilters with elemental sulfur media consistently reduced oxidized nitrogen (nitrate and nitrite) to less than 1 mg/L and appeared to provide a suitable electron donor media for full scale Stage 2 denitrifying biofilters. Anoxic biofilters containing lignocellulosic media (Southern yellow pine) were also capable of achieving high NO<sub>x</sub>-N reductions in the conditions of the pilot work, but overall performance

was variable and not equal to the sulfur biofilter performance.  $\text{NO}_x\text{-N}$  reductions appeared to be limited by water retention time in denitrification biofilters containing lignocellulosic media. The pilot studies also demonstrated that biofilters with vertically stacked Stage 1/Stage 2 media configurations were capable in some configurations of achieving high total nitrogen reductions. Lignocellulosic media is relatively inexpensive and a readily available waste byproduct. Elemental sulfur is used as a fertilizer and sold in agricultural supply stores. It is more expensive than lignocellulosic media, but very effective in smaller volumes. Both Stage 1 and sulfur Stage 2 biofilters may need oyster shell or other slow release alkalinity adjustment material mixed with the primary media where wastewater alkalinity is low.

In-ground stacked Stage 1/Stage 2 biofilter systems will typically use native soil materials as media, if suitable. The Stage 1 layer should consist of a slightly limited sand with less than 1% fines. The Stage 2 layer should be a mixture of lignocellulosic media and the same sand. A media mixture of 50% lignocellulosic and 50% sand worked well in the pilot testing.

### **3.4.3 Tankage**

Tankage specifically designed for biofiltration is not readily available in Florida. The Stage 1 biofilter tank typically requires an outlet positioned near the bottom of the tank to allow unsaturated operation. In addition, for long term operation and maintenance, easy access to the surface of the biofilter for maintenance activities is required. A tank with a hinged, lightweight cover which provides access to the entire upper surface area of the biofilter is recommended.



## 4 Full Scale Prototype PNRS Evaluations: Materials and Methods

Activities prior to installation of full scale prototype PNRS included: site identification and selection, wastewater characterization, process technology identification and selection, completion of final design and notification including applicable permitting to DOH. Operation and monitoring included: monitoring of flowrate or volume treated; energy; media consumption; chemical and microbiological analyses; and routine and non-routine maintenance.

### 4.1 Full Scale PNRS Demonstration Sites


Over sixty sites were evaluated to identify individual homeowner sites for their suitability for establishing full scale PNRS technology testing. Criteria considered in the suitability analysis included: homeowner willingness to host treatment system, site access, number of residents and continuousness of occupancy, power supply, site security, adequate space, access for monitoring and maintenance, participation in previous or concurrent studies and pre-existing treatment technologies. The homeowner and/or system users were surveyed on home occupancy and use characteristics. Table 4-1 provides a summary by County of the number of sites evaluated and agreements established.

**Table 4-1: Site Evaluation by County**

<b>County</b>	<b>No. of Sites Evaluated</b>	<b>No. of Agreements Established</b>
Charlotte	12	0
Hernando	1	0
Hillsborough	4	3
Lake	1	0
Lee	4	1
Marion	8	3
Orange	2	0
Polk	3	1
Sarasota	13	0
Seminole	8	6
Wakulla	4	4
<b>Total</b>	<b>60</b>	<b>18</b>



**Figure 4-1: Map of Evaluated Field Sites**



Installation of full scale prototype PNRS technologies for nitrogen reduction of residential onsite wastewater was completed at seven of the evaluated sites (see Figure 4-1). The Task B Quality Assurance Project Plan (Hazen & Sawyer and AET, 2010) documents the objectives, monitoring framework, sample frequency and duration and analytical methods to be used at the test sites. Table 4-2 summarizes the characteristics of each test site.

**Table 4-2: Test Site Characteristics**

Test Site	County	Age of Existing System(s) (yrs.)	No. of Residents	No. of Bedrooms	Building Area (ft <sup>2</sup> )	64E-6 <sup>1</sup> Design Flow (gpd)
BHS-1	Wakulla	14	4	3	1200	300
BHS-2	Hillsborough	13	2	3	2542	400
BHS-3	Seminole	23	2	5	4940	580
BHS-4 <sup>2</sup>	Seminole	40 & 6	5	4	2517	400
BHS-5	Seminole	33	3	5	3315	500
BHS-6	Wakulla	2	4	3	1200	300
BHS-7	Marion	5	2	3	2112	300

<sup>1</sup>per FAC 64E-6.008 Table I

<sup>2</sup>Site had two existing OSTDS

## 4.2 System Types and Configurations

The seven installed prototype PNRS for full scale evaluation included both in-tank and in-ground two-stage biofilter systems. Various hydraulic configurations for Stage 1 biofilters were tested including: Stage 1 single pass (SP), Stage 1 with internal recirculation flow to spray nozzles located above the Stage 1 media (R internal) and Stage 1 with recirculation to a recirculation tank (R tank). The PNRS that incorporated multiple hydraulic configurations for testing included flow splits on the pump discharge line with applicable valves to isolate and test a specific hydraulic configuration. The Stage 1 SP configuration did not incorporate any recycle of Stage 1 effluent; therefore 100 percent of the flow was discharged to the Stage 2 biofilter inlet. The Stage 1 R internal configuration split the flow between the Stage 2 biofilter inlet and the spray nozzles located above the Stage 1 media for dispersal. The R tank configuration split the flow between the Stage 2 biofilter inlet and the recirculation tank inlet. The recycled nitrified effluent was mixed with incoming septic tank effluent in both recycle configurations either within the Stage 1 biofilter (R internal) or within the recirculation tank (R tank). Stage 1 in-tank biofilters that received flow by gravity utilized a distribution box (d-box) within the Stage 1 tank to allow adjustment and even distribution of flow to the perforated distribution pipes.

Stage 2 configurations included lignocellulosic media biofilters alone or dual media biofilter configurations where lignocellulosic media was followed by sulfur media. In the dual media Stage 2 biofilters, the lignocellulosic media was referred to as Stage 2a and the sulfur media was referred to as Stage 2b. Table 4-3 summarizes the full scale prototype system design characteristics. Process flow diagrams (Figure 4-2 through Figure 4-8) are provided for each of the seven prototype systems.

Design and construction details were presented previously in the FOSNRS Task B.6 System Installation Reports, and the system monitoring results were presented previously in the FOSNRS Task B.7 Field Systems Monitoring Reports; additional details can be found in these documents. The main section of the System Installation Report for each prototype PNRS is included in Appendix A. The main section of the final Field System Monitoring Report summarizing the results for each system is included in Appendix B.



-THIS PAGE INTENTIONALLY LEFT BLANK-



Table 4-3: Summary of Prototype PNRS Design Characteristics


System ID	Location (County)	System Description	Hydraulics	64E-6 <sup>1</sup> Design Flow (STE)	Stage 1 Biofilter Design Characteristics						Stage 2 Biofilter Design Characteristics							Dispersal
					Design HLR (gal/ft <sup>2</sup> -d)	Recirculation Rate	Tankage	Media	Media Size	Media Depth	Design HLR (gal/ft <sup>2</sup> -d)	Tankage	Media	Media Size	Media Depth	Media Volume (ft <sup>3</sup> )	% Reactive Media	
BHS-1	Wakulla	Proprietary: Stage 1 Aerocell Stage 2 Nitrex	Pumped with Stage 1 internal recirculation	300		R:Q = 10:1	Aerocell Model# ATS-SCAT8-AC-C500; 1050 gallon fiberglass	Open Cell Foam Cubes	8 in <sup>3</sup> each 85 ft <sup>3</sup> total	~28"	5.1	1500 gallon concrete tank	Nitrex	Wood chips and sawdust	~40"	195	100%	STU with Chambers
BHS-2	Hillsborough	In-tank two stage biofilter with stage 1 recirculation, dual media stage 2; lignocellulosic (2a) followed by elemental sulfur (2b)	Pumped with both Stage 1 recirculation to tank and Stage 1 internal recirculation tested	400		R:Q = 3:1	300 gallon recirculation tank	None	NA	NA	11.1	2 compartment 1500 gallon concrete tank	Lignocellulosic; Southern Yellow Pine sawmill waste	Sawdust	42"	126	100%	STU with PTI bundles
					10.8		1050 gallon concrete tank	Expanded Clay	1/4" top layer	10"	22.2		Elemental Sulfur	0.1" Pastille pellets	24"	36	90%	
									3/16" bottom layer	20"								
BHS-3	Seminole	In-ground stacked biofilter, single pass stage 1 over stage 2a with supplemental stage 2b tank; stage 2a lignocellulosic/sand mixture; stage 2b elemental sulfur tank	Pumped with subsurface drip irrigation STE application	580	0.8	N/A	none, in-ground	fine sand, typical mound fill	fine sand	18"	0.8	in-ground liner underlying Stage 1	Lignocellulosic; blended waste wood	Wood chips	9"	273	50%	subsurface drip irrigation of zoysia turfgrass
											15.1	1050 gallon concrete tank	Elemental Sulfur	0.1" Pastille pellets	12"	38.5	90%	
BHS-4	Seminole	In-tank two stage biofilter with single pass stage 1, dual media stage 2; lignocellulosic (2a) followed by elemental sulfur (2b)	Gravity	400	3.5	N/A	2800 gallon concrete tank	Expanded Clay	1/4" top layer	10"	11.1	2 compartment 1500 gallon concrete tank	Lignocellulosic; blended waste wood	Wood chips	42"	126	100%	STU with Chambers
									3/16" bottom layer	20"	22.2		Elemental Sulfur	0.1" Pastille pellets	18"	27	90%	
BHS-5	Seminole	In-tank two stage biofilter with recirculation stage 1, dual media stage 2;lignocellulosic (2a) followed by elemental sulfur (2b)	Pumped with both Stage 1 internal recirculation and single pass tested	500	6.4	R:Q = 3:1	1500 gallon plastic tank	Expanded Clay	1/4" top layer	12.8"	13.9	2 compartment 1500 gallon concrete tank	Lignocellulosic; blended waste wood	Wood chips	42"	126	100%	STU with standard gravel bed (perforated corrugated pipe)
									3/16" bottom layer	21"	27.8		Elemental Sulfur	0.1" Pastille pellets	18"	27	90%	
BHS-6	Wakulla	In-tank vertically stacked biofilter, single pass stage 1 over stage 2a with supplemental stage 2b tank; stage 2a lignocellulosic; stage 2b elemental sulfur tank	Pumped with spray nozzle application (no recirculation)	300	4.5	N/A	1650 gallon concrete tank	Expanded Clay	1/4"	30"	4.5	underlying Stage 1	Lignocellulosic; blended waste wood	Wood chips	12"	67	100"	STU with Chambers
											15	1500 gallon concrete tank with wall	Elemental Sulfur	0.1" Pastille pellets	12"	20	90%	
BHS-7	Marion	In-ground stacked biofilter, single pass stage 1 over stage 2 lignocellulosic	Pumped low pressure distribution	300	0.83	N/A	none, in-ground	native Candler sand	fine sand	24"	0.83	in-ground liner, underlying Stage 1	Lignocellulosic; blended waste wood	Wood chips	12"	362	100"	Around the perimeter of the liner

<sup>1</sup>per FAC 64E-6.008 Table I




The BHS-1 system (Figure 4-2) consisted of a 1,500 gallon two chamber concrete tank with a 1,000 gallon primary treatment tank (primary chamber) and a 500 gallon pump chamber (pump chamber); an Aerocell™ unsaturated foam media filter and a 1,500 gallon single chamber up-flow tank containing Nitrex™ media. Treated effluent from the Nitrex™ unit is discharged to a soil treatment unit (drainfield) consisting of four Infiltrator trenches. The Aerocell™ effluent flows into an adjustable split recirculation device which allows for a portion (up to a 10:1 recycle ratio R:Q) of the effluent to recycle back to the pump chamber. The recycle ratio was initially set at 5:1; however in order to optimize nitrification the recycle ratio was increased to 10:1 by the vendor following the first sample event. While this system consisted of proprietary components, it was considered a prototype as a PNRS.

**Figure 4-2: BHS-1 Process Flow Diagram**




The BHS-2 prototype PNRS (Figure 4-3) consisted of a 1,050 gallon two chamber concrete primary tank; 300 gallon concrete recirculation tank; 900 gallon concrete Stage 1 unsaturated expanded clay media biofilter; 300 gallon concrete pump tank and 1,500 gallon two chamber concrete Stage 2 saturated media (lignocellulosic followed by sulfur) biofilter. The treated effluent is discharged into the existing mounded drainfield (P.T.I.™ bundles). The Stage 1 effluent flow splits, which allows for a portion (3:1 recycle ratio R:Q) of the effluent to recycle. The system was tested with two modes of recycle operation: Stage 1 with recirculation back to the recirculation tank (R tank) and Stage 1 with recirculation back to spray nozzles located above the surface of the Stage 1 media (R internal).

**Figure 4-3: BHS-2 Process Flow Diagram (R tank)**



The BHS-3 prototype system (Figure 4-4) consisted of a 1,500 gallon two chamber concrete primary treatment tank; a 600 gallon concrete septic tank effluent (STE) dose tank; a two zone Perc-Rite™ drip application system and a 1,050 gallon concrete tank enclosing a Stage 2 saturated sulfur media biofilter. The first zone of the drip system applied primary effluent to the top of a Stage 1&2a lined drip zone (STE Zone) consisting of fine sand (Stage 1) overlying a 50/50 mixture of lignocellulosic/sand (Stage 2a) on a sloped liner with an underdrain for effluent collection and discharge to the Stage 2b sulfur biofilter. The second drip zone received final treated effluent from Stage 2b for landscape irrigation and dispersal.


**Figure 4-4: BHS-3 Process Flow Diagram**



The BHS-4 prototype PNRS (Figure 4-5) consisted of a 1,200 gallon concrete primary tank; a 2,800 gallon concrete tank that houses a Stage 1 unsaturated expanded clay media biofilter; and 1,500 gallon two chamber concrete tank that houses a Stage 2 saturated dual media (2a & 2b) biofilter. The treated effluent is discharged into a new soil treatment unit consisting of four Infiltrator chamber trenches. The 1,200 gallon primary tank is located on the west side of the dwelling and also received flow from a second primary tank serving the east side of the dwelling. Because of the topography at this site, wastewater flow through the PNRS was accomplished by gravity.




**Figure 4-5: BHS-4 Process Flow Diagram**



The BHS-5 PNRS (Figure 4-6) consisted of a 1,350 gallon concrete primary tank; a 1,500 gallon plastic tank housing a Stage 1 unsaturated expanded clay media biofilter; a 300 gallon concrete pump tank and a 1,500 gallon two chamber concrete tank housing a Stage 2 saturated dual media (2a & 2b) biofilter. The treated effluent is discharged into the existing soil treatment unit which is of standard gravel bed geometry. The Stage 1 effluent flow splits, which allows for a portion (3:1 recycle ratio R:Q) of the effluent to recycle. The system was tested with two modes of operation: Stage 1 single pass and Stage 1 with internal recirculation to spray nozzles located above the surface of the Stage 1 media.


**Figure 4-6: BHS-5 Process Flow Diagram (R Internal)**



The BHS-6 prototype system (Figure 4-7) consisted of a 1,500 gallon concrete primary tank; 275 gallon pump tank; a 1,650 gallon concrete tank housing a vertically stacked Stage 1 over a Stage 2a media biofilter (expanded clay over lignocellulosic) and a 1,500 gallon single chamber tank housing a Stage 2b saturated sulfur media biofilter. The treated effluent is discharged into the existing soil treatment unit, four Infiltrator chamber trenches.




**Figure 4-7: BHS-6 Process Flow Diagram**



The BHS-7 PNRS prototype (Figure 4-8) consisted of a 900 gallon concrete primary tank; 300 gallon concrete pump tank; low-pressure distribution network and an in-ground Stage 1 unsaturated sand biofilter directly above a lined Stage 2 lignocellulosic media biofilter. The primary treated effluent was expected to percolate through the Stage 1 native fine sand media for nitrification into the liner filled with lignocellulosic media for denitrification, and then discharge into the soil around the perimeter of the liner by overflowing the liner. As will be explained further in Section 5, effluent movement did not appear to occur as expected with this system.

**Figure 4-8: BHS-7 Process Flow Diagram**



### 4.3 Monitoring

Each of the seven prototype PNRS demonstration systems were evaluated over an approximately 18 month period, with formal sampling events occurring bi-monthly. This section presents the monitoring methods utilized in the PNRS evaluations.

#### 4.3.1 Flowrate Measurement

The source of wastewater supplied to each of the PNRS prototype systems was primary effluent (STE) from the single family residence. The household daily wastewater flow was estimated from the potable water meter and system process flow meters (as applicable). Table 4-4 summarizes the location(s) of the flow measurement devices for each system. Flowrates for the systems with timed dosing were calibrated at initial start-up. The flowrates were measured and recorded at each monitoring event.

**Table 4-4: Flow Measurement Devices**

<b>System</b>	<b>Meter 1 Household Water Use (Q)</b>	<b>Meter 2 Stage 1 Forward Flow (Q)</b>	<b>Meter 3 Stage 1 Recycle (R)</b>	<b>Meter 4 Stage 2 Forward Flow (Q)</b>
BHS-1	Private well, meter installed on water line prior to entering residence		Combined Aerocell Flow (Q+R), meter installed on pump tank discharge line	
BHS-2	Private well, meter installed on water line prior to entering residence		Combined pump flow (Q+R), meter installed on pump tank discharge line prior to Q and R flow split	Stage 2 forward flow (Q), meter installed on pump tank discharge line following Q and R flow split
BHS-3	Public utility, meter located on water line to property	Combined pump flow (STE + BIO drip zones), meter installed in drip system hydraulic unit prior to zone split		Treated effluent drip zone flow (Q), meter installed on zone 2 feed line following hydraulic unit
BHS-4	Private well, meter installed on water line prior to entering residence			
BHS-5	Private well, meter installed on water line prior to entering residence		Stage 1 recirculation flow (R), meter installed on pump tank discharge R line	Stage 2 forward flow (Q), meter installed on pump tank discharge Q line
BHS-6	Private well, meter installed on water line prior to entering residence	Stage 1 forward flow (Q), meter installed on pump tank discharge line		
BHS-7	Private well, meter installed on water line prior to entering residence	Stage 1 forward flow (Q), meter installed on pump tank discharge line		

#### 4.3.2 Water Quality

The prototype PNRs were designed to include sampling of the system influent, Stage 1 biofilter effluent and Stage 2 biofilter effluent as a minimum. The BHS-1 and BHS-2 systems included an additional sampling location which was the holding tank for Stage 1 recirculated effluent which provided the opportunity for pre-denitrification. Systems BHS-2, -3, -4, -5 and -6 included dual Stage 2 media.

Therefore the lignocellulosic media (Stage 2a) effluent which preceded the sulfur media (Stage 2b) was also sampled.

**Table 4-5: Water Quality Monitoring Locations**

Sample ID	A	B	C	D	E
System	System Influent	Recirculation Tank Effluent	Stage 1 Biofilter Effluent	Intermediate Stage 2a Effluent	Stage 2b Final Effluent
BHS-1	X	X	X		X
BHS-2	X	X	X	X	X
BHS-3	X		X	X	X
BHS-4	X		X	X	X
BHS-5	X		X	X	X
BHS-6	X		X	X	X
BHS-7	X		X		X

In addition, stainless steel drivepoint samplers were installed along the vertical depth of some of the Stage 2 biofilters to enable vertical profiling of nitrogen species and other water quality parameters. Solute profiles of Stage 2 denitrification biofilters were collected intermittently throughout the study period in conjunction with the sample events.

Sampling was performed using a peristaltic pump to collect sufficient sample volume into analysis-specific containers which were supplied by the certified analytical laboratory and contained the appropriate preservatives. These containers were labeled, placed in coolers and transported on ice to the analytical laboratory. Each sample container was secured in packing material as appropriate to prevent damage and spills and was recorded on chain-of-custody forms supplied by the laboratory.

Field parameters were measured using a HACH 40D multimeter and portable electronic probes and included temperature (Temp), dissolved oxygen (DO), oxidation-reduction potential (ORP), pH and specific conductance (Table 4-6).

**Table 4-6: Field Parameter Analyses**

Analyte	Method
Temperature	Hach temperature probe and meter
pH	Hach pH electrode and meter
Specific Conductance	Hach specific conductance probe and meter
DO	Hach luminescence DO probe and meter
ORP	Hach ORP probe and meter

The influent, intermediate and effluent samples were analyzed by the laboratory for the parameters listed in Table 4-7. Sulfate (SO<sub>4</sub>) and hydrogen sulfide (H<sub>2</sub>S) analyses were only conducted on influent and effluent samples for the Stage 2 biofilters containing sulfur media. Analytical methods and detection limits for these analyses are also listed in Table 4-7. Additional details of sampling methods and QA/QC can be found in Hazen & Sawyer and AET (2010) and in the system monitoring reports (Appendix B).

**Table 4-7: Laboratory Analyses Methods**

Analytical Parameter	Method of Analysis	Laboratory Detection Limit
Total Alkalinity as CaCO <sub>3</sub>	SM 2320B	2 mg/L
Total Kjeldahl Nitrogen (TKN)	EPA351.2	0.05 mg/L
Ammonia Nitrogen (NH <sub>3</sub> -N)	EPA350.1	0.01 mg/L
Nitrate/Nitrite Nitrogen (NO <sub>x</sub> -N)	EPA353.2	0.01 mg/L
Carbonaceous BOD (CBOD <sub>5</sub> )	SM 5210B	2 mg/L
Total Suspended Solids (TSS)	SM 2540D	1 mg/L
Volatile Suspended Solids (VSS)	EPA 160.4	1 mg/L
Total Organic Carbon (TOC)	SM5310B	0.06 mg/L
Chemical Oxygen Demand (COD)	EPA 410.4	10 mg/L
Total Phosphorus (TP)	SM 4500PE	0.01 mg/L
Orthophosphate as P (Ortho P)	EPA 300.0	0.01 mg/L
Fecal Coliform (fecal)	SM9222D	1 ct/100mL
E.coli	SM9223B	2 ct/100mL
Sulfate (SO <sub>4</sub> )	EPA300.0	0.2 mg/L
Hydrogen Sulfide Unionized (H <sub>2</sub> S)	SM4500S F	0.01 mg/L
Sulfide	SM4500S F	0.1 mg/L

#### 4.3.3 Energy Consumption

Energy consumption was monitored for each prototype PNRS using an electrical meter as detailed in Table 4-8. The electrical meter records the cumulative power usage of the system in kilowatt-hours. The power usage of the system is primarily due to the single pump, although a small amount of power is used by the control panel itself. Flow through the BHS-4 PNRS was accomplished by gravity due to the topography at that site, so no power was used by the PNRS. However, the home originally had two OSTDS, and a small pump was used to transfer flow from the second system to the PNRS.

**Table 4-8: Energy Consumption Monitoring Location**

System	Meter Location
BHS-1	Installed on the electrical line dedicated to the system control panel
BHS-2	Installed on the electrical line dedicated to the system control panel
BHS-3	Installed on the electrical line dedicated to the system control panel
BHS-4	PNRS flow was by gravity, small pump used to transfer flow from second OSTDS
BHS-5	Installed on the electrical line dedicated to the system control panel
BHS-6	Installed on the electrical line dedicated to the system control panel
BHS-7	Installed on the electrical line dedicated to the low pressure distribution pump

#### 4.3.4 Operation and Maintenance

Overall, the prototype PNRS are passive and required little operation and maintenance (O&M). The systems with Stage 1 recirculation require slightly more O&M than single pass systems. The dual drip system required greater O&M than any of the other systems. Performance verification and monitoring should be performed routinely, as required by permitting agencies and summarized in Table 4-9. The Stage 2 media are reactive, and therefore must be replenished when depleted.

**Table 4-9: General Operation & Maintenance**

System Component	General Maintenance Action	General Frequency
Primary (septic) tank	Pump-out to remove solids	1 time every 3-5 years
	Clean effluent screen	1-2 times annually
	Check water level within the tank	1-2 times annually
Pump tank	Pump-out to remove solids	Same frequency as septic tank
	Check water level within the tank	1-2 times annually
Distribution box	Check for debris, equalized flow, pipe placement	1-2 times annually
	Check water level within the box	1-2 times annually
Stage 1 biofilter	Check for clogging or ponding (rake if required)	1-2 times annually
	Check water level within the biofilter	1-2 times annually
Pump	Check dose volume	1-2 times annually
	Lubricate motor according to manufacturer's instructions	1-2 times annually
Float switches	Check register within control panel	1-2 times annually
Stage 2 biofilter	Check reactive media Replenish reactive media as needed	Check Annually
	Check water level within the biofilter	1-2 times annually
Soil Treatment Unit (drainfield)	Check for odors, ponding, etc.	1-2 times annually

## 5 Full Scale Prototype PNRS Evaluations: Results

Flow rate, temperature, water quality, operation and maintenance, energy use and media consumption results for the seven installed PNRS prototypes for full scale evaluation are presented in this section. Table 5-1 summarizes the operating period for each system.

**Table 5-1: Test System Operating Periods**

System	Stage 1 Mode of Operation <sup>2</sup>	System start-up date	Monitoring end date	Experimental days	Period of days
BHS-1 <sup>1</sup>	R tank	Jun 10, 2011	Jan 24, 2013	594	594
BHS-2	R tank	Sep 25, 2012	Aug 7, 2013	0 through 316	316
	R internal	Aug 7, 2013	Mar 14, 2014	316 through 535	219
	Study period	Sep 25, 2012	Mar 14, 2014	535	535
BHS-3	Drip SP	Jul 12, 2013	Dec 17, 2014	523	523
BHS-4	Gravity SP	Jul 9, 2013	Dec 16, 2014	525	525
BHS-5	SP	Jul 9, 2013	Apr 25, 2014	0 through 290	290
	R internal	Apr 25, 2014	Dec 15, 2014	290 through 524	234
	Study period	Jul 9, 2013	Dec 15, 2014	524	524
BHS-6	SP	Nov 14, 2013	Jan 29, 2015	441	441
BHS-7	In-ground LP	Nov 19, 2013	Feb 4, 2015	442	442

<sup>1</sup>BHS-1 split recirculation device was replaced on experimental day 181; recirculation ratio was increased to a target of 10:1 from 5:1

<sup>2</sup>R tank = recirculation to tank

R internal = recirculation to top of Stage 1 media

SP = single pass

LP = low pressure distribution

### 5.1 Flowrates

System monitoring included measuring and recording the metered flowrates. The flow measurement devices for each PNRS are described in Table 4-4. The average and standard deviation for each flow measurement device over the study period are summarized in Table 5-2 which includes the measured household daily wastewater flowrate and additional process specific flowrates. Additional details and results on flow monitoring can be found in the System Monitoring Reports in Appendix B. Based on the flow monitoring results in Table 5-2, the actual hydraulic loading rate to the PNRS processes can be calculated. These results are presented in Table 5-3.

**Table 5-2: Flowrate**

System	Stage 1 Mode of Operation <sup>2</sup>	Period of flow data	Metered Household Water Use (Q)		Metered Stage 1 Forward Flow (Q)		Metered or Calculated Stage 1 Recycle (R)			Metered Stage 2 Forward Flow (Q)	
		# days	Mean (gpd)	SD (gpd)	Mean (gpd)	SD (gpd)	Mean (gpd)	SD (gpd)	Mean Recycle Rate R:Q	Mean (gpd)	SD (gpd)
BHS-1 <sup>1</sup>	R tank	398	111.9	6.9			1,037.1	151.9	9.3		
BHS-2	R tank	314	97.6	24.4			377.5	84.4	3.5	109.1	22.3
	R internal	219	107.5	42.0			305.4	157.4	2.7	112.4	56.8
	mean	533	100.9	31.2			344.2	126.3	3.1	110.7	41.0
BHS-3	Drip SP	523	118.9	65.9	145.0	64.8				144.6	62.8
BHS-4	SP	525	297.0	70.3							
BHS-5	SP	290	123.9	36.1						114.1	39.5
	R internal	234	159.1	98.9			392.8	68.9	3.2	123.5	21.3
	mean	524	135.0	64.0						116.5	35.6
BHS-6	SP	441	125.5	21.8	152.6	22.8					
BHS-7	In-ground LP	421	157.9	18.7	125.4	32.7					

<sup>1</sup> After replacement of split flow recirculation device

<sup>2</sup> R tank = recirculation to tank

R internal = recirculation to top of Stage 1 media

SP = single pass

LP = low pressure distribution

**Table 5-3: Hydraulic Loading Rate**


System	Mean Forward Flowrate (gpd)	Stage 1 Biofilter		Stage 2a (Lignocellulosic) Biofilter		Stage 2b (Sulfur) Biofilter	
		Surface Area (ft <sup>2</sup> )	HLR (gal/ft <sup>2</sup> -d)	Surface Area (ft <sup>2</sup> )	HLR (gal/ft <sup>2</sup> -d)	Surface Area (ft <sup>2</sup> )	HLR (gal/ft <sup>2</sup> -d)
BHS-2	110.7	37	3.0	36	3.1	18	6.1
BHS-3	145.0	728	0.2	728	0.2	39	3.8
BHS-4	297.0	113	2.6	36	8.2	18	16.5
BHS-5	116.5	78	1.5	36	3.2	18	6.5
BHS-6	152.6	67	2.3	67	2.3	20	7.6
BHS-7	125.4	362	0.3	362	0.3		



## 5.2 Wastewater Temperature

Each system process component was monitored for field parameters including temperature. A cumulative frequency diagram showing all the influent wastewater (STE) and in-tank treated effluent, prior to subsurface dispersal, measurements taken during the study are provided in Figure 5-1. The influent STE temperature ranged from 16.1 to 29.4 degrees Celsius, and the treated effluent temperature ranged from 13.6 to 30.4 degrees Celsius. The 50<sup>th</sup> percentile influent and effluent temperatures were ca. 20.5 and 21.9°C. respectively.

**Figure 5-1: Temperature Cumulative Frequency Diagram**



## 5.3 Water Quality


Mean effluent values and standard deviation (mean  $\pm$  SD) for key water quality results and a time series of influent and effluent total nitrogen over the study period for each test system are graphically displayed in Figures 5-2 through 5-17. The performance of various system components can be compared by considering


the changes through treatment of nitrogen species (TKN,  $\text{NH}_3\text{-N}$  and  $\text{NO}_x\text{-N}$ ) as well as supporting water quality parameters. The System Monitoring Summary reports for each PNRS provide more detailed water quality monitoring summaries over the study period, and can be found in Appendix B.

The BHS-1 influent wastewater water quality parameters were in the upper range of values typically reported for Florida single family residences (Figure 5-2). The pump chamber effluent average  $\text{NO}_x\text{-N}$  was 28.1 mg/L, and Aerocell<sup>TM</sup> effluent average  $\text{NO}_x\text{-N}$  was 32.3 mg/L. These results indicate denitrification was occurring as the effluent was recirculated back into the pump chamber. The Aerocell<sup>TM</sup> unit provided significant nitrification with average effluent  $\text{NH}_3\text{-N}$  concentration of 8.3 mg/L and average effluent TKN of 11.5 mg/L. The Nitrex<sup>TM</sup> system was effective in producing a reducing environment and achieving the  $\text{NO}_x\text{-N}$  reduction goals (average  $\text{NO}_x\text{-N}$  concentration of 0.1 mg/L). The average final total nitrogen in the treatment system effluent was 7.1 mg/L (Figure 5-3), primarily as TKN (average TKN concentration of 7.0 mg/L). The Nitrex<sup>TM</sup> unit effluent average TSS and fecal coliform concentrations were effectively reduced to below 10 throughout the study period.

The data for the Nitrex<sup>TM</sup> system included one data point with very high influent nitrogen concentrations (93 mg/L, day 349 on Figure 5-3), and this appeared to result in an upset and reduced nitrification of the Aerocell<sup>TM</sup> unit, which in turn would have resulted in less overall nitrogen removal by the Nitrex<sup>TM</sup> system. The precise cause of the Aerocell<sup>TM</sup> upset is unknown, but performance of the BHS-1 system would be slightly higher without this one data point.


**Figure 5-2: BHS-1 Graphical Representation of Water Quality Results (mean  $\pm$  SD)**





The BHS-2 prototype system was tested with two modes of recycle operation: Stage 1 recirculation to the recirculation tank (R tank) and Stage 1 internal recirculation (R internal) to spray nozzles located above the surface of the Stage 1 media. The initial mode of operation (R tank) was tested for 316 days of operation; the mode of operation was revised to R internal for the remainder of the study period. Figure 5-4 summarizes the overall water quality results for the R tank mode of operation throughout the study period. The influent wastewater average total nitrogen concentration was 50.5 mg/L. The Stage 1 biofilter with recirculation to tank provided significant nitrification with an average  $\text{NH}_3\text{-N}$  concentration of 0.9 mg/L and average TKN of 3.1 mg/L. The Stage 1 biofilter effluent average  $\text{NO}_x\text{-N}$  was 16.7 mg/L. These results indicate significant denitrification (approximately 60% total nitrogen reduction) was occurring. The Stage 2 biofilter was effective in producing a reducing environment and achieving the  $\text{NO}_x\text{-N}$  reduction goals (average  $\text{NO}_x\text{-N}$  concentration of 0.02 mg/L). The average final total nitrogen in the treatment system effluent was 3.5 mg/L (Figure 5-4), primarily as TKN (average TKN concentration of 3.4 mg/L).

**Figure 5-4: BHS-2 (R Tank) Graphical Representation of Water Quality Overall Results (mean  $\pm$  SD)**



The mode of operation was revised to R internal for the remainder of the study period. Figure 5-5 summarizes the overall water quality results for the R internal mode of operation throughout the study period. The influent wastewater average total nitrogen concentration was 57.8 mg/L. The Stage 1 biofilter with internal recirculation provided nitrification with an average NH<sub>3</sub>-N concentration of 0.9 mg/L and average TKN of 4.5 mg/L. The Stage 1 biofilter effluent average NO<sub>x</sub>-N was 34.0 mg/L. These results indicate denitrification (approximately 33% total nitrogen reduction) was occurring. Stage 2 biofilter was effective in producing a reducing environment and achieving the NO<sub>x</sub>-N reduction goals (average NO<sub>x</sub>-N concentration of 0.02 mg/L). The average final total nitrogen in the treatment system effluent was 1.8 mg/L (Figure 5-5), primarily as TKN (average TKN concentration of 1.8 mg/L). Figure 5-6 provides an overall study period total nitrogen time series graph which depicts the change in performance following the change in Stage 1 mode of operation. Additional details of this system operation and performance can be found in Anderson et al., 2014 and Hirst and Anderson, 2015.



**Figure 5-5: BHS-2 (R Internal) Graphical Representation of Water Quality Overall Results (mean  $\pm$  SD)**





Figure 5-6: BHS-2 Total Nitrogen Time Series Graph




Note: Daily samples were collected on experimental days 531 through 535

The BHS-3 influent wastewater average total nitrogen concentration was 50.5 mg/L (Figure 5-7). The Stage 1 suction lysimeters showed slightly variable results; however overall the Stage 1 biofilter provided significant ammonia, fecal coliform and total phosphorus removal. The combined Stage 1 and Stage 2a lined drip zone effluent indicated significant ammonia removal with an average  $\text{NH}_3\text{-N}$  concentration of 0.2 mg/L and average TKN of 2.1 mg/L. The average Stage 1&2a biofilter effluent  $\text{NO}_x\text{-N}$  was 5.8 mg/L. These results indicate significant  $\text{NO}_x\text{-N}$  removal and approximately 84% total nitrogen reduction through the Stage 1 and Stage 2a process. The Stage 2b biofilter with sulfur media was effective in producing a reducing environment and achieving significant  $\text{NO}_x\text{-N}$  removal (average  $\text{NO}_x\text{-N}$  concentration of 0.6 mg/L). The average final total nitrogen in the treatment system effluent was 1.9 mg/L (Figure 5-8), primarily as TKN (average TKN concentration of 1.3 mg/L). This represents a 96 percent average reduction in total nitrogen from STE for this PNRS over the study period.




**Figure 5-7: BHS-3 Graphical Representation of Water Quality Results (mean  $\pm$  SD)**



NA = Not analyzed

**Figure 5-8: BHS-3 Total Nitrogen Time Series Graph**



*Note: Daily samples were collected on experimental days 206 through 210*


The BHS-4 influent wastewater average total nitrogen concentration was 70.1 mg/L (Figure 5-9). The Stage 1 biofilter provided ammonia removal with an average  $\text{NH}_3\text{-N}$  concentration of 8.1 mg/L and average TKN of 12.0 mg/L. The Stage 1 biofilter effluent average  $\text{NO}_x\text{-N}$  was 33.6 mg/L. These results indicate denitrification was likely occurring in the Stage 1 biofilter, with a total nitrogen reduction of approximately 35%. The Stage 2 biofilter was effective in producing a reducing environment and achieving significant  $\text{NO}_x\text{-N}$  removal (average  $\text{NO}_x\text{-N}$  concentration of 0.8 mg/L). The average final total nitrogen in the treatment system effluent was 7.4 mg/L (Figure 5-10), primarily as TKN (average TKN concentration of 6.6 mg/L). Average total nitrogen reduction from this PNRS was approximately 89 percent.

**Figure 5-9: BHS-4 Graphical Representation of Water Quality Results (mean  $\pm$  SD)**



	Statistical Parameter	Septic Tank Effluent	Stage 1 Effluent	Stage 2A Lignocellulosic Effluent	Stage 2B Sulfur Effluent
<b>Water Quality Parameter</b>	<b>n</b>	<b>12</b>	<b>12</b>	<b>12</b>	<b>12</b>
CBOD <sub>5</sub> mg/L	mean	136.9 $\pm$ 53.0	8.8 $\pm$ 6.2	12.7 $\pm$ 6.6	12.3 $\pm$ 8.2
TSS mg/L	mean	61.1 $\pm$ 21.0	9.4 $\pm$ 6.1	5.3 $\pm$ 3.7	4.1 $\pm$ 2.3
TKN mg N/L	mean	70.0 $\pm$ 9.8	12.0 $\pm$ 7.5	8.7 $\pm$ 6.2	6.6 $\pm$ 4.4
NH <sub>3</sub> mg N/L	mean	62.3 $\pm$ 7.3	8.1 $\pm$ 8.2	5.6 $\pm$ 6.2	4.4 $\pm$ 4.0
NO <sub>x</sub> mg N/L	mean	0.1 $\pm$ 0.2	33.6 $\pm$ 15.5	3.2 $\pm$ 4.1	0.8 $\pm$ 2.7
TN mg N/L	mean	70.1 $\pm$ 10.0	45.6 $\pm$ 10.6	11.8 $\pm$ 4.4	7.4 $\pm$ 4.9
Sulfate mg/L	mean	1.7 $\pm$ 1.5	19.7 $\pm$ 3.1	14.7 $\pm$ 7.5	37.2 $\pm$ 17.6
Fecal Coliform (Ct/100mL)	geomean	48,499	2,764	1,150	409
TP mg/L	mean	9.4 $\pm$ 2.1	3.3 $\pm$ 1.5	2.7 $\pm$ 1.4	2.6 $\pm$ 1.1

Figure 5-10: BHS-4 Total Nitrogen Time Series Graph




Note: Daily samples were collected on experimental days 209 through 213

The BHS-5 system was tested with two modes operation: Stage 1 single pass (SP) and Stage 1 with internal recirculation (R internal) to spray nozzles located above the surface of the Stage 1 media. The initial mode of operation (SP) was tested for 290 days of operation; the mode of operation was revised to R internal for the remainder of the study period. Figure 5-11 summarizes the overall water quality results for the Stage 1 single pass mode of operation throughout the study period. The influent wastewater average total nitrogen concentration was 70.8 mg/L. The Stage 1 biofilter provided significant nitrification with an average  $\text{NH}_3\text{-N}$  concentration of 3.3 mg/L and average TKN of 6.4 mg/L. The Stage 1 biofilter effluent average  $\text{NO}_x\text{-N}$  was 43.4 mg/L. These results indicate denitrification (approximately 30% total nitrogen reduction) was occurring. Stage 2 biofilter was effective in producing a reducing environment and achieving the  $\text{NO}_x\text{-N}$  reduction goals (average  $\text{NO}_x\text{-N}$  concentration of 0.04 mg/L). The average final total nitrogen in the treatment system effluent was 2.3 mg/L (Figure 5-11), primarily as TKN (average TKN concentration of 2.2 mg/L), representing a 96.7 percent average reduction in total nitrogen.



**Figure 5-11: BHS-5 (Single Pass) Graphical Representation of Water Quality Overall Results (mean  $\pm$  SD)**



The mode of operation was revised to R internal for the remainder of the study period. Figure 5-12 summarizes the overall water quality results for the Stage 1 R internal mode of operation throughout the study period. The influent wastewater average total nitrogen concentration was 75.0 mg/L. Stage 1 recirculation mode of operation resulted in generally overall similar treatment performance as single pass mode. The Stage 1 biofilter provided significant nitrification with an average NH<sub>3</sub>-N concentration of 0.1 mg/L and average TKN of 4.5 mg/L. The Stage 1 biofilter effluent average NO<sub>x</sub>-N was 57.3 mg/L. These results indicate denitrification (approximately 18% total nitrogen reduction) was occurring. The time series plot (Figure 5-13) shows a trend in increasing total nitrogen in the Stage 2a lignocellulosic effluent with time which indicates less NO<sub>x</sub>-N removal. The cause for the reduction in NO<sub>x</sub>-N removal effectiveness in the lignocellulosic chamber is unclear; it is thought to be related to the change in operation to Stage 1 dosing and recirculation, which appeared to increase the dissolved oxygen content of the Stage 1 effluent. Loss in reactivity of the media or other factors could also be involved. However, the Stage 2b biofilter sulfur media was effective in producing a reducing environment and achieving the NO<sub>x</sub>-N reduction goals (average NO<sub>x</sub>-N concentration of 0.03 mg/L). The average final total nitrogen in the treatment system effluent was 1.8 mg/L, primarily TKN (average TKN concentration of 1.8 mg/L), representing a 97.6 percent average reduction in total nitrogen. Figure 5-13 provides an overall study period total nitrogen time series graph which depicts the change in performance following the change in Stage 1 mode of operation.

**Figure 5-12: BHS-5 (R Internal) Graphical Representation of Water Quality Overall Results (mean  $\pm$  SD)**





Figure 5-13: BHS-5 Total Nitrogen Time Series Graph



Note: Daily samples were collected on experimental days 209 through 213

The BHS-6 influent wastewater average total nitrogen concentration was 66.3 mg/L (Figure 5-14). During the study period the water level in the combined Stage 1 and 2a (Stage 1&2a) tank was found to significantly fluctuate. The periods of high water level suggested hydraulic blockages in the system which could adversely affect nitrogen removal performance. The water level was significantly elevated during the sampling on Day 148. As a result of several system investigations, partial clogging of the Stage 2b inlet pipe and Stage 1&2a outlet pipe were found and fixed by Day 329. The low Stage 1 total nitrogen measured on Day 221 is likely a result of the elevated water level (Figure 5-15). The Stage 1 drivepoint samplers showed slightly variable results; however overall the Stage 1 biofilter provided significant ammonia removal. The combined Stage 1&2a effluent indicated ammonia removal with an average  $\text{NH}_3\text{-N}$  concentration of 5.9 mg/L and average TKN of 8.0 mg/L. The average Stage 1&2a biofilter effluent  $\text{NO}_x\text{-N}$  was 24.9 mg/L. The Stage 2b biofilter with sulfur media was effective in producing a reducing environment and achieving  $\text{NO}_x\text{-N}$  removal (average  $\text{NO}_x\text{-N}$  concentration of 4.4 mg/L), however denitrification through Stage 2b



decreased significantly after about day 350. The reason for this is unclear, but could be due to hydraulic short-circuiting that may have developed from the maintenance activities on the Stage 2b inlet pipe. The average final total nitrogen in the treatment system effluent was 12.4 mg/L (Figure 5-14), primarily as TKN (average TKN concentration of 8.0 mg/L). This PNRS reduced STE total nitrogen by an average of 81% over the study period. Based on these results, it was felt that design of the system's lignocellulosic underdrain and sulfur influent distribution could be significantly improved in ways that would increase system reliability and performance.

**Figure 5-14: BHS-6 Graphical Representation of Water Quality Results (mean  $\pm$  SD)**





Figure 5-15: BHS-6 Total Nitrogen Time Series Graph



Note: Fluctuating water level in Stage 1 & 2a tank days 148 through 329

The BHS-7 influent wastewater average total nitrogen concentration was 54.9 mg/L (Figure 5-16). The four Stage 1 suction lysimeters showed variable results; however the overall average indicates that the Stage 1 biofilter provided significant ammonia, fecal coliform and total phosphorus removal. The Stage 1 results indicated significant ammonia removal with an average  $\text{NH}_3\text{-N}$  concentration of 0.6 mg/L and average TKN of 3.4 mg/L. The average Stage 1 effluent  $\text{NO}_x\text{-N}$  was 25.5 mg/L. The Stage 2 biofilter with lignocellulosic media was effective in producing a reducing environment and achieving significant  $\text{NO}_x\text{-N}$  removal (average  $\text{NO}_x\text{-N}$  concentration of 0.1 mg/L). However, the average perimeter soil water results (average  $\text{NO}_x\text{-N}$  concentration of 18.7 mg/L) indicated that the liner was not large enough to capture the unsaturated plume from the Stage 1 biofilter, and some of the nitrified effluent bypassed the liner. This is thought to be one reason for the high nitrate concentrations measured in the liner perimeter monitoring points. Therefore, it appears that the liner for this type of system needs to be designed much larger to capture all percolating effluent. Additionally, it appears that the fine sand media holds considerable water at the sand/lignocellulosic interface, and this also may contribute to nitrified effluent moisture transfer away from

the liner into the surrounding soil. A better transitional interface between the sand/lignocellulosic media is needed in order to direct the effluent flow into the liner. Also, using a 50/50 mixture of sand and lignocellulosic within the liner would better maintain the moisture profile into the liner. The average total nitrogen in the perimeter soil water was 19.1 mg/L (Figure 5-17), primarily  $\text{NO}_x\text{-N}$  (average TKN concentration of 2.2 mg/L). Based on the perimeter sample results, this PNRS reduced STE total nitrogen by an average of 65% over the study period.

**Figure 5-16: BHS-7 Graphical Representation of Water Quality Results (mean  $\pm$  SD)**





Figure 5-17: BHS-7 Total Nitrogen Time Series Graph



The mean effluent Total Nitrogen (TN) concentration for the seven prototype PNRS ranged from 1.8 to 19.1 mg/L (Table 5-4).



**Table 5-4: Summary of Effluent Total Nitrogen (mean  $\pm$  SD)**

System	System Description <sup>1</sup>	Mean Influent TN, mg/L	Mean Effluent TN, mg/L	Mean TN Reduction, %
BHS-1	Proprietary: Stage 1 Aerocell™ Stage 2 Nitrex™	82.7 $\pm$ 11.0	7.1 $\pm$ 5.7	91
BHS-2	In-tank Stage 1 with R tank, dual-media Stage 2	50.5 $\pm$ 5.4	3.5 $\pm$ 2.4	93
BHS-2	In-tank Stage 1 with R internal, dual-media Stage 2	57.8 $\pm$ 7.5	1.8 $\pm$ 1.2	97
BHS-3	In-ground stacked Stage 1 over Stage 2a ligno with supplemental Stage 2b sulfur	50.5 $\pm$ 8.8	1.9 $\pm$ 1.7	96
BHS-4	In-tank SP Stage 1, dual-media Stage 2	70.1 $\pm$ 10.0	7.4 $\pm$ 4.9	89
BHS-5	In-tank SP Stage 1, dual-media Stage 2	70.8 $\pm$ 7.8	2.3 $\pm$ 1.8	97
BHS-5	In-tank Stage 1 with R internal, dual-media Stage 2	75.0 $\pm$ 11.6	1.8 $\pm$ 0.4	98
BHS-6	In-tank stacked Stage 1 over Stage 2a ligno with supplemental Stage 2b sulfur	66.3 $\pm$ 17.9	12.4 $\pm$ 8.5	81
BHS-7	In-ground LP stacked SP Stage 1 over Stage 2 ligno	54.9 $\pm$ 9.8	19.1 $\pm$ 10.9	65

<sup>1</sup>R tank = recirculation to tank

R internal = recirculation to top of Stage 1 media

SP = single pass

LP = low pressure distribution

## 5.4 Operation and Maintenance

Overall the prototype PNRS operated continually following start-up as summarized in Table 5-5, with very limited or no downtime. A field technician visited the sites on a monthly basis. In general, very little maintenance was required. Most of the operational issues were resolved during start-up of the treatment systems as summarized in Table 5-6. A summary log of repairs, maintenance actions, inspection results and system observations are included in the System Monitoring Summary reports in Appendix B.



**Table 5-5: System Operation**

<b>System</b>	<b>Total # of days operated during study period</b>	<b>Total # days offline during study period</b>	<b>Total # of monitoring site visits during study period</b>
BHS-1	593	0	27
BHS-2	535	0	34
BHS-3	523	8 <sup>1</sup>	46
BHS-4	525	21 <sup>2</sup>	36
BHS-5	524	0	30
BHS-6	441	0	32
BHS-7	442	9 <sup>3</sup>	30

<sup>1</sup>The PNRS was not operating experimental days 59 through 67; a replacement part for the hydraulic unit was required.

<sup>2</sup>The PNRS was bypassed experimental days 37 through 58; a smaller pump in the lift station was required.

<sup>3</sup>The PNRS was bypassed experimental days 7 through 13 and 17 through 20 because the homeowners hosted two large holiday parties during the system start-up period.

**Table 5-6: System Operation and Maintenance**

<b>System</b>	<b>Major Issues encountered</b>	<b>General O&amp;M requirements</b>	<b>Other O&amp;M</b>
BHS-1	<p>During start-up:</p> <ul style="list-style-type: none"> <li>Flow splitter device flow split</li> <li>Control panel wiring</li> <li>Float placement within pump vault</li> </ul> <p>During study period:</p> <ul style="list-style-type: none"> <li>Leaks detected in flow splitter device (was replaced)</li> </ul>	<ul style="list-style-type: none"> <li>Recirculation ratio adjustment to meet target of 10:1</li> </ul>	<ul style="list-style-type: none"> <li>Recirculation ratio was increased to target of 10:1 for better performance</li> </ul>
BHS-2	<p>During start-up:</p> <ul style="list-style-type: none"> <li>Float placement</li> </ul>	<ul style="list-style-type: none"> <li>Cleaning of septic tank effluent screen</li> </ul>	<ul style="list-style-type: none"> <li>Recirculation mode of operation was revised from recirc tank to sprayers installed above Stage 1 biofilter media</li> </ul>
BHS-3	<p>During start-up:</p> <ul style="list-style-type: none"> <li>Solenoid valve malfunction due to construction debris</li> </ul>	<ul style="list-style-type: none"> <li>Cleaning of septic tank and STE dose tank effluent screens</li> <li>Air release valve replacement</li> </ul>	<ul style="list-style-type: none"> <li>The drip system controller includes automated cleaning sequences which leads to system complexity (9 solenoid valves) which requires additional oversight for system operation</li> </ul>
BHS-4	<p>During start-up:</p> <ul style="list-style-type: none"> <li>Oversized STE transfer pump caused significant mixing in primary tank (was replaced)</li> </ul> <p>During study period:</p> <ul style="list-style-type: none"> <li>Additional centerline distribution pipe was installed above Stage 1 media to improve coverage of effluent over entire surface of biofilter</li> </ul>	<ul style="list-style-type: none"> <li>Cleaning of septic tank effluent screen</li> <li>Raking of Stage 1 biofilter media surface</li> </ul>	<ul style="list-style-type: none"> <li>High cleaning frequency of septic tank effluent screen attributed to flow transfer pump flow into single chamber septic tank</li> <li>Solids carryover from the septic tank led to biomat formation and some ponding near Stage 1 distribution box</li> </ul>
BHS-5	<p>During start-up:</p> <ul style="list-style-type: none"> <li>Float placement</li> </ul> <p>During study period:</p> <ul style="list-style-type: none"> <li>During recirculation mode of operation sprayers required adjustment</li> </ul>	<ul style="list-style-type: none"> <li>Cleaning of septic tank effluent screen</li> </ul>	<ul style="list-style-type: none"> <li>Stage 1 mode of operation was revised from single pass to recirculating using sprayers installed above Stage 1 biofilter media.</li> </ul>



**Table 5-6 (cont.): System Operation and Maintenance**

System	Major Issues encountered	General O&M requirements	Other O&M
BHS-6	<p>During start-up:</p> <ul style="list-style-type: none"> <li>Loose wiring</li> </ul> <p>During study period:</p> <ul style="list-style-type: none"> <li>Stage 1 spray nozzle clogging and inadequate distribution</li> <li>Stage 1&amp;2a effluent collection pipe clogged</li> <li>Stage 2 inlet pipe clogged</li> </ul>	<ul style="list-style-type: none"> <li>Cleaning of Stage 1 spray nozzles</li> <li>Clearing blockages in Stage 1&amp;2a effluent collection pipe and Stage 2 inlet pipe</li> <li>Cleaning of process flowmeter</li> </ul>	<ul style="list-style-type: none"> <li>Operational issues are associated with design and construction problems. A better dosing system for the Stage 1 biofilter, a better underdrain design for the Stage 1&amp;2a tank and improved inlet to the Stage 2 tank without bends between the tanks would likely eliminate most of the operational problems.</li> </ul>
BHS-7	<p>During start-up:</p> <ul style="list-style-type: none"> <li>Float placement</li> </ul> <p>During study period:</p> <ul style="list-style-type: none"> <li>Pump had erroneously been installed with a connection to a GFI breaker (replaced with regular 30-amp breaker)</li> </ul>	<ul style="list-style-type: none"> <li>Cleaning of septic tank effluent screen</li> <li>Flushing of low pressure distribution pipe</li> </ul>	<ul style="list-style-type: none"> <li>It appears that the liner was not large enough to capture the unsaturated plume from the Stage 1 biofilter, and some of the nitrified effluent missed the liner. Also a better transitional interface between the sand and the lignocellulosic media is needed, to direct the effluent into the liner.</li> <li>However, this system type would provide the simplest operation and maintenance of all the systems tested.</li> </ul>

## 5.5 Energy and Media Consumption

Energy consumption was monitored using an electrical meter installed on the electrical line dedicated to the PNRs. The electrical meter records the cumulative power usage of the system in kilowatt-hours. The power usage of the system is primarily associated with the single pump; therefore the energy use is indicative of the size of the pump motor, the number of pump starts (doses per day), pump runtime (dose volume) and system hydraulic design. Table 5-7 provides the average power usage in kWh per day and the average power usage per 1000 gallons treated as graphically displayed in Figure 5-18.

**Table 5-7: Energy Consumption**

System	Stage 1 Operation <sup>3</sup>	Power Use		Electrical Use vs Treated Flow	
		Mean (kWh/day)	Standard Deviation (kWh/day)	Mean (kWh/1000 gallon)	Standard Deviation (kWh/1000 gallon)
BHS-1 <sup>1</sup>	R tank	3.21	0.57	28.72	4.85
BHS-2	R tank	0.31	0.07	2.80	0.23
	R internal	0.26	0.13	2.36	0.34
	mean	0.28	0.1	2.59	0.36
BHS-3	Drip SP	0.98	0.56	7.83	5.99
BHS-4 <sup>2</sup>	Gravity SP	0	0	0	0
BHS-5	SP	0.04	0.02	0.42	0.5
	R internal	0.14	0.02	1.15	0.04
	mean	0.07	0.05	0.61	0.54
BHS-6 <sup>4</sup>	SP	0.48	0.17	3.20	1.16
BHS-7	In-ground LP	0.04	0.02	0.31	0.12

<sup>1</sup>After replacement of split flow recirculation device

<sup>2</sup>For system BHS-4 to test the total household wastewater volume, 0.14 kWh/day was used by a small transfer pump to get flow from the second OSTDS to the PNRS.

<sup>3</sup>R tank = recirculation to tank


R internal = recirculation to top of Stage 1 media

SP = single pass

LP = low pressure distribution

<sup>4</sup>Higher energy use at BHS-6 due to use of the pump from BHS-1, which was designed for high recirculation rate and higher head for sprayers.

**Figure 5-18: Time Series of Energy Use per 1000 Gallons Treated**



<sup>1</sup>BHS-1 split recirculation device was replaced on experimental day 181; recirculation ratio was increased to a target of 10:1 from 5:1

<sup>2</sup>BHS-2 Stage 1 mode of operation was revised from tank recirculation to internal recirculation on experimental day 316

<sup>3</sup>BHS-5 Stage 1 mode of operation was revised from single pass to internal recirculation on experimental day 290

Note: BHS-4 is not included because the PNRS did not use energy

There are no chemicals added to the systems. However, the Stage 2 media (lignocellulosic and sulfur) are reactive media which will be consumed during operation. The level of the top of the media surfaces were monitored throughout the study period, and the estimated change, which would represent media consumption, was negligible.

## 6 Data Analyses and Discussion

Based on the data collected during the prototype PNRS evaluations, several analyses have been conducted to assist with evaluation of PNRS performance. This section presents these analyses and performance metrics.

### 6.1 Stage 1 Performance

The prototype unsaturated biofilters (Stage 1) were highly effective in treating primary effluent. The performance of the various Stage 1 biofilters are compared by evaluating the removal efficiencies as summarized in Table 6-1 for single pass operation and recirculating operation. Removal efficiency for TSS, CBOD<sub>5</sub>, Total Nitrogen, Total Kjeldahl Nitrogen and Organic Nitrogen were calculated as:

$$\% RE = \frac{C_{inf} - C_{eff}}{C_{inf}} \times 100 \quad (\text{Eq. 6-1})$$

where:

% RE = percent removal efficiency

C<sub>inf</sub> = influent concentration

C<sub>eff</sub> = effluent concentration

Ammonia removal efficiencies were calculated using an effective influent ammonia concentration, which was defined as the sum of the analytical influent NH<sub>3</sub>-N and the difference in organic N between influent and effluent. The effective influent NH<sub>3</sub> concept assumes that the release of ammonium due to ammonification of influent organic nitrogen is equal to the difference between influent organic N and effluent organic N. The effective influent ammonium nitrogen then equals the analytical influent NH<sub>3</sub>-N plus the NH<sub>3</sub>-N release from ammonification. The effective ammonia removal efficiency for the biofilter is:

$$\% NH_3 RE = \frac{TKN_{inf} - TKN_{eff}}{TKN_{inf} - OrgN_{eff}} \times 100 \quad (\text{Eq. 6-2})$$

where:

% NH<sub>3</sub> RE = percent ammonia removal efficiency

TKN<sub>inf</sub> = influent Total Kjeldahl Nitrogen

TKN<sub>eff</sub> = effluent Total Kjeldahl Nitrogen

OrgN<sub>eff</sub> = effluent Organic Nitrogen


**Table 6-1: Stage 1 Biofilters Mean Removal Efficiencies (%)**

	<b>System</b>	<b>TSS</b>	<b>CBOD<sub>5</sub></b>	<b>TN</b>	<b>TKN</b>	<b>Organic N</b>	<b>NH<sub>3</sub>-N</b>
Single Pass	BHS-3 (in-ground)	91%	90%	48%	96%	72%	100%
	BHS-4 (in-tank)	85%	94%	35%	83%	49%	88%
	BHS-5 (in-tank)	94%	86%	30%	91%	60%	95%
	BHS-6 (in-tank)	-207% <sup>1</sup>	72%	25%	88%	69%	92%
	BHS-7 (in-ground)	90%	91%	47%	94%	74%	99%
Recirculating	BHS-1 (R tank)	90%	75%	47%	86%	83%	90%
	BHS-2 (R tank)	4%	86%	61%	94%	76%	98%
	BHS-2 (R internal)	98%	97%	33%	92%	79%	98%
	BHS-5 (R internal)	97%	96%	18%	94%	50%	100%

<sup>1</sup>The Stage 1 samples from this vertically stacked system were taken from pan lysimeters placed at the expanded clay/lignocellulosic interface. It is suspected that pumping samples up from these pans included some fines from the expanded clay media, thus the increase in TSS over the influent value.

The aerobic biofilters (Stage 1) convert organic nitrogen to ammonia through ammonification and oxidize ammonia through nitrification. The mean ammonia removal efficiency is a good measure of Stage 1 performance. Mean ammonia removal efficiencies for the Stage 1 biofilters were greater than or equal to 88% for all seven systems, with many systems exceeding 95%. In addition to ammonia removal, the Stage 1 biofilters also ostensibly removed varying quantities of NO<sub>x</sub>. PNRS with the greatest total nitrogen mean removal efficiency were the recirculating Stage 1 biofilters and the single pass in-ground systems (see Table 6-1 and Figure 6-1). The recirculating Stage 1 biofilters that include a separate recirculation tank show some pre-denitrification by recycling nitrified effluent back to a recirculation tank or to the Stage 1 biofilter itself. The higher total nitrogen removal efficiency shown in the single pass in-ground Stage 1 systems is most likely attributed to denitrification at anoxic microsites within the soil profile, resulting from lower applied hydraulic loading rates and finer textured sand, and agrees with previous studies of nitrogen reduction by soil treatment units (Anderson et. al, 1994; Anderson et. al., 1998; Anderson and Otis, 2000; Long, 1995; Siegrist and Jenssen, 1989). The Figure 6-1 box and whiskers plot provides an immediate comparative visualization of the total nitrogen removal efficiency of Stage 1 biofilter, including the center and spread of the distribution. The box plot provides a “six point” summary of data values, including the mean, median, minimum, maximum values and upper and lower quartiles interval. The box plots show the upper and lower quartile (75<sup>th</sup> and 25<sup>th</sup> percentile) interval as bounded by the shaded area. The median is shown as the line between the shaded areas, the mean is shown as a black diamond and maximum and minimum are shown as horizontal “whisker” lines.

**Figure 6-1: Stage 1 Biofilters Total Nitrogen Removal Efficiencies**



## 6.2 Stage 2 Performance

The saturated biofilters (Stage 2) were highly effective in treating the Stage 1 nitrified effluent. The performance of the various prototype Stage 2 biofilters were compared by evaluating the oxidized nitrogen (NO<sub>x</sub>-N) removal efficiencies.

### Lignocellulosic Performance

Saturated biofilters with lignocellulosic media, as characterized in Table 6-2, were not uniformly effective in removing oxidized nitrogen (NO<sub>x</sub>-N) as summarized in Table 6-3. The box and whiskers plot (Figure 6-2) provides an immediate comparative visualization of Stage 2 biofilters with lignocellulosic media influent and effluent NO<sub>x</sub>-N, including the center and spread of the distribution. As shown in the cumulative



frequency diagram of influent and effluent  $\text{NO}_x\text{-N}$  for all lignocellulosic biofilters (Figure 6-3), approximately 80 percent of the lignocellulosic effluent  $\text{NO}_x\text{-N}$  sample concentrations were below 10 mg-N/L. As noted during the pilot work, hydraulic retention time should be considered when evaluating lignocellulosic performance. To further evaluate the effect of retention time,  $\text{NO}_x\text{-N}$  removal rate as a function of empty bed hydraulic retention time for the various in-tank saturated lignocellulosic-containing biofilters was plotted to examine any trends (Figure 6-4). As the figure shows, system BHS-4 had a low retention time but the highest nitrate removal rate. Systems with long retention times had much lower  $\text{NO}_x\text{-N}$  removal rates. While it appears from the limited data that  $\text{NO}_x$  removal rate decreases with retention time, this may not be the controlling factor in overall system performance. Others have shown that these systems are nitrate limited at higher retention times, resulting in lower  $\text{NO}_x$  removal rates as  $\text{NO}_x$  concentrations decrease to low levels (Schipper et al., 2010).

The nitrate removal rate in denitrification biofilters incorporating lignocellulosic media are commonly reported as  $\text{g N m}^{-3} \text{ media day}^{-1}$ . Cameron and Schipper (2012) tested nine different carbon substrates including softwood and hardwood which showed no statistical difference. Mean nitrate removal rates tested at two temperatures 14°C and 23.5°C were 3.0 and 4.9  $\text{g N m}^{-3} \text{ day}^{-1}$  for softwood and 3.3 and 4.4  $\text{g N m}^{-3} \text{ day}^{-1}$  for hardwood, respectively. Schmidt and Clark (2013) found similar results of 3.0 and 3.61  $\text{g N m}^{-3} \text{ day}^{-1}$  for softwood and hardwood, respectively. Both studies determined that temperature and carbon availability of the media are more important for controlling nitrate removal rate than hydraulic efficiency. Schipper (2010) summarized that nitrate removal rates supported by denitrification beds incorporating wood generally range from 2 to 10  $\text{g N m}^{-3} \text{ day}^{-1}$ . Table 6-3 summarizes the mean nitrate removal rates ( $\text{g N m}^{-3} \text{ day}^{-1}$ ) for the seven test systems which ranged from 1.18 to 9.59  $\text{g N m}^{-3} \text{ day}^{-1}$ . These values are within the range reported by other investigators as summarized in Table 6-4. In Florida, temperature should not be a controlling factor for denitrification with lignocellulosic media (see Figure 5-1).



**Table 6-2: Stage 2 Lignocellulosic Biofilter Characteristics**

<b>System</b>	<b>Media (% Reactive)</b>	<b>Media placement</b>	<b>Stage 1 Operation<sup>4</sup></b>	<b>Mean Influent Flow (m<sup>3</sup>/day)</b>	<b>Media Volume (m<sup>3</sup>)</b>	<b>Hydraulic Retention Time<sup>1</sup> (days)</b>
BHS-1	Nitrex™	In-tank	Aerocell™	0.424	5.52	13.0
BHS-2	Sawdust (100%)	In-tank	R tank	0.413	3.57	8.6
			R internal	0.426	3.57	8.4
BHS-3	Urban Waste Wood (50%)	Underlying Stage 1 above liner in-ground	Drip application	0.547	7.73	NA
BHS-4	Urban Waste Wood (100%)	In-tank	SP	1.124	3.57	3.2
BHS-5	Urban Waste Wood (100%)	In-tank	SP	0.432	3.57	8.3
			R internal	0.468	3.57	7.6
BHS-6	Urban Waste Wood (100%)	Underlying Stage 1 in-tank	SP	0.578	1.90 <sup>2</sup>	2.2 <sup>2</sup>
BHS-7	Urban Waste Wood (100%)	Underlying Stage 1 above liner in-ground	In-ground LP	0.475	10.25 <sup>3</sup>	10.8 <sup>3</sup>

<sup>1</sup> Calculated for in-tank systems as empty bed residence time

<sup>2</sup> Calculated for the saturated portion of the lignocellulosic media.

<sup>3</sup> Calculated for the saturated portion of the lignocellulosic/liner volume. However, as discussed, much effluent from this system likely did not reach the liner.

<sup>4</sup> R tank = recirculation to tank

R internal = recirculation to top of Stage 1 media

SP = single pass

LP = low pressure distribution

The BHS-7 prototype in-ground system is not included further in the Stage 2 performance analysis due to the unknown hydraulic conditions surrounding the lignocellulosic Stage 2 liner. As discussed previously, it appeared that the flow from the Stage 1 soil media at this system did not routinely flow through the liner system, thus the Stage 2 performance of the system is not well represented by the liner samples.

**Table 6-3: Stage 2 Lignocellulosic Biofilter NO<sub>x</sub>-N Removal**

<b>System</b>	<b>Stage 1 Operation<sup>2</sup></b>	<b>Influent Mean NO<sub>x</sub>-N, mg N/L</b>	<b>Effluent Mean NO<sub>x</sub>-N, mg N/L</b>	<b>Mean NO<sub>x</sub>-N Removal Efficiency (%)</b>	<b>Mean NO<sub>x</sub>-N Removal Rate (g N m<sup>-3</sup>d<sup>-1</sup>)</b>
BHS-1	R tank	32.33	0.09	100%	2.48
BHS-2	R tank	16.72	0.02	100%	1.93
	R internal	34.00	3.96	88%	3.58
BHS-3	Drip SP	23.92	5.77	76%	1.28 <sup>1</sup>
BHS-4	SP	33.58	3.15	91%	9.59
BHS-5	SP	43.44	4.10	91%	4.76
	R internal	57.25	32.25	44%	3.28
BHS-6	SP	42.26	24.87	41%	5.30

<sup>1</sup>System BHS-3 lignocellulosic media mixture was 50% reactive media, the mean NO<sub>x</sub>-N removal rate is calculated using the total mixed media volume.

<sup>2</sup>R tank = recirculation to tank


R internal = recirculation to top of Stage 1 media

SP = single pass

**Table 6-4: Summary of Literature Values for Lignocellulosic Denitrification**

No.	Reference	System Type	Field Site Location	Influent NO <sub>3</sub> -N (mg-N/L)	Temperature (°C)	N removal rate (g N/m <sup>3</sup> media-day)
1	Robertson and Cherry, 1995	Wall	Canada	57-62	NR	1.0 - 1.9
2	Schipper and Vojvodic-Vokovic, 1998	Wall	New Zealand	5-16	13-21	3.6
3	Robertson et al., 2000	Wall Bioreactor	Canada	28-57 4.8	NR	0.7-0.8 for reactive barriers 1.3-10.2 for mulch reactor
4	Robertson et al., 2008	Wall Wall	Canada	2-100	6-10 20-22	0.07-0.35 1.1-1.9
5	Schipper et al., 2010	Lined Bed	New Zealand	2-20	NR	0.1-11
6	Cameron and Schipper, 2010	Bed Bed	New Zealand New Zealand	159 141 159 141	14 23.5 14 23.5	3.0 4.9 3.3 4.4
7	Robertson, 2010	Columns	Lab Column Study	3.1-48.8 3.1-48.8 3.1-48.8	21-23 21-23 21-23	10.8-16.1 (fresh wood) 8.5 (2 yr old bioreactor) 6.4 (7 yr old bioreactor)
8	Moorman et al., 2010	Bioreactor	Iowa	20-25	NR	5.4-22.7
9	Long et al., 2011	Wall	New Zealand	2-15	11-14	NR
10	Schmidt and Clark, 2012	Wall	Florida	3-10	15-22	4.9-5.5
11	Schmidt and Clark, 2013	Columns	Florida, Lab study	7.5	7.9-24.1	2-6

**Figure 6-2: Stage 2 Lignocellulosic Biofilter Effluent  $\text{NO}_x\text{-N}$**







Figure 6-4: In-tank Lignocellulosic Biofilter  $\text{NO}_x\text{-N}$  Removal Rate vs HRT



### 6.2.1 Sulfur Performance

The Figure 6-5 box and whisker plot provides an immediate comparative visualization of influent and effluent  $\text{NO}_x$  concentrations of Stage 2 biofilters with sulfur media. Saturated biofilters with sulfur media were generally but not uniformly effective in removing oxidized nitrogen ( $\text{NO}_x\text{-N}$ ) as summarized in Table 6-5. However in all prototype PNRS that employed sulfur, the sulfur media biofilters followed treatment by preceding lignocellulosic media biofilters. In some individual sample events for some systems,  $\text{NO}_x$  removal was highly complete in sulfur biofilter influent and little  $\text{NO}_x$  reduction occurred. As shown in Figure 6-6, a cumulative frequency diagram for all the sulfur biofilter influent and effluent  $\text{NO}_x\text{-N}$  sample concentrations, greater than 90 percent of the sulfur effluent  $\text{NO}_x\text{-N}$  concentrations were below 0.2 mg-N/L. These values are within the range reported by other investigators as summarized in Table 6-6.



**Table 6-5: Stage 2 Sulfur Biofilter NO<sub>x</sub>-N Removal**

<b>System</b>	<b>Percent Reactive Media</b>	<b>Stage 1 Operation<sup>2</sup></b>	<b>Mean Influent Flow (m<sup>3</sup>/day)</b>	<b>Media Volume (m<sup>3</sup>)</b>	<b>Hydraulic Retention Time<sup>1</sup> (days)</b>	<b>Influent Mean NO<sub>x</sub>-N, mg N/L</b>	<b>Effluent Mean NO<sub>x</sub>-N, mg N/L</b>	<b>Mean NO<sub>x</sub>-N Removal Efficiency (%)</b>
BHS-2	90%	R tank	0.413	1.02	2.5	0.02	0.02	NA
		R internal	0.426	1.02	2.4	3.96	0.02	99%
BHS-3	90%	Drip SP	0.548	1.09	2.0	5.77	0.61	89%
BHS-4	90%	SP	1.124	0.76	0.7	3.15	0.82	74%
BHS-5	90%	SP	0.432	0.76	1.8	4.10	0.04	99%
		R internal	0.468	0.76	1.6	32.25	0.03	100%
BHS-6	90%	SP	0.578	0.57	1.0	24.87	4.41	82%

<sup>1</sup>Calculated as empty bed residence time

<sup>2</sup>R tank = recirculation to tank

R internal = recirculation to top of Stage 1 media

SP = single pass

Figure 6-5: Sulfur Biofilter Effluent  $\text{NO}_x\text{-N}$  Box





Figure 6-6: Sulfur Biofilter Effluent  $\text{NO}_x\text{-N}$  Cumulative Frequency Diagram



Note: System BHS-2 R tank operation is not included because the influent  $\text{NO}_x\text{-N}$  was never above the method detection limit.

**Table 6-6: Summary of Literature Values for Sulfur Denitrification**

Ref. No.	Reference	Systems Studied	Field Site Location	Influent NO <sub>3</sub> -N (mg-N/L)	Temperature (°C)	N Removal Rate (g N/m <sup>3</sup> media-day)	Media Life
1	Batchelor and Lawrence, 1978	Denitrification of nitrate using elemental sulfur in a mixed liquor slurry reactor system	New York, Lab study	30 mg N/L	12-30	0.97-3.92 mg NO <sub>3</sub> -N/mg biomass (as org N) /day	2.5 - 5.6 mg S/mg NO <sub>3</sub> removed
2	Kanter et al., 1998	mound with liner Sulfur/dolomite	University of Wisconsin, Madison	25.7 mg-N/L and 51.7 mg/L	NR	66-98% TN reduction	NR
3	Sengupta et al., 2006	Lab-scale and pilot-scale upflow packed bioreactors. Media was Sulfur mixed with 3 different alkalinity sources: marble chips, crushed limestone and crushed oyster shell at 3:1 ratio	Massachusetts, at the MASSTC	2-32 mg-N/L	NR	80% NO <sub>3</sub> -N reduction	NR
4	Smith, 2012	Lab-scale study of two stage biofiltration for N removal. Stage 2 sulfur based denitrification system (PNRS I). Media was sulfur and oyster shell at 3:1 ratio		59 mg NO <sub>x</sub> -N/L	NR	exceeded 99.8% NO <sub>x</sub> -N reduction	NR
5	Smith, 2009	Lab-scale study of two stage biofiltration for N removal. Stage 2 sulfur based denitrification system (PNRS I). Media was sulfur and oyster shell at 3:1 ratio	Florida, PNRS I study	59 mg NO <sub>x</sub> -N/L	10-30	14.4 (based on total media volume, a mixture of 60% sulfur, 20% oyster shell, and 20% expanded shale)	NR - based on media volume and should approximately follow stoichiometry
6	Shao et al., 2010	Literature review of sulfur based denitrification, packed bed reactor (PBR) results reported.	Literature review	Varied	NR	48-2688	NR

A potential concern associated with the use of sulfur media biofilters is the effluent sulfate concentration, which was previously discussed in Section 3.2. Effluent sulfate concentrations for sulfur biofilters are summarized in Table 6-7. Mean effluent sulfate levels were below the secondary drinking water standard of 250 mg/L for all systems utilizing sulfur media.

**Table 6-7: Effluent Sulfate**

System	Stage 1 Operation <sup>1</sup>	Effluent Sulfate, mg/L			
		Mean	Standard Deviation	Min	Max
BHS-2	R tank	192	28	170	240
	R internal	209	54	160	320
BHS-3	Drip SP	114	57	27	250
BHS-4	SP	37	18	21	71
BHS-5	SP	68	20	29	98
	R internal	248	71	160	330
BHS-6	SP	136	37	64	190

<sup>1</sup>R tank = recirculation to tank

R internal = recirculation to top of Stage 1 media


SP = single pass

## 6.2.2 Estimates of Media Life

Studies in the literature suggest very long life spans for lignocellulosic denitrification biofilters (Schipper et. al., 2010). Robertson et al. (2008) reported on a lignocellulosic reactive barrier wall that had been removing nitrate from groundwater for 15 years, and samples taken from the wall in year 15 indicated the wall was still functional with a 4 g N/m<sup>3</sup>-day denitrification rate, approximately 50% less than the rate in year 1. Several studies have shown leaching of carbon content during the first few months of operation of lignocellulosic bioreactors; however, the denitrification rates were still sufficient to account for nitrate removal for five years and greater following initial startup (Schipper et. al., 2001).

Moorman et al. (2010) studied an in situ wood chip bioreactor receiving influent nitrate levels of 20-25 mg NO<sub>3</sub>-N/L for 8 years, and measured the loss of wood. The half-life of the reactive media was estimated to be over 36 years in the saturated zone under anaerobic conditions. Based on these and other literature sources, it appears that lignocellulosic denitrifying systems could be designed for many years of life.

The lifespan of the lignocellulosic biofilters is difficult to calculate. However, if an assumption that the lignocellulosic organic carbon material is consumed only by the heterotrophic denitrification equation (Schmidt and Clark, 2012) a theoretical calculation of media life can be made.



The longevity of the mass of lignocellulosic media to denitrify the mean NO<sub>x</sub>-N supplied to each treatment system was estimated using the total wastewater volume applied, mean NO<sub>x</sub>-N concentration applied and stoichiometric relationships for lignocellulosic based heterotrophic denitrification (Eq. 6-3). Results of these calculations are presented in Table 6-8. From the calculations, it appears that Stage 2 denitrification biofilters using lignocellulosic media can be designed to last many years. Additionally, the media for in-tank Stage 2 biofilters is easily replenished via manholes above the biofilter if needed to maintain performance goals.

**Table 6-8: Lignocellulosic Media Life**


<b>System</b>	<b>Mode of Operation</b>	<b>Percent reactive media</b>	<b>Volume of Lignocellulosic Media, ft<sup>3</sup></b>	<b>Calculated Longevity<sup>1</sup>, years</b>	<b>Longevity with factor of safety<sup>2</sup>, years</b>
BHS-1	upflow	100%	194.8	83.8	64.5
BHS-2	Dual media tank	100%	126.0	107.5	82.7
BHS-3	in-ground liner	50%	136.5	80.8	62.2
BHS-4	Dual media tank	100%	126.0	21.6	16.6
BHS-5	Dual media tank	100%	126.0	43.6	33.5
BHS-6	Stacked Stage1/Stage 2	100%	67.0	39.1	30.1
BHS-7 (ligno/liner water)	in-ground liner	100%	362.0	176.2 <sup>3</sup>	135.5 <sup>3</sup>
PNRS II 17-LS-50	horizontal	50%	0.6	20.2	15.5
PNRS II 9-LS-25	upflow	25%	1.3	5.4	4.1
PNRS II 7-LS-50	upflow	50%	2.6	8.4	6.5
PNRS II 10-LS-30	upflow	30%	1.6	13.4	10.3

<sup>1</sup> Assumptions regarding lignocellulosic media included: dry bulk density of 20 lb./ft<sup>3</sup>; 50% carbon content by weight with available carbon being approximately 50% of carbon content

<sup>2</sup> Factor of safety used was 1.3

<sup>3</sup> The longevity calculation is based on the liner water samples (essentially complete NO<sub>x</sub>-N reduction). Our opinion is that for this system the majority of the effluent did not go through the lignocellulosic liner media; however the design could be modified to direct all effluent to the liner media, and the calculated longevity presented would be the result.


As discussed in Section 3, autotrophic denitrification with elemental sulfur can be represented with the following biochemical reaction (Batchelor and Lawrence, 1978; Smith, 2009a):





Based on this equation, for each gram of  $\text{NO}_3\text{-N}$  removed approximately 2.29 grams of sulfur are utilized and 6.87 grams of sulfate are generated. Sample ports were installed along the depth of the Stage 2 biofilters to enable longitudinal profiling of nitrogen species and other water quality parameters. Solute profiles of the Stage 2 sulfur-containing denitrification biofilters showed significant decline in  $\text{NO}_x\text{-N}$  concentration and increase in sulfate concentration at the entrance region (see Figure 6-7, 6 inches from inlet). During PNRS pilot work, the sulfate concentration in the biofilter did not increase substantially after  $\text{NO}_x\text{-N}$  (and presumably DO) were depleted. However, Figure 6-7 shows an increase in sulfate after  $\text{NO}_x\text{-N}$  depletion which may be attributed to air entering the Stage 2 biofilter and increasing DO near the sulfur media for some of the systems (BHS-2 Day 436; BHS-3 Day 523 and BHS-5 Day 524).

**Figure 6-7: Solute Profiles for Stage 2 Sulfur Biofilters**



The theoretical longevity of the sulfur media for each Stage 2 sulfur-containing biofilter was estimated using the total wastewater volume, mean  $\text{NO}_x\text{-N}$  concentrations applied and stoichiometric relationships for sulfur based autotrophic denitrification (Eq. 6-4). The theoretical longevity of sulfur media are summarized in Table 6-9. Based on equation 6-4, the moles of sulfate produced is equivalent to the moles of  $\text{NO}_3\text{-N}$  reduced. Therefore, the solute profile results were used to determine a ratio of mole

sulfate produced to mole  $\text{NO}_3\text{-N}$  reduced for each of the treatment systems which includes the effect of dissolved oxygen. The mean 12-inch profile results indicate that the sulfate produced through the biofilter was 1.2 times greater than the mole of  $\text{NO}_3\text{-N}$  removed. Therefore, a factor of safety of 1.3 was applied to estimates of the longevity of the sulfur media. The estimated sulfur media longevity for the home systems under the study conditions is generally high (ranged from 44 to 400 years) which was determined using the lignocellulosic biofilter mean effluent  $\text{NO}_x\text{-N}$  as the applied concentration. As expected, the sulfur media longevity using the higher effluent  $\text{NO}_x\text{-N}$  in Stage 1 as the applied concentration to the sulfur biofilter decreases theoretical sulfur longevity to a range from 20 to 149 years.

**Table 6-9: Sulfur Media Life**

System	Percent Reactive Media	Volume of sulfur media, $\text{ft}^3$	Study Conditions			If Lignocellulosic Media is Depleted		
			Mean influent $\text{NO}_x\text{-N}$ , $\text{mg-N/L}$	Longevity <sup>1</sup> , years	Longevity with factor of safety <sup>2</sup> , years	Stage 1 Mean Effluent $\text{NO}_x\text{-N}$ , $\text{mg-N/L}$	Longevity <sup>1</sup> , years	Longevity with Factor of Safety <sup>2</sup> , years
BHS-2	90%	32.4	0.02	N/A	N/A	16.7	194.0	149.2
BHS-3	90%	34.7	5.8	461.2	354.8	23.9	112.2	86.3
BHS-4	90%	24.3	3.2	348.5	268.0	33.6	27.2	20.9
BHS-5	90%	24.3	4.1	520.5	400.4	43.4	53.5	41.1
BHS-6	90%	18.0	24.9	57.2	44.0	42.3	34.0	26.1
PNRS II 15-SU-80	80%	0.9	23.8	204.7	157.5	N/A	N/A	N/A
PNRS II 16-SU-30	30%	0.4	23.8	75.5	58.1	N/A	N/A	N/A
PNRS II 8-SU-80	80%	4.2	37.9	72.5	55.8	N/A	N/A	N/A
PNRS II 6-SU-30	30%	1.6	41.2	25.4	19.6	N/A	N/A	N/A

<sup>1</sup> Assumptions regarding sulfur media included: dry bulk density of 76  $\text{lb./ft}^3$  and influent  $\text{NO}_x$  concentrations from the preceding process. In systems where lignocellulosic denitrification preceded the sulfur, low influent  $\text{NO}_x$  concentrations resulted in very long estimates of longevity.

<sup>2</sup> Factor of safety used was 1.3

### 6.3 Overall System Performance

The PNRS mean effluent TN concentrations and other water quality constituents of interest are summarized in Table 6-10. The mean effluent Total Nitrogen (TN) concentration for the seven prototype PNRS ranged from 1.8 to 19.1 mg/L. The highest mean TN effluent concentrations can be attributed to the BHS-7 design issues previously discussed. The most refined and best performing prototype systems (BHS-2, BHS-3 and BHS-5) produced a mean effluent TN concentration of 2.6 mg/L. Other water quality constituents of interest include carbonaceous biochemical oxygen demand (CBOD<sub>5</sub>), total suspended solids (TSS) and total phosphorus (TP).

**Table 6-10: Summary of Mean Effluent Water Quality Constituents of Interest**

System	Stage 1 Operation <sup>1</sup>	Mean TN, mg/L	Mean CBOD <sub>5</sub> , mg/L	Mean TSS, mg/L	Mean TP, mg/L
BHS-1	R tank	7.1	27.3	3.5	7.6
BHS-2	R tank	3.5	67.6	6.8	4.9
	R internal	1.8	54.9	2.4	4.3
BHS-3	In-ground drip SP	1.9	14.3	4.3	0.2
BHS-4	SP	7.4	12.3	4.1	2.6
BHS-5	SP	2.3	9.4	2.3	1.1
	R internal	1.8	15.5	3.3	1.3
BHS-6	SP	12.4	8.3	3.6	4.1
BHS-7	In-ground LP	19.1	12.4	4.4	0.7

<sup>1</sup>R tank = recirculation to tank

R internal = recirculation to top of Stage 1 media

SP = single pass

LP = low pressure distribution

The objective of the FOSNRS Task B was to perform field demonstrations under actual operating conditions of full scale prototype PNRS to critically assess these nitrogen reduction technologies. Therefore the primary water quality constituent for assessing overall system performance is total nitrogen (TN) removal efficiency. The overall system TN removal efficiencies and other water quality constituents of interest are summarized in Table 6-11. The mean Total Nitrogen (TN) removal efficiency for the seven full scale prototype passive two-stage nitrogen removal systems ranged from 65 to 98% with an overall mean of 90% for all systems. However, the nitrogen removal efficiency of the three most refined and best performing prototype systems (BHS-2, BHS-3 and BHS-5) averaged over 95% TN removal. The two lowest performing PNRS (BHS-6 and BHS-7) showed the potential to achieve similar TN removal efficiencies at times, but their performance was hampered by less than optimal design or construction issues.

The mean CBOD<sub>5</sub> removal efficiency for the seven full scale prototype passive two-stage nitrogen removal systems ranged from 36 to 91% with an overall mean of 79% for all systems. The mean Stage 2 effluent in most of the systems showed an increase in CBOD<sub>5</sub> concentration as compared to the Stage 1 effluent which may be attributed to CBOD<sub>5</sub> release from the lignocellulosic media itself. The BHS-2 system which incorporated a sawdust lignocellulosic media is associated with the highest concentration of Stage 2 CBOD<sub>5</sub>. The mean TSS removal efficiency for the seven full scale prototype passive two-stage nitrogen removal systems ranged from 76 to 97% with an overall mean of 89% for all systems. The mean effluent TSS concentration for all seven systems was below 10 mg/L.

The mean Total Phosphorus (TP) removal efficiency for the seven full scale prototype passive two-stage nitrogen removal systems ranged from 12 to 96% with an overall mean of 64% for all systems. The best performing PNRS were the in-ground systems (BHS-3 and BHS-7). An evaluation of the long term phosphorus adsorption capacity of the evaluated media was not conducted as part of this study, and phosphorus removal may decline at some future point when P adsorption sites become limiting.

The geomean of effluent fecal coliform concentration for the seven prototype PNRS ranged from 1 to 1,838 ct/100 mL. The highest geomean fecal coliform count can be attributed to the BHS-6 design issues previously discussed. The most refined and best performing prototype systems (BHS-2, BHS-3 and BHS-5) produced an effluent fecal coliform concentration below 60 ct/100 mL.

**Table 6-11: Overall Performance of Prototype PNRS**

<b>System</b>	<b>Stage 1 Operation<sup>3</sup></b>	<b>Mean TN Removal Efficiency, %</b>	<b>Mean CBOD<sub>5</sub> Removal Efficiency, %</b>	<b>Mean TSS Removal Efficiency, %</b>	<b>Mean TP Removal Efficiency, %</b>
BHS-1	R tank	91%	75%	93%	12%
BHS-2	R tank	93%	36%	76%	40%
	R internal	97%	78%	97%	51%
BHS-3	Drip SP	96%	80%	81%	96%
BHS-4	SP	89%	91%	93%	72%
BHS-5	SP	97%	87%	94%	85%
	R internal	98%	86%	90%	83%
BHS-6 <sup>1</sup>	SP	81%	90%	87%	49%
BHS-7 <sup>2</sup>	In-ground LP	65% <sup>2</sup>	87% <sup>2</sup>	88% <sup>2</sup>	90% <sup>2</sup>

<sup>1</sup>Clogging of internal drainage and distribution pipes within this system caused flooding of the Stage 1 media on several occasions, which hampered performance. Different construction materials for drains and a revised design would eliminate these problems.

<sup>2</sup>The reported values are calculated using the mean perimeter monitoring samples. Since it is believed that the hydraulics of the system as designed did not allow most flow to pass through the liner media, this reduction is most likely not attributed to lignocellulosic media, but to reductions in the Stage 1 media. A revised liner design could solve this problem.

<sup>3</sup>R tank = recirculation to tank


R internal = recirculation to top of Stage 1 media

SP = single pass

LP = low pressure distribution

An overall analysis of PNRS performance is presented here for the first six prototype PNRS (BHS-1 through BHS-6). The prototype BHS-7 in-ground system was excluded from the overall performance analysis for reasons discussed previously. The total nitrogen removal efficiency time series for each system is presented in Figure 6-8 and mean total nitrogen concentrations are presented in Figure 6-9.


**Figure 6-8: Overall PNRs Total Nitrogen Removal Efficiency Time Series**



<sup>1</sup> System BHS-1 Stage 1 mode of operation was revised from R tank to R internal on experimental day 316

<sup>2</sup> System BHS-5 Stage 1 mode of operation was revised from single pass to R internal on experimental day 290





A summary of the total nitrogen mass balance through each process of the treatment trains is summarized in Table 6-12. System BHS-2 mass balances for the two recirculation modes of operation tested illustrate greater Stage 1 biofilter total nitrogen reduction utilizing recirculation to a recirculation tank as compared to internal recirculation (60% as compared to 33%).

**Table 6-12: Total Nitrogen Mass Balance for Prototype PNRs**

<b>System</b>	<b>Parameter, units</b>	<b>Influent (STE)</b>	<b>Stage 1 Biofilter Effluent</b>	<b>Stage 2 Lignocellulosic Effluent</b>	<b>Stage 2 Sulfur Effluent</b>
BHS-1 (R tank)	g TN/day	35.03	18.85	3.01	NA
	g TN/day reduction from previous unit process	NA	16.18	15.84	NA
	% reduction from STE	NA	46.19	91.41	NA
BHS-2 (R tank)	g TN/day	20.86	8.18	1.16	1.45
	g TN/day reduction from previous unit process	NA	12.68	7.02	-0.29
	% reduction from STE	NA	60.79	94.46	93.07
BHS-2 (R internal)	g TN/day	24.59	16.38	2.68	0.77
	g TN/day reduction from previous unit process	NA	8.21	13.70	1.91
	% reduction from STE	NA	33.39	89.10	96.89
BHS-3 (in-ground)	g TN/day	27.66	14.24	4.29	1.05
	g TN/day reduction from previous unit process	NA	13.42	9.95	3.25
	% reduction from STE	NA	48.51	84.48	96.22
BHS-4 (SP)	g TN/day	78.82	51.23	13.28	8.35
	g TN/day reduction from previous unit process	NA	27.59	37.96	4.92
	% reduction from STE	NA	35.00	83.16	89.40
BHS-5 (SP)	g TN/day	30.58	21.54	2.92	0.98
	g TN/day reduction from previous unit process	NA	9.04	18.62	1.94
	% reduction from STE	NA	29.58	90.45	96.79
BHS-5 (R internal)	g TN/day	35.08	28.86	16.29	0.83
	g TN/day reduction from previous unit process	NA	6.22	12.57	15.46
	% reduction from STE	NA	17.73	53.55	97.63
BHS-6 (SP vertically stacked)	g TN/day	78.82	51.23	13.28	8.35
	g TN/day reduction from previous unit process	NA	27.59	37.96	4.92
	% reduction from STE	NA	35.00	83.16	89.40

**Table 6-12 (cont.): Total Nitrogen Mass Balance for Prototype PNRS**

<b>System</b>	<b>Parameter, units</b>	<b>Influent (STE)</b>	<b>Stage 1 Biofilter Effluent</b>	<b>Stage 2 Lignocellulosic Effluent</b>	<b>Stage 2 Sulfur Effluent</b>
BHS-7 (in-ground)	g TN/day	26.07	13.72	9.06 <sup>1</sup>	NA
	g TN/day reduction from previous unit process	NA	12.35	4.66 <sup>1</sup>	NA
	% reduction from STE	NA	47.37	65.25 <sup>1</sup>	NA

<sup>1</sup>The reported value is the mean of the perimeter monitoring locations. Since it is believed that the hydraulics of the system did not allow flow into and through the liner media, this reduction is most likely not attributed to lignocellulosic media, but to TN reductions in the stage 1 media.

Other water quality constituents of interest include carbonaceous biochemical oxygen demand (CBOD<sub>5</sub>), total suspended solids (TSS) and total phosphorus (TP). Figures 6-10 through 6-12 summarize respectively the mean CBOD<sub>5</sub>, TSS and TP concentrations for influent and effluents of each PNRS process. Figures 6-13 through 6-15 depict the mean fecal coliforms, sulfate and total alkalinity concentration for each process, respectively.





Figure 6-11: Overall Prototype Systems Mean TSS Removal Performance



<sup>1</sup> The BHS-6 Stage 1 samples from this vertically stacked system were taken from pan lysimeters placed at the expanded clay/lignocellulosic interface. It is suspected that pumping samples up from these pans included some fines from the expanded clay media, thus the increase in TSS over the influent value.

**Figure 6-12: Overall Prototype Systems Mean Total Phosphorus Removal Performance**









Figure 6-13: Overall Prototype Systems Geomean Fecal Coliform



**Figure 6-14: Overall Prototype Systems Mean Sulfate for Systems using Sulfur in Stage 2**



**Figure 6-15: Overall Prototype Systems Mean Total Alkalinity**





-THIS PAGE INTENTIONALLY LEFT BLANK-

## 7 Life Cycle Cost Analysis

The LCCA tool developed by the project team to provide planning level life cycle costs for the PNRS was used to evaluate the seven prototype PNRS evaluated in FOSNRS Task B. This section summarizes the LCCA result for each PNRS installed and provides a comparison to the actual reported as-built installation costs.

### 7.1 Life Cycle Cost Analysis Tool (PNRS LCCA)

The PNRS LCCA (Life Cycle Cost Analysis Tool for Passive Nitrogen Removal Systems) is a computer spreadsheet tool developed by the FOSNRS Project Team to estimate planning level life cycle costs for PNRS. However, the PNRS LCCA tool incorporates three approaches for application of the tool:

- Planning level PNRS LCCA, the user specifies a desired nitrogen removal efficiency range: low, medium or high. The PNRS LCCA calculates planning level LCCA for user specified nitrogen removal efficiency range.
- Specific PNRS LCCA, the user specifies known performance nitrogen removal efficiency for a specific treatment system with known performance data. The PNRS LCCA calculates planning level LCCA for user specified performance data.
- Non-PNRS LCCA, the user specifies a user defined level of nitrogen removal efficiency, installed cost of the advanced treatment technology, performance data and other system costs. The PNRS LCCA calculates an estimated LCCA for user specified data.

For the planning level PNRS LCCA, the user specifies a desired nitrogen removal efficiency range: low, medium or high. Additional details regarding the nitrogen reduction framework for removal efficiency are provided in Section 8. The planning level PNRS LCCA provides selections for treatment processes that achieve the selected nitrogen removal range and estimates the costs to meet the selected nitrogen removal efficiency range. The planning level PNRS LCCA incorporates all system costs over the entire project life, including construction, engineering fees, state and county permitting, system maintenance, media and pump replacement, water quality monitoring and energy, as well as primary treatment solids removal (Hazen & Sawyer and AET, 2015). PNRS LCCA applies discounting to future costs at a specified net interest rate to derive the Present Worth (PW) of a PNRS, also termed Net Present Value (NPV). PNRS LCCA estimates Present Worth (PW) for both the entire treatment system (conventional OSTDS components + PNRS) and for the conventional OSTDS components alone (primary tank and soil treatment unit). PNRS LCCA provides detailed cost breakouts for each life cycle analysis in both tabular and graphical

format. Estimates are provided for the mass of nitrogen removed by each system and the unit cost of nitrogen removed (\$PW/lb. nitrogen). Additional details on the PNRS LCCA tool can be found in the LCCA Report and User Guidelines (Hazen & Sawyer and AET, 2015).

The PNRS LCCA also has a built-in function to allow evaluation of a specific treatment system with known performance data. The user has the ability to override the default nitrogen removal efficiency for the selected planning level nitrogen removal range. This approach was used in the evaluation of the seven FOSNRS Task B prototype PNRS BHS1 through BHS7, and those results are provided in Section 7.3.

Although the planning level default system sizing and cost data in PNRS LCCA are based on the OSTDS code and planning level costs in Florida, the tool allows user specific inputs which allow its use elsewhere, with some limitations. For example, the PNRS LCCA can be used to evaluate a user defined nitrogen removal efficiency for non-PNRS. The 'User Defined' level of treatment is selected, and the user inputs the nitrogen removal efficiency, installed cost of the advanced treatment technology, energy use, and other system costs. The PNRS LCCA derives the PW for the user defined system. This approach was used to compare the Task B prototype PNRS with other advanced treatment technologies with similar data from a study conducted in Maryland as summarized in Section 7.5.

## 7.2 Application of PNRS LCCA

PNRS LCCA was applied to the seven prototype PNRS studied in Task B, and listed in Table 7-1. These PNRS each included Stage 1 and Stage 2 biofiltration processes. All systems were designed for high level nitrogen removal, however not all systems met that level of treatment during the study as previously discussed. The overall performance mean TN removal efficiency and mean energy consumption for the prototype PNRS was input into the PNRS LCCA tool by using the user override function. Additional sources of input data to the PNRS LCCA analysis included:

- Permit data for each system (no. bedrooms, building area, permitted design flow, STU area, STU configuration, STU loading rate and depth to seasonal high water table). Note: PNRS LCCA embedded nitrogen load calculation was used where the number of occupants is equal to the number of bedrooms, and the residential wastewater nitrogen load is 11.2 grams of nitrogen per capita (person) per day (USEPA, 2002).
- Conventional and PNRS components data from installation reports for each prototype PNRS
- Florida Department of Health and counties permitting fee structures
- Electrical rates from Florida utilities



- Mean energy use for the study period
- Service Provider costs for inspection and maintenance visits and water quality monitoring

To provide a uniform basis for comparison of results, several inputs to PNRS LCCA were kept the same for all systems. These included:

- Project life of 30 years
- Net interest rate of 2.0%
- Two inspection and maintenance visits per year
- One water quality monitoring event per year of equal cost (\$120)
- Primary treatment system solids removal every five years of equal cost (\$250)
- Stage 2 media replacement every 15 years for in-tank systems; 30 years for in-ground systems
- Pump replacement every ten years

**Table 7-1: Seven PNRS Evaluated**

System ID	First Stage			Second Stage	PNRS LCCA Level of Treatment	User Override TN Removal Efficiency, %
	Media	Enclosure	Hydraulics <sup>1</sup>	Media (In-tank)		
BHS-1	Aerocell™	tank	R tank	Nitrex™	High	91
BHS-2	ex clay	tank	R tank	dual media ligno-sulfur	High	93
BHS-3	stacked sand/ligno	in-ground liner	SP	sulfur	High	96
BHS-4	ex clay	tank	SP	dual media ligno-sulfur	High	89
BHS-5	ex clay	tank	SP	dual media ligno-sulfur	High	97
BHS-6	stacked ex clay/ ligno	tank	SP	sulfur	High	81
BHS-7	stacked sand/ligno	in-ground liner	SP		Medium	65

<sup>1</sup>R tank = recirculation to tank

SP = single pass

A brief summary of PNRS LCCA application for each prototype PNRS evaluated is included here. The default costs embedded within PNRS LCCA were used without adjustment for four systems, while user override cost adjustments were applied for BHS-1, BHS-4 and BHS-6 as noted below.

- **BHS-1** Stage 1 was a commercial proprietary Stage 1 system (Aerocell™) followed by a commercial proprietary Stage 2 system (Nitrex™). Although individual components were proprietary, the packaged system was considered prototype as it was the first such system installed under a “passive nitrogen reduction” definition. Installed cost of the Stage 1 system is taken directly from cost documentation supplied by the vendor. An engineer design cost of \$700 was entered into PNRS LCCA, which when added to the embedded engineer design cost of \$1,000 for PNRS equaled the vendor cost of \$1,700 for engineer design plus as-built engineering design. Electricity use was input using the Task B study period average daily electrical use measured for the home system of 3.21 kWh per day. Cost estimates for Stage 2 were based on those for lignocellulosic Stage 2 biofilters embedded in the PNRS LCCA. User override costs were entered for conventional system pump and conventional system energy cost.
- **BHS-2** Stage 1 and 2 were prototype PNRS designed for the site. Costs included a new primary tank. All costs were PNRS LCCA embedded costs.
- **BHS-3** Stage 1 and 2 were prototype PNRS designed for the site. Costs included a new primary tank and new drip dispersal system. All costs were PNRS LCCA embedded costs.
- **BHS-4** Stage 1 and 2 were prototype PNRS designed for the site. Costs included a new STU. User override costs were specified for STU, PNRS tankage and media.
- **BHS-5** Stage 1 and 2 were prototype PNRS designed for the site. An existing primary tank and STU was present, so no conventional system costs were incurred. All costs were PNRS LCCA embedded costs.
- **BHS-6** Stage 1 and 2 were prototype PNRS designed for the site. No conventional system costs incurred. User override costs were specified for PNRS tankage, media, pump and control panel and contractor fee.
- **BHS-7** Stage 1 and 2 were prototype PNRS designed for the site. No conventional system costs were incurred. All costs were PNRS LCCA embedded costs. However, the BHS-7 PNRS design included a low pressure distribution system utilizing a pump and pump tank. The PNRS LCCA default system design for a lined in-ground Stage 1 biofilter underlain by lignocellulosic media assumes a gravity system if the depth to seasonal high water table is greater than 54 inches. To

have the PNRS LCCA include the cost of a pump and pump tank for the BHS-7 system as designed, the LCCA user specified input depth to seasonal high water table was input as 53 inches even though the seasonal high water table at the site is greater than 72 inches.

### **7.3 PNRS LCCA Results**

Detailed life cycle cost output reports generated by PNRS LCCA for each of the evaluated prototype PNRS are presented in Tables 7-2 through 7-8. PNRS LCCA cost estimates for the total systems (including PNRS and conventional treatment components, as required for retrofit) are summarized in Table 7-9. Also shown are as-built construction costs estimated from the Task B full scale system installation reports. Adjustments were made to the full scale costs to reflect treatment system construction costs only, e.g. costs for permitting, experimental monitoring equipment and other non-construction costs were removed. PNRS LCCA construction cost estimates for PNRS treatment components only are listed in Table 7-10.



-THIS PAGE INTENTIONALLY LEFT BLANK-



Table 7-2: PNRS LCCA Results Output for BHS-1 PNRS








Table 7-3: PNRS LCCA Results Output for BHS-2 PNRS

PNRS LCCA: Planning Level Life Cycle Cost Analysis Tool for Passive Nitrogen Reduction Systems  
LCCA Identification: BHS-2

Worksheet

1. LCCA Structure

2. Table of LCCA Worksheets

3. WW Quantity & System Parameters

4. PNRS Process Selection

5. Baseline Design & Cost

6. Baseline Design Cost Summary

7. User Override Costs

8. LCCA Conventional

9. LCCA Total System

10. Design Data

11. Example LCCAs

9. LCCA Total System

Present Worth (2015 dollars)

Installed Capital Cost

Engineering Design & Construction Permit

Operation & Maintenance

Compliance

Installed Capital Cost

Soil Treatment Unit

Proprietary Stage 1 System

Media

Pump(s)

Control Panel

Misc. Appurtenance

Piping

Drip Dispersal Unit Complete (control panel, valves, tubing, etc.)

Liner

Conventional System Summary

No. of Bedrooms

3

Building area, square feet

2542

Depth to seasonal high water table (inches)

12

New OSTDS installation or retrofit of existing system

retrofit

Design wastewater flow, gallon/day

360

User override Conventional costs have been specified

PNRS System Summary

PNRS System

9

Stage 1: PNRS or proprietary

PNRS

PNRS Stage(s)

Stage 1&2

Stage 1 in-tank or in-ground

Tank

Stage 1 single pass or recirculation

Recirculation

Stage 1 media type

Expanded Clay

Ligno disposition

Tank

Stage 2 media type

Dual: Ligno & sulfur

Construction Complexity

Moderate

Level of nitrogen removal efficiency provided by system

High

User override PNRS costs have been specified

User Override Nitrogen Removal Efficiency

Life Cycle Cost Calculations

Project Life (PL), years

30

Interest Rate (IR), %

2.000

Primary tank pump out interval (TI), years

5.0

Pump out analysis life (PL), years

25.0

Stage 2 media replacement interval (MI), years

15.0

Stage 2 media cost analysis life (ML), years

15.0

Equipment replacement interval (EI), years

10.0

Equipment replacement analysis life (EL), years

20.0

Compound Interest Factors

P/A PL/IR

22.396

A/P PL/IR

0.04465

A/F TI

0.19216

P/A PL

19.523

A/F MI

0.05783

P/A ML

12.849

A/F EI

0.09133

P/A EL

16.351

Nitrogen Removal

Mass loading/year, lbs.

27.0

Removal efficiency, %

93.0

Mass removal/year, lbs.

25.12

Life Cycle Cost

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Total Life Cycle Cost

Conventional System Installation

Primary treatment tank

1,400.00

62.51

4.2

Pump tank

600.00

26.79

1.8

Conventional system pump

0.00

0.00

0.0

Soil treatment unit

326.00

14.56

1.0

Subtotal Conventional

2,326.00

103.86

7.0

Proprietary Stage 1 system

0.00

0.00

0.0

PNRS Installation

Tankage

5,489.90

245.12

16.6

Media

2,000.07

89.30

6.0

PNRS Pump

250.00

11.16

0.8

Control Panel

1,200.00

53.58

3.6

Piping

318.56

14.22

1.0

Misc. Appurtenance

1,862.30

83.15

5.6

Stage 1 Drip Dispersal System Complete (control panel, valves, tubing, etc.)

0.00

0.00

0.0

Liner

0.00

0.00

0.0

Contractor Fee

5,000.00

223.25

15.1

Subtotal

16,120.83

719.79

48.6

Total System Installation

18,446.83

823.65

55.6

Engineering Design & Construction Permit

Construction permit

710.00

31.70

2.1

Engineering design fees

1,000.00

44.65

3.0

Operation and Maintenance

Annual energy cost

230.61

10.30

0.7

Annual inspection & maintenance

6,718.94

300.00

20.3

Primary tank pump out

937.90

41.88

2.8

Stage 2 media replacement

569.13

25.41

1.7

Equipment replacement

746.66

33.34

2.3

Subtotal

9,203.23

410.92

27.7

Compliance

Operating permit fee

1,119.82

50.00

3.4

Water quality monitoring

2,687.57

120.00

8.1

Subtotal

3,807.40

170.00

11.5

Total

33,167.46

1,480.92

100.00

Installed Capital Cost

Installation

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Installation Cost

Tankage

7,489.90

334.42

40.6

Soil Treatment Unit

326.00

14.56

1.8

Proprietary Stage 1 System

0.00

0.00

0.0

Media

2,000.07

89.30

10.8

Pump(s)

250.00

11.16

1.4

Control Panel

1,200.00

53.58

6.5

Misc. Appurtenance

1,862.30

83.15

10.1

Piping

318.56

14.22

1.7

Drip Dispersal Unit Complete (control panel, valves, tubing, etc.)

0.00

0.00

0.0

Liner

0.00

0.00

0.0

Contractor Fee

5,000.00

223.25

27.1

Total System

18,446.83

823.65

100.0

Life Cycle Cost

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Total Life Cycle Cost

Installed Capital Cost

18,446.83

823.65

55.6

Engineering Design & Construction Permit

1,710.00

76.35

5.2

Operation & Maintenance

9,203.23

410.92

27.7

Compliance

3,807.40

170.00

11.5

Total

33,167.46

1,480.92

100.0

\$/lb nitrogen removed

44.01

58.95

Developed by:

HAZEN AND SAWYER

Environmental Engineers & Scientists

and

AET

Advanced Environmental Technology

H&S Project No. 44237-003  
August 2015

7-7








Table 7-4: PNRS LCCA Results Output for BHS-3 PNRS










Table 7-5: PNRS LCCA Results Output for BHS-4 PNRS

PNRS LCCA: Planning Level Life Cycle Cost Analysis Tool for Passive Nitrogen Reduction Systems

LCCA Identification: BHS-4

Worksheet

1. LCCA Structure

2. Table of LCCA Worksheets

3. WW Quantity & System Parameters

4. PNRS Process Selection

5. Baseline Design & Cost

6. Baseline Design Cost Summary

7. User Override Costs

8. LCCA Conventional

9. LCCA Total System

10. Design Data

11. Example LCCAs

9. LCCA Total System

Present Worth (2015 dollars)

Installed Capital Cost

Engineering Design & Construction Permit

Operation & Maintenance

Compliance

Installed Capital Cost

Tankage

Soil Treatment Unit

Proprietary Stage 1 System

Media

Pump(s)

Control Panel

Misc. Appurtenance

Piping

Drip Dispersal Unit Complete (control panel, valves, tubing, etc.)

Liner

Conventional System Summary

No. of Bedrooms

4

Building area, square feet

2517

Depth to seasonal high water table (inches)

60

New OSTDS installation or retrofit of existing system

retrofit

Design wastewater flow, gallon/day

400

User override Conventional costs have been specified

PNRS System Summary

PNRS System

3

Stage 1: PNRS or proprietary

PNRS

PNRS Stage(s)

Stage 1&2

Stage 1 in-tank or in-ground

Tank

Stage 1 single pass or recirculation

Single pass

Stage 1 media type

Expanded Clay

Ligno disposition

Tank

Stage 2 media type

Dual: Ligno & sulfur

Construction Complexity

Moderate

Level of nitrogen removal efficiency provided by system

High

User override PNRS costs have been specified

User Override Nitrogen Removal Efficiency

Life Cycle Cost Calculations

Project Life (PL), years

30

Interest Rate (IR), %

2.000

Primary tank pump out interval (TI), years

5.0

Pump out analysis life (PL), years

25.0

Stage 2 media replacement interval (MI), years

15.0

Stage 2 media cost analysis life (ML), years

15.0

Equipment replacement interval (EI), years

10.0

Equipment replacement analysis life (EL), years

20.0

Compound Interest Factors

P/A PL/IR

22.396

A/P PL/IR

0.04465

A/F TI

0.19216

P/A PL

19.523

A/F MI

0.05783

P/A ML

12.849

A/F EI

0.09133

P/A EL

16.351

Nitrogen Removal

Mass loading/year, lbs.

36.0

Removal efficiency, %

89.0

Mass removal/year, lbs.

32.06

Life Cycle Cost

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Total Life Cycle Cost

Conventional System Installation

Primary treatment tank

0.00

0.00

0.0

Pump tank

0.00

0.00

0.0

Conventional system pump

0.00

0.00

0.0

Soil treatment unit

3,170.75

141.57

9.5

Subtotal Conventional

3,170.75

141.57

9.5

Proprietary Stage 1 system

0.00

0.00

0.0

PNRS Installation

Tankage

5,800.15

258.98

17.4

Media

3,198.73

142.82

9.6

PNRS Pump

0.00

0.00

0.0

Control Panel

0.00

0.00

0.0

Piping

318.56

14.22

1.0

Misc. Appurtenance

1,862.30

83.15

5.6

Stage 1 Drip Dispersal System Complete (control panel, valves, tubing, etc.)

0.00

0.00

0.0

Liner

0.00

0.00

0.0

Contractor Fee

5,000.00

223.25

15.0

Subtotal

16,179.74

722.42

48.5

Total System Installation

19,350.49

864.00

58.0

Engineering Design & Construction Permit

Construction permit

870.00

38.85

2.6

Engineering design fees

1,000.00

44.65

3.0

Operation and Maintenance

Annual energy cost

0.00

0.00

0.0

Annual inspection & maintenance

4,479.29

200.00

13.4

Primary tank pump out

937.90

41.88

2.8

Stage 2 media replacement

688.99

30.76

2.1

Equipment replacement

0.00

0.00

0.0

Subtotal

6,106.18

272.64

18.3

Compliance

Operating permit fee

3,359.47

150.00

10.1

Water quality monitoring

2,687.57

120.00

8.1

Subtotal

6,047.04

270.00

18.1

Total

33,373.71

1,490.13

100.00

Installed Capital Cost

Installation

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Installation Cost

Tankage

5,800.15

258.98

30.0

Soil Treatment Unit

3,170.75

141.57

16.4

Proprietary Stage 1 System

0.00

0.00

0.0

Media

3,198.73

142.82

16.5

Pump(s)

0.00

0.00

0.0

Control Panel

0.00

0.00

0.0

Misc. Appurtenance

1,862.30

83.15

9.6

Piping

318.56

14.22

1.6

Drip Dispersal Unit Complete (control panel, valves, tubing, etc.)

0.00

0.00

0.0

Liner

0.00

0.00

0.0

Contractor Fee

5,000.00

223.25

25.8

Total System

19,350.49

864.00

100.0

Life Cycle Cost

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Total Life Cycle Cost

Installed Capital Cost

19,350.49

864.00

58.0

Engineering Design & Construction Permit

1,870.00

83.50

5.6

Operation & Maintenance

6,106.18

272.64

18.3

Compliance

6,047.04

270.00

18.1

Total

33,373.71

1,490.13

100.0

\$/lb nitrogen removed

34.70

46.49

Developed by:

Hazen and Sawyer

Environmental Engineers & Scientists

and

AET





Table 7-6: PNRS LCCA Results Output for BHS-5 PNRS








Table 7-7: PNRS LCCA Results Output for BHS-6 PNRS











Table 7-8: PNRS LCCA Results Output for BHS-7 PNRS







**Table 7-9: Summary of Construction Costs for Full Scale PNRS LCCA Tool vs. As-built Cost**

System ID	System Description	PNRS LCCA Estimated Total System Costs		Total System As-built Construction Cost for Task B Systems		
		Total PW, \$	Total Construction Cost, \$	Task B Total Construction Cost, \$	Adjustment for permitting, monitoring, and other costs, \$	Task B Total Construction Cost, \$
BHS-1	Proprietary: Stage 1 Aerocell™ Stage 2 Nitrex™	38,269.71	19,748.84	23,600.00	4,994.00	18,606.00
BHS-2	In-tank Stage 1 with R, dual-media Stage 2	33,167.46	18,446.83	19,142.18	1,085.84	18,056.34
BHS-3	In-ground stacked Stage 1 over Stage 2a ligno with supplemental Stage 2b sulfur	53,253.23	33,154.65	40,129.79	8,014.05	32,115.74
BHS-4	In-tank SP Stage 1, dual-media Stage 2	33,373.71	19,350.49	22,030.34	5,933.17	16,097.17
BHS-5	In-tank Stage 1 with R, dual-media Stage 2	37,796.79	20,920.13	22,361.55	4,066.24	18,295.31
BHS-6	In-tank stacked Stage 1 over Stage 2a ligno with supplemental Stage 2b sulfur	30,155.22	12,926.12	13,727.12	3,327.88	10,399.24
BHS-7	In-ground stacked SP Stage 1 over Stage 2 ligno	24,838.19	13,133.85	13,836.66	3,320.81	10,515.86

**Table 7-10: Summary of Estimated Construction Costs by Treatment Component**

<b>System ID</b>	<b>System Description</b>	<b>PNRS LCCA Total Construction Cost, \$</b>	<b>Conv. Component replaced with PNRS retrofit</b>	<b>Conv. Component Construction Cost, \$</b>	<b>PNRS Component Construction Cost, \$</b>
BHS-1	Proprietary: Stage 1 Aerocell™ Stage 2 Nitrex™	19,749	primary tank STU	5,475	14,274
BHS-2	In-tank Stage 1 with R, dual-media Stage 2	18,447	primary tank	2,326	16,121
BHS-3	In-ground stacked Stage 1 over Stage 2a ligno with supplemental Stage 2b sulfur	33,155	primary tank pump tank STU	10,734	22,421
BHS-4	In-tank SP Stage 1, dual- media Stage 2	19,350	STU	3,171	16,180
BHS-5	In-tank Stage 1 with R, dual-media Stage 2	20,920	None	0	20,920
BHS-6	In-tank stacked Stage 1 over Stage 2a lingo with supplemental Stage 2b sulfur	12,926	None	0	12,926
BHS-7	In-ground stacked SP Stage 1 over Stage 2 ligno	13,134	None	0	13,134

Table 7-9 shows the reasonable comparison of PNRS LCCA estimated construction costs to actual as-built construction costs for the various PNRS evaluated. PNRS LCCA is to be used as a planning tool and contains many default values, while the actual construction costs are specific to details at each site, therefore some difference in costs are expected. Overall, PNRS LCCA should provide good planning level estimates of the various PNRS construction costs and life cycle costs of such a system.

The seven prototype systems required varying levels of new conventional OSTDS components (see Table 7-10), depending on site conditions. Some of the sites required a new primary tank and soil treatment unit, while others had conventional treatment components that could be reused within the new PNRS. Table 7-10 provides a comparison of the PNRS LCCA total estimated construction costs for the seven systems, the portion of that cost which was for required conventional treatment components and the estimated

construction cost of the PNRS components alone. This provides a more representative comparison of the cost of the PNRS installations, and narrows the range of PNRS costs relative to total system costs. Further analyses and comparisons of these cost results are discussed in the following sections.

## 7.4 Comparison of Life Cycle Costs of PNRS

The life cycle costs and unit nitrogen removal costs estimated by PNRS LCCA varied based on the size and complexity of the seven systems. Table 7-11 provides a statistical summary of these key life cycle cost metrics.

**Table 7-11: Key Life Cycle Cost Statistics for Prototype PNRS**


Metric	PNRS LCCA Statistics for the Seven PNRS Evaluated			
	Mean	Standard Deviation	Minimum	Maximum
Total PW, \$	35,836	8,940	24,838	53,253
Total Construction Cost, \$	19,669	6,748	12,926	33,155
lb. N removed per year	29.73	10.32	17.56	43.67
\$ PW/ lb. N removed	41.95	7.86	28.85	51.89

### 7.4.1 PNRS Total Present Worth and Construction Costs

The mean Total Present Worth (PW) of life cycle costs and total construction costs estimated by PNRS LCCA were \$35,836 and \$19,669, respectively. Total Present Worth of life cycle costs reflected system complexity and ranged from \$24,838 to \$53,253 (Figure 7-1). Total Present Worth was highest for the dual drip irrigation system at BHS-3 and lower for relatively simpler systems such as BHS-7.


Construction costs estimated by PNRS LCCA ranged from \$12,926 to \$33,155 (Figure 7-1). The construction cost estimate was also highest for the dual drip irrigation system (BHS-3) and lower for relatively simpler systems such as BHS-6 and BHS-7.

**Figure 7-1: Total Present Worth of Life Cycle Costs and Estimated Construction Cost of PNRS from PNRS LCCA**



Estimated construction costs of the seven PNRS averaged 54% of the Total Present Worth of Life Cycle Costs and ranged from 43 to 62% (Figure 7-2). The balance of the Total Present Worth, which ranged from 38 to 57% of the total life cycle cost, includes the non-construction costs such as: site design, inspection and maintenance visits, permits, monitoring, media and pump replacement, energy and primary treatment solids removal. For all home systems evaluated, non-construction costs are a significant component of total life cycle costs.


**Figure 7-2: PNRS Construction Cost as Percentage of Present Worth**



#### 7.4.2 Task B System Construction Costs and PNRS LCCA Estimates


Task B as-built construction costs and PNRS LCCA construction cost estimates are shown in Figure 7-3. PNRS LCCA estimates provided somewhat higher costs than those derived from the Task B installation reports, with an average relative error for all systems of 11% versus the Task B cost. Task B as-built construction costs are plotted in Figure 7-4 versus the PNRS LCCA construction cost estimate. PNRS LCCA provides construction cost estimates that are quite acceptable for planning level analysis.

**Figure 7-3: Comparison of PNRS As-built Construction Costs and  
PNRS LCCA Construction Cost Estimates**






**Figure 7-4: Trend Line for As-built Construction Costs and PNRS LCCA Estimates**



#### 7.4.3 PNRS Present Worth per Mass Nitrogen Removed

The mean Total Present Worth per pound of nitrogen removed for all the prototype PNRS was estimated by PNRS LCCA as \$41.95. Cost per nitrogen mass removed ranged from \$29 to 52 (Figure 7-5). Present Worth per pound of nitrogen removed is affected by all system costs, the nitrogen generation rate of the home occupants and the nitrogen reduction efficiency of the PNRS.

**Figure 7-5: PNRS Present Worth per Mass of Nitrogen Removal**



## 7.5 Comparison of Life Cycle Costs to Other Studies

The Maryland Department of the Environment initiated the Bay Restoration Fund (BRF) Program (2015) in an effort to reduce nitrogen loading to the Chesapeake Bay. The program evaluated several best available technologies for OSTDS nitrogen removal and determined a field verified mean percent TN reduction based on arithmetic mean of the effluent for each technology tested (Maryland DEP, 2015). Therefore, as a comparison to the FOSNRS prototype PNRS, LCCA were performed for BRF technologies. BRF LCCA incorporated the reported capital cost, percent TN reduction and energy use to determine a present worth in \$/lb. N removed and total present worth. Similar LCCA were also performed for six PNRS technologies incorporating the PNRS LCCA embedded capital costs, PNRS Task B testing mean energy use and the PNRS Task B testing mean percent TN reduction. The standard inputs into the LCCA comparison for all systems included:

- 3 bedroom single family home of 2,200 ft<sup>2</sup> area. Note: PNRS LCCA embedded nitrogen load calculation was used where the number of occupants is equal to the number of bedrooms, and the

residential wastewater nitrogen load is 11.2 grams of nitrogen per capita (person) per day (USEPA, 2002).

- Cost of 900 gallon septic tank
- Cost of 375 ft<sup>2</sup> soil treatment unit trench configuration designed for 0.8 gal/ft<sup>2</sup>-day loading rate
- 42 inch depth to seasonal high water table at soil treatment unit
- Cost of Florida PBTS construction and operating permit (State fees)
- Electrical rate of \$0.1/kw-hour
- Two inspection and maintenance visits per year at a cost of \$150 per visit except for FOSNRS High In-tank gravity Stage 1 single pass, Stage 2 dual media and FOSNRS Medium In-ground Stage 1/2a (ligno) which were run at a cost of \$100 per visit because of relative system simplicity
- One water quality monitoring event per year of equal cost (\$120)
- Primary treatment system solids removal every five years of equal cost (\$250)
- Project life of 30 years
- Net interest rate of 2 percent
- Stage 2 media replacement and equipment replacement were not included in this PNRS LCCA for comparison purposes because similar information was not available for BRF technologies

The Present Worth per pound of nitrogen removed for the technologies ranged from \$40.00 to 64.54 (Table 7-12) which is compared with the percent total nitrogen removed in Figure 7-6. Overall, the present worth per pound of nitrogen removed for the prototype PNRS were less than the BRF technologies, and they achieved higher percent nitrogen removal. It is noteworthy that several PNRS with very high % TN reductions have lower PW cost per pound of nitrogen removed than systems with lower TN removal efficiency (Figure 7-6). It also should be noted that the systems evaluated in the FOSNRS project were prototype systems, installed at existing residences, with customized components, which added to their cost. As PNRS are implemented on a wider scale, it is anticipated that considerable reductions in cost can be achieved.

**Table 7-12: Summary of Comparison of Life Cycle Costs**

<b>Study</b>	<b>System Description</b>	<b>Field Tested Mean % TN Reduction</b>	<b>Field Tested Mean Energy Use, kWhr/day</b>	<b>Total PW, \$1000s</b>	<b>PW, \$/lb N removed</b>
FOSNRS	FOSNRS Medium In-ground Stage 1/2a (ligno) <sup>1</sup>	84.5 <sup>1</sup>	0.98 <sup>1</sup>	27.39	40.00
FOSNRS	FOSNRS High In-ground Stage 1/2a + Stage 2b tank <sup>2</sup>	96.2 <sup>2</sup>	0.98 <sup>2</sup>	34.46	44.20
FOSNRS	FOSNRS High In-tank Stage 1 R tank, Stage 2 dual media <sup>3</sup>	93.1 <sup>3</sup>	0.31 <sup>3</sup>	33.46	44.34
FOSNRS	FOSNRS High In-tank gravity Stage 1 SP, Stage 2 dual media <sup>4</sup>	89.4 <sup>4</sup>	0.00 <sup>4</sup>	33.23	45.86
BRF	BRF AdvanTex AX20RT	76.0	0.92	32.08	52.09
BRF	BRF AdvanTex AX20	71.0	0.92	30.26	52.59
FOSNRS	FOSNRS Medium In-tank Stage 1 + R tank <sup>5</sup>	60.8 <sup>5</sup>	0.31 <sup>5</sup>	27.84	56.50
BRF	BRF Hoot BNR	64.0	2.10	30.67	59.13
BRF	BRF SeptiTech M400D	67.0	4.77	33.45	61.60
BRF	BRF Biomicrobics RetroFast	57.0	3.84	29.38	63.61
BRF	BRF Singulair TNT	55.0	2.68	28.74	64.47
BRF	BRF Singulair Green	55.0	2.68	28.77	64.54

<sup>1</sup> BHS-3 Stage 2 lignocellulosic effluent mean % TN reduction and energy use


<sup>2</sup> BHS-3 Stage 2 sulfur effluent mean % TN reduction and energy use

<sup>3</sup> BHS-2 Stage 2 sulfur effluent mean % TN reduction and energy use

<sup>4</sup> BHS-4 Stage 2 sulfur effluent mean % TN reduction and energy use

<sup>5</sup> BHS-2 Stage 1 effluent mean % TN reduction and energy use

**Figure 7-6: Comparison of Present Worth per Pound Nitrogen Removed and Percent TN Reduction**



<sup>1</sup> BHS-3 Stage 2 lignocellulosic effluent mean % TN reduction

<sup>2</sup> BHS-3 Stage 2 sulfur effluent mean % TN reduction

<sup>3</sup> BHS-2 Stage 2 sulfur effluent mean % TN reduction

<sup>4</sup> BHS-4 Stage 2 sulfur effluent mean % TN reduction

<sup>5</sup> BHS-2 Stage 1 effluent mean % TN reduction

## 7.6 Summary

PNRS LCCA provides a useful planning level tool for Passive Nitrogen Removal Systems for nitrogen removal from residential onsite wastewater treatment systems. For the seven PNRS prototype systems, which varied significantly in design and operation, PNRS LCCA cost estimates were in reasonable agreement with actual Task B construction costs. For all seven prototype systems, PNRS LCCA results highlight that recurring costs are a significant component (approximately 50%) of the total life cycle costs of passive nitrogen removal systems for residential onsite wastewater treatment. Recurring costs must be included in any economic and planning analysis of Passive Nitrogen Removal Systems and alternative technologies as well.



A comparison of the PNRS to the Maryland Department of the Environment BRF best available technologies showed that the PNRS technologies present worth per pound of nitrogen removed were less than the BRF technologies evaluated, and also achieved higher percent total nitrogen removals.



## 8 Recommended Framework for Onsite Wastewater Nitrogen Reduction in Florida

Florida contains a wide variety of landscapes, soils, geology and water resources, each with different sensitivities to nitrogen loading. In some locations, such as Florida's unique springs and the watersheds/springsheds that feed them, significant nitrogen load reductions from all sources including OSTDS may be critical to rehabilitating or maintaining a pristine water quality. In other locations, such as those with deep soils and no direct linkage to surface waters or potable aquifers, nitrogen load reductions from OSTDS may be less critical. Many other locations may require nitrogen load reductions from onsite wastewater systems that lie in between these two options. Anderson and Janicki (2010) provide a good discussion of the difficulties and uncertainty associated with linking nutrient sources to receiving water impacts.

As specific total maximum daily loads (TMDLs) and basin management action plans (BMAPs) are developed for Florida water bodies, it will become important to have a range of available options for nitrogen load reductions from OSTDS, since the cost of nitrogen reducing OSTDS is related to the level of treatment achieved. Therefore, it appears a strategy that includes a range of onsite wastewater nitrogen removal treatment alternatives should be recommended.

This section describes a planning level framework for recommended treatment systems and processes at three expected performance levels in regards to residential onsite wastewater nitrogen removal (level of treatment). Effluent quality from residential onsite wastewater systems can be highly variable, and depends on many factors in the home and the treatment system itself. For this reason, a range of expected treatment is provided at each of the three recommended nitrogen removal levels, described below:

**Low level residential onsite wastewater nitrogen removal:** defined as a system which achieves a 25 to 35 percent reduction in total nitrogen reaching the water table below the OSTDS. Assuming primary treatment followed by a STU, a 30% reduction is used as the basis for planning level nitrogen load reduction calculations at the low level.

**Medium level residential onsite wastewater nitrogen removal:** defined as a wastewater treatment system which achieves a 50 to 70 percent reduction in total nitrogen prior to discharge to a STU. Assuming discharge of the effluent to a STU, a 70% reduction in total nitrogen reaching the water table below the OSTDS is used as the basis for planning level nitrogen load reduction calculations at the medium level.

**High level residential onsite wastewater nitrogen removal:** defined as a wastewater treatment system which achieves an 85 to 95 percent reduction in total nitrogen prior to discharge to a STU. Assuming discharge of the effluent to a STU, a 95% reduction in total nitrogen reaching the water table below the OSTDS is used as the basis for planning level nitrogen load reduction calculations at the high level.

The expected operation, maintenance and permitting requirements are provided for each level of treatment. Example systems are run in PNRS LCCA to obtain planning level life cycle costs, assuming a 3 bedroom, 2200 ft<sup>2</sup> existing single family home and includes new conventional system components (primary tank and STU) as required by the system type. Fine sand soils are assumed at the site with a water table greater than 42 inches below grade. Based on these assumptions, the associated planning level PNRS LCCA output report is provided.

## **8.1 Low Level Onsite Wastewater Nitrogen Removal**

The low level nitrogen removal option is defined as a current code compliant conventional residential onsite wastewater treatment system. This OSTDS typically would consist of a two chamber primary treatment tank (i.e. septic tank) followed by a soil treatment unit (STU or drainfield). Soil treatment units can be bed or trench configuration. The low level option may require a mounded soil treatment unit as determined by site topography, seasonal high groundwater levels and soil characteristics. Maintaining at least a 2 foot separation between the STU infiltrative surface and the seasonal high water table is essential for nitrification and for achieving this level of nitrogen removal from effluent prior to reaching groundwater.

### **8.1.1 Expected Performance**

The low level nitrogen removal option provides an expected percentage of total nitrogen removal in the range of 25 to 35%. A 30% planning level TN removal rate is assigned for Low Level systems. Table 8-1 summarizes multiple studies that help to document the nitrogen removal performance of low level options. Anderson and Otis (2000) and Hazen & Sawyer and AET (2009a) each provided a literature review that includes many other examples of field studies documenting this level of treatment performance for properly functioning STUs. FOSNRS Task D.7 provided simple tools to aid in evaluation of nitrogen reduction in Florida soils. The Task D.7 look-up tables of HYDRUS-2D results show the estimated % total nitrogen removed for trench systems with equal distribution in fine sands range from 27 to 60 percent depending on the water table depth (Hazen & Sawyer and CSM, 2014). In addition to the simple tools, the STUMOD-FL-HPS model was developed as part of FOSNRS Task D to quantify vadose and groundwater nitrogen transport from residential onsite wastewater systems for user-specified conditions. The STUMOD-FL-HPS model output provides soil treatment, groundwater fate and transport, and quantitative estimations of nitrogen removal as affected by a range of conditions (Hazen & Sawyer and CSM, 2015).

The vadose zone model (STUMOD-FL) results in similar levels of TN concentration removal in fine sands which range from 35 to 65% depending on water table depth.

**Table 8-1: Performance References for Low Level Nitrogen Removal Option**

Reference	Mean % reduction from STE					
	TSS	CBOD <sub>5</sub>	TN	TKN	NH <sub>3</sub>	TP
Anderson et al., 1994 (Candler FS at 2', USF Lysimeter Station)	na	99	<b>51</b>	98	na	90
Long, 1995 (medium sand)	na	na	<b>40</b>	na	na	na
Long, 1995 (fine sand)	na	na	<b>60</b>	na	na	na
Anderson et al., 1998 (Keys OWNRS Report, Sand SDI Bed)	53	96	<b>34</b>	95	99	40
Anderson and Otis, 2000 (Conventional OWTS)	95	95	<b>10-50</b>	na	na	80-95
Hazen & Sawyer and AET, 2009a (Task A Literature Review)	na	na	<b>0-86<sup>a</sup></b>	na	na	na
Florida Onsite Sewage Nitrogen Reduction – Strategies Study						
Task B Home Systems, Hazen & Sawyer and AET, 2015						
BHS-3 Stage 1 Fine Sand Fill (LY01, LY02)	91	90	<b>48</b>	96	100	73
BHS-7 Candler FS (SL 01, 02, 03, 04)	90	91	<b>47</b>	94	99	96
BHS-5 Single Pass Stage 1, Expanded clay	94	86	<b>30</b>	91	95	67
BHS-4 Single Pass Stage 1, Expanded clay	85	94	<b>35</b>	83	88	65
BHS-6 Stage 1, Expanded clay (DP2)	na <sup>b</sup>	72	<b>25</b>	88	92	na
PNRS Pilot, Hazen & Sawyer and AET, 2014						
S&GW Test Facility TA1 (Trench) LY24S	na	na	<b>29</b>	95	100	97
S&GW Test Facility TA3 (Drip) LY24S	na	na	<b>61</b>	96	100	98
Task D Simple Tools (D.7), Hazen & Sawyer and CSM, 2014						
HYDRUS-2D runs @ denite rate 2.58 mg-N L <sup>-1</sup> d <sup>-1</sup>						
Trench equal distribution (fine sand), 2 ft water table	na	na	<b>27</b>	na	na	na
Trench equal distribution (fine sand), 6 ft water table	na	na	<b>60</b>	na	na	na
Task D Tools (D.16), Hazen & Sawyer and CSM, 2015						
STUMOD-FL runs @ denite rate 2.58 mg-N L <sup>-1</sup> d <sup>-1</sup>						
(LPS - fine sand), 2 ft water table	na	na	<b>35</b>	na	na	na
(LPS - fine sand), 3 ft water table	na	na	<b>47</b>	na	na	na
(LPS - fine sand), 6 ft water table	na	na	<b>65</b>	na	na	na

<sup>a</sup> Range of nitrogen reduction results from a review of numerous onsite wastewater studies

<sup>b</sup> TSS samples higher than STE, suspect media fines in samples

### **8.1.2 Operation and Maintenance**

The operation and maintenance requirement for low level nitrogen removal systems is minimal. Primary tank solids should be removed every three to five years. Conventional systems with a pump require periodic inspection and pump replacement if necessary, and a maintenance inspection of the pump and floats is recommended at the time of primary solids removal.

### **8.1.3 Permitting and Monitoring Requirements**

A new OSTDS requires a new system conventional construction permit from the Florida Department of Health. A retrofit system requires an existing system conventional construction permit from the Florida Department of Health. Water quality monitoring is not required for conventional OSTDS.

### **8.1.4 Life Cycle Cost Analysis**

The PNRS LCCA low level treatment planning level result for the example 3 bedroom single family house of 2,200 ft<sup>2</sup> area is shown in Table 8-2.



Table 8-2: PNRS LCCA Result for Low Level Nitrogen Removal Option (30%)

PNRS LCCA: Planning Level Life Cycle Cost Analysis Tool for Passive Nitrogen Reduction Systems

LCCA Identification: Low Level

Worksheet

1. LCCA Structure

2. Table of LCCA Worksheets

3. WW Quantity & System Parameters

4. PNRS Process Selection

5. Baseline Design & Cost

6. Baseline Design Cost Summary

7. User Override Costs

8. LCCA Conventional

9. LCCA Total System

10. Design Data

11. Example LCCAs

9. LCCA Total System

Present Worth (2015 dollars)

Installed Capital Cost

Engineering Design & Construction Permit

Operation & Maintenance

Compliance

Installed Capital Cost

Soil Treatment Unit

Proprietary Stage 1 System

Media

Pump(s)

Control Panel

Misc. Appurtenance

Piping

Drip Dispersal Unit Complete (control panel, valves, tubing, etc.)

Liner

Contractor Fee

Conventional System Summary

No. of Bedrooms

3

Building area, square feet

2200

Depth to seasonal high water table (inches)

42

New OSTDS installation or retrofit of existing system

retrofit

Design wastewater flow, gallon/day

300

PNRS System Summary

PNRS System

0

Stage 1: PNRS or proprietary

0

PNRS Stage(s)

0

Stage 1 in-tank or in-ground

0

Stage 1 single pass or recirculation

0

Stage 1 media type

0

Ligno disposition

0

Stage 2 media type

0

Construction Complexity

Moderate

Level of nitrogen removal efficiency provided by system

Low

Life Cycle Cost Calculations

Project Life (PL), years

30

Interest Rate (IR), %

2.000

Primary tank pump out interval (TI), years

5.0

Pump out analysis life (PL), years

25.0

Stage 2 media replacement interval (MI), years

0.0

Stage 2 media cost analysis life (ML), years

#DIV/0!

Equipment replacement interval (EI), years

10.0

Equipment replacement analysis life (EL), years

20.0

Compound Interest Factors

P/A PL/IR

22.396

A/P PL/IR

0.04465

A/F TI

0.19216

P/A PL

19.523

A/F MI

#DIV/0!

P/A ML

#DIV/0!

A/F EI

0.09133

P/A EL

16.351

Nitrogen Removal

Mass loading/year, lbs.

27.0

Removal efficiency, %

30.0

Mass removal/year, lbs.

8.10

Life Cycle Cost

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Total Life Cycle Cost

Conventional System Installation

Primary treatment tank

1,400.00

62.51

25.3

Pump tank

0.00

0.00

0.0

Conventional system pump

0.00

0.00

0.0

Soil treatment unit

2,625.00

117.21

47.4

Subtotal Conventional

4,025.00

179.72

72.6

Proprietary Stage 1 system

0.00

0.00

0.0

PNRS Installation

Tankage

0.00

0.00

0.0

Media

0.00

0.00

0.0

PNRS Pump

0.00

0.00

0.0

Control Panel

0.00

0.00

0.0

Piping

0.00

0.00

0.0

Misc. Appurtenance

0.00

0.00

0.0

Stage 1 Drip Dispersal System Complete (control panel, valves, tubing, etc.)

0.00

0.00

0.0

Liner

0.00

0.00

0.0

Contractor Fee

0.00

0.00

0.0

Subtotal

0.00

0.00

0.0

Total System Installation

4,025.00

179.72

72.6

Engineering Design & Construction Permit

Construction permit

580.00

25.90

10.5

Engineering design fees

0.00

0.00

0.0

Operation and Maintenance

Annual energy cost

0.00

0.00

0.0

Annual inspection & maintenance

0.00

0.00

0.0

Primary tank pump out

937.90

41.88

16.9

Stage 2 media replacement

0.00

0.00

0.0

Equipment replacement

0.00

0.00

0.0

Subtotal

937.90

41.88

16.9

Compliance

Operating permit fee

0.00

0.00

0.0

Water quality monitoring

0.00

0.00

0.0

Subtotal

0.00

0.00

0.0

Total

5,542.90

247.49

100.00

Installed Capital Cost

Installation

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Installation Cost

Tankage

1,400.00

62.51

34.8

Soil Treatment Unit

2,625.00

117.21

65.2

Proprietary Stage 1 System

0.00

0.00

0.0

Media

0.00

0.00

0.0

Pump(s)

0.00

0.00

0.0

Control Panel

0.00

0.00

0.0

Misc. Appurtenance

0.00

0.00

0.0

Piping

0.00

0.00

0.0

Drip Dispersal Unit Complete (control panel, valves, tubing, etc.)

0.00

0.00

0.0

Liner

0.00

0.00

0.0

Contractor Fee

0.00

0.00

0.0

Total System

4,025.00

179.72

100.0

Life Cycle Cost

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Total Life Cycle Cost

Installed Capital Cost

4,025.00

179.72

72.6

Engineering Design & Construction Permit

580.00

25.90

10.5

Operation & Maintenance

937.90

41.88

16.9

Compliance

0.00

0.00

0.0

Total

5,542.90

247.49

100.0

\$/lb nitrogen removed

22.80

30.54

Developed by:

HAZEN AND SAWYER

Environmental Engineers & Scientists

and

AET

Applied Environmental Technology





## 8.2 Medium Level Onsite Wastewater Nitrogen Removal

The recommended medium level nitrogen removal options consist of both an in-tank approach and an in-ground approach. The in-tank approach consists of a primary treatment tank (i.e. septic tank), a Stage 1 unsaturated biofilter with recirculation to a recirculation tank and a soil treatment unit. Soil treatment units could be bed or trench configuration. This option is similar to the BHS-2 Stage 1 module, without the Stage 2 biofilter.

The in-ground approach consists of a primary treatment tank (i.e. septic tank) followed by an in-ground Stage 1 unsaturated biofilter in native soil underlain by a Stage 2 lignocellulosic biofilter in a liner, with the effluent overflowing the liner into surrounding soil. This option is similar to the BHS-7 system, with low pressure effluent dosing to the Stage 1 biofilter. However, based on the hydraulic problems suspected at BHS-7, a larger liner and a 50/50 lignocellulosic/fine sand media mixture was assumed.

### 8.2.1 Expected Performance

The medium level nitrogen removal option provides wastewater treatment systems with an expected percentage of total nitrogen removal in the range of 50 to 70% prior to discharge to a STU. A 70% planning level TN removal rate is assigned for Medium Level systems when considering additional treatment provided by the soil treatment unit prior to effluent reaching the water table. Table 8-3 summarizes multiple studies that document nitrogen removal performance of medium level options.

**Table 8-3: Performance References for Medium Level Nitrogen Removal Option  
(Results prior to STU)**

Reference	Mean % reduction from STE				
	CBOD <sub>5</sub>	TN	TKN	NH <sub>3</sub>	TP
Venhuizen et al., 1998	94-98	<b>59-89</b>	na	na	na
Piluk & Peters, 1994	98	<b>59-70</b>	na	na	na
Osesek et al., 1994	95-98	<b>60-69</b>	73-89	71-89	62-74
Boyle et al., 1994	95-96	<b>57-59</b>	78-93	na	14-29
Florida Onsite Sewage Nitrogen Reduction Strategies Study					
Task B Home Systems, Hazen & Sawyer and AET, 2015					
BHS-2 In-tank Stage 1 Expanded Clay with Recirculation	86	<b>61</b>	94	98	32
BHS-3 In-ground Stage 1 underlain by Stage 2 Lignocellulosic	95	<b>84</b>	96	100	90
Florida Onsite Sewage Nitrogen Reduction Strategies Study					
PNRS Pilot, Hazen & Sawyer and AET, 2014					
S&GW Test Facility TA5 (PNRS In-ground biofilter 23)	94	<b>90</b>	95	99	24

### **8.2.2 Operation and Maintenance**

The medium level option requires a twice per year maintenance inspection under Florida code. Inspection should include pump operation and electrical connections, general hydraulic inspection including flow distribution to the Stage 1 biofilter, flushing and cleaning of distribution lines, inspection of biofilter media surfaces and measurement of recycle flowrate and adjustment if needed. The medium level option requires periodic inspection of the pump and replacement if necessary. Primary tank solids should be removed every three to five years.

### **8.2.3 Permitting and Monitoring Requirements**

A Performance Based Treatment System Construction Permit and a Performance Based Treatment System Operating Permit are required by the Florida Department of Health. Once per year water quality monitoring is recommended for TKN, ammonia nitrogen, nitrite + nitrate nitrogen, carbonaceous biochemical oxygen demand and alkalinity.

### **8.2.4 Life Cycle Cost Analysis**

The PNRS LCCA medium level planning level results for the example 3 bedroom house of 2,200 ft<sup>2</sup> area are shown in Tables 8-4 and 8-5. Table 8-4 provides the PNRS LCCA for an in-tank PNRS system that includes a Stage 1 biofilter with recirculation to a recirculation tank. Table 8-5 provides the PNRS LCCA for an in-ground PNRS system that includes a Stage 1 biofilter underlain by a Stage 2 lignocellulosic/fine sand mix biofilter in a liner.



Table 8-4: PNRS LCCA Result for Medium Level In-Tank Nitrogen Removal Option (70%)

PNRS LCCA: Planning Level Life Cycle Cost Analysis Tool for Passive Nitrogen Reduction Systems

LCCA Identification: Medium Level In-tank

Worksheet

1. LCCA Structure

2. Table of LCCA Worksheets

3. WW Quantity & System Parameters

4. PNRS Process Selection

5. Baseline Design & Cost

6. Baseline Design Cost Summary

7. User Override Costs

8. LCCA Conventional

9. LCCA Total System

10. Design Data

11. Example LCCAs

9. LCCA Total System

Present Worth (2015 dollars)

Installed Capital Cost

Engineering Design & Construction Permit

Operation & Maintenance

Compliance

Installed Capital Cost

Tankage

Soil Treatment Unit

Proprietary Stage 1 System

Media

Pump(s)

Control Panel

Misc. Appurtenance

Piping

Drip Dispersal Unit Complete (control panel, valves, tubing, etc.)

Liner

Contractor Fee

Conventional System Summary

No. of Bedrooms

3

Building area, square feet

2200

Depth to seasonal high water table (inches)

42

New OSTDS installation or retrofit of existing system

retrofit

Design wastewater flow, gallon/day

300

PNRS System Summary

PNRS System

22

Stage 1: PNRS or proprietary

PNRS

PNRS Stage(s)

Stage 1 only

Stage 1 in-tank or in-ground

Tank

Stage 1 single pass or recirculation

Recirculation

Stage 1 media type

EC

Ligno disposition

None

Stage 2 media type

None

Construction Complexity

Moderate

Level of nitrogen removal efficiency provided by system

Medium

Life Cycle Cost Calculations

Project Life (PL), years

30

Interest Rate (IR), %

2.000

Primary tank pump out interval (TI), years

5.0

Pump out analysis life (PL), years

25.0

Stage 2 media replacement interval (MI), years

15.0

Stage 2 media cost analysis life (ML), years

15.0

Equipment replacement interval (EI), years

10.0

Equipment replacement analysis life (EL), years

20.0

Compound Interest Factors

P/A PL/IR

22.396

A/P PL/IR

0.04465

A/F TI

0.19216

P/A PL

19.523

A/F MI

0.05783

P/A ML

12.849

A/F EI

0.09133

P/A EL

16.351

Nitrogen Removal

Mass loading/year, lbs.

27.0

Removal efficiency, %

70.0

Mass removal/year, lbs.

18.91

Life Cycle Cost

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Total Life Cycle Cost

Conventional System Installation

1,400.00

62.51

5.0

Primary treatment tank

0.00

0.00

0.0

Pump tank

0.00

0.00

0.0

Conventional system pump

2,625.00

117.21

9.4

Soil treatment unit

4,025.00

179.72

14.5

Subtotal Conventional

0.00

0.00

0.0

Proprietary Stage 1 system

0.00

0.00

0.0

PNRS Installation

Tankage

3,728.68

166.49

13.4

Media

1,234.09

55.10

4.4

PNRS Pump

250.00

11.16

0.9

Control Panel

875.00

39.07

3.1

Piping

144.80

6.47

0.5

Misc. Appurtenance

846.50

37.80

3.0

Stage 1 Drip Dispersal System Complete (control panel, valves, tubing, etc.)

0.00

0.00

0.0

Liner

0.00

0.00

0.0

Contractor Fee

2,500.00

111.62

9.0

Subtotal

9,579.07

427.70

34.4

Total System Installation

13,604.07

607.42

48.9

Engineering Design & Construction Permit

Construction permit

660.00

29.47

2.4

Engineering design fees

1,000.00

44.65

3.6

Operation and Maintenance

Annual energy cost

736.23

32.87

2.6

Annual inspection & maintenance

6,718.94

300.00

24.1

Primary tank pump out

937.90

41.88

3.4

Stage 2 media replacement

0.00

0.00

0.0

Equipment replacement

373.33

16.67

1.3

Subtotal

8,766.39

391.42

31.5

Compliance

Operating permit fee

1,119.82

50.00

4.0

Water quality monitoring

2,687.57

120.00

9.7

Subtotal

3,807.40

170.00

13.7

Total

27,837.86

1,242.96

100.00

Installed Capital Cost

Installation

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Installation Cost

Tankage

5,128.68

229.00

37.7

Soil Treatment Unit

2,625.00

117.21

19.3

Proprietary Stage 1 System

0.00

0.00

0.0

Media

1,234.09

55.10

9.1

Pump(s)

250.00

11.16

1.8

Control Panel

875.00

39.07

6.4

Misc. Appurtenance

846.50

37.80

6.2

Piping

144.80

6.47

1.1

Drip Dispersal Unit Complete (control panel, valves, tubing, etc.)

0.00

0.00

0.0

Liner

0.00

0.00

0.0

Contractor Fee

2,500.00

111.62

18.4

Total System

13,604.07

607.42

100.0

Life Cycle Cost

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Total Life Cycle Cost

Installed Capital Cost

13,604.07

607.42

48.9

Engineering Design & Construction Permit

1,660.00

74.12

6.0

Operation & Maintenance

8,766.39

391.42

31.5

Compliance

3,807.40

170.00

13.7

Total

27,837.86

1,242.96

100.0

S/lb nitrogen removed

49.07

65.73

Developed by:

Hazen and Sawyer

Environmental Engineers & Scientists

and

AET

Applied Environmental Technology





Table 8-5: PNRS LCCA Result for Medium Level In-Ground Nitrogen Removal Option (70%)

PNRS LCCA: Planning Level Life Cycle Cost Analysis Tool for Passive Nitrogen Reduction Systems

LCCA Identification: Medium Level In-ground

Worksheet

1. LCCA Structure

2. Table of LCCA Worksheets

3. WW Quantity & System Parameters

4. PNRS Process Selection

5. Baseline Design & Cost

6. Baseline Design Cost Summary

7. User Override Costs

8. LCCA Conventional

9. LCCA Total System

10. Design Data

11. Example LCCAs

9. LCCA Total System

Present Worth (2015 dollars)

Installed Capital Cost

Engineering Design & Construction Permit

Operation & Maintenance

Compliance

Installed Capital Cost

Soil Treatment Unit

Proprietary Stage 1 System

Media

Pump(s)

Control Panel

Misc. Appurtenance

Piping

Drip Dispersal Unit Complete (control panel, valves, tubing, etc.)

Liner

Contractor Fee

Conventional System Summary

No. of Bedrooms3

Building area, square feet2200

Depth to seasonal high water table (inches)42

New OSTDS installation or retrofit of existing systemretrofit

Design wastewater flow, gallon/day300

PNRS System Summary

PNRS System17

Stage 1: PNRS or proprietaryPNRS

PNRS Stage(s)Stage 1&2

Stage 1 in-tank or in-groundIn-ground

Stage 1 single pass or recirculationSingle pass

Stage 1 media typeNative Sand

Ligno dispositionUnderlying Stage 1 in-ground liner

Stage 2 media typeLigno only

Construction ComplexityModerate

Level of nitrogen removal efficiency provided by systemMedium

Life Cycle Cost Calculations

Project Life (PL), years30

Interest Rate (IR), %2.000

Primary tank pump out interval (TI), years5.0

Pump out analysis life (PL), years25.0

Stage 2 media replacement interval (MI), years30.0

Stage 2 media cost analysis life (ML), years0.0

Equipment replacement interval (EI), years10.0

Equipment replacement analysis life (EL), years20.0

Compound Interest Factors

P/A PL/IR22.396

A/P PL/IR0.04465

A/F TI0.19216

P/A PL19.523

A/F MI0.02465

P/A ML0.000

A/F EI0.09133

P/A EL16.351

Nitrogen Removal

Mass loading/year, lbs.27.0

Removal efficiency, %70.0

Mass removal/year, lbs.18.91

Life Cycle Cost

Conventional System Installation

Primary treatment tank1,400.0062.514.8

Pump tank0.000.000.0

Conventional system pump0.000.000.0

Soil treatment unit0.000.000.0

Subtotal Conventional1,400.0062.514.8

Proprietary Stage 1 system0.000.000.0

PNRS Installation

Tankage600.0026.792.1

Media2,301.25102.757.9

PNRS Pump250.0011.160.9

Control Panel875.0039.073.0

Piping289.6012.931.0

Misc. Appurtenance1,693.0075.595.8

Stage 1 Drip Dispersal System Complete (control panel, valves, tubing, etc.)0.000.000.0

Liner2,925.00130.6010.1

Contractor Fee5,000.00223.2517.2

Subtotal13,933.85622.1548.0

Total System Installation15,333.85684.6652.8

Engineering Design & Construction Permit

Construction permit660.0029.472.3

Engineering design fees1,000.0044.653.4

Operation and Maintenance

Annual energy cost184.068.220.6

Annual inspection & maintenance6,718.94300.0023.2

Primary tank pump out937.9041.883.2

Stage 2 media replacement0.000.000.0

Equipment replacement373.3316.671.3

Subtotal8,214.22366.7628.3

Compliance

Operating permit fee1,119.8250.003.9

Water quality monitoring2,687.57120.009.3

Subtotal3,807.40170.0013.1

Total29,015.471,295.54100.00

Installed Capital Cost

Installation

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Installation Cost

Tankage2,000.0089.3013.0

Soil Treatment Unit0.000.000.0

Proprietary Stage 1 System0.000.000.0

Media2,301.25102.7515.0

Pump(s)250.0011.161.6

Control Panel875.0039.075.7

Misc. Appurtenance1,693.0075.5911.0

Piping289.6012.931.9

Drip Dispersal Unit Complete (control panel, valves, tubing, etc.)0.000.000.0

Liner2,925.00130.6019.1

Contractor Fee5,000.00223.2532.6

Total System15,333.85684.66100.0

Life Cycle Cost

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Total Life Cycle Cost

Installed Capital Cost15,333.85684.6652.8

Engineering Design & Construction Permit1,660.0074.125.7

Operation & Maintenance8,214.22366.7628.3

Compliance3,807.40170.0013.1

Total29,015.471,295.54100.0

\$/lb nitrogen removed51.1568.51

Developed by:

HAZEN AND SAWYER

Environmental Engineers & Scientists

and

AET

Applied Environmental Technology





### **8.3 High Level Onsite Wastewater Nitrogen Removal**

The recommended high level nitrogen removal options consist of both an in-tank approach and an in-ground approach. The high level option consists overall of a primary treatment tank (i.e. septic tank), a Stage 1 unsaturated biofilter, a Stage 2 saturated media biofilter and a soil treatment unit. The in-tank Stage 1 biofilter hydraulics can be single pass or recirculation. In-tank Stage 2 biofilters can be single or dual media. The recommended in-tank system would be similar to BHS-2 or BHS-5. The in-ground system would contain the Stage 1/2a biofilter in a liner, with effluent collection to a saturated sulfur biofilter for further TN reduction, or directly to an STU. This system would be similar to BHS-3, but without drip distribution to the Stage 1 module. Soil treatment units can be bed or trench configuration. The high level option may require a mounded soil treatment unit as determined by site topography, seasonal high groundwater levels and soil characteristics.

#### **8.3.1 Expected Performance**

The high level nitrogen removal option provides wastewater treatment systems with an expected percentage of total nitrogen removal in the range of 85 to 95% prior to discharge to a STU. A 95% planning level TN removal rate is thus assigned for High Level systems when considering additional treatment provided by the soil treatment unit prior to effluent reaching the water table. Table 8-6 summarizes recent studies that document nitrogen removal performance of high level options.

**Table 8-6: Performance References for High Level Nitrogen Removal Options  
(Results prior to STU)**

Reference	Mean % reduction from STE				
	CBOD <sub>5</sub>	TN	NH <sub>3</sub>	TSS	TP
Smith, 2008 Passive Nitrogen Removal Study 1					
Two Stage Biofiltration					
Single Pass Stage 1 Expanded Clay/ Stage 2 Elemental Sulfur	>96	<b>95.2</b>	97.8	na	na
Single Pass Stage 1 Clinoptilolite/ Stage 2 Elemental Sulfur	>96	<b>96.7</b>	99.1	na	na
Florida Onsite Sewage Nitrogen Reduction Strategies Study					
PNRS Pilot, Hazen & Sawyer and AET, 2014					
Single Pass Stage 1 Expanded Clay/ Stage 2 Elemental Sulfur Biofilter 6-SU-30	97	<b>97.7</b>	99	97	na
Stage 1 with Recirculation Composite/ Stage 2 Elemental Sulfur Biofilter 15-SU-80	80	<b>95.3</b>	97	98	44
Stage 1 with Recirculation Composite/ Stage 2 Elemental Sulfur Biofilter 16-SU-30	87	<b>96.8</b>	99	96	na
S&GW Test Facility TA5 (PNRS In-ground biofilter 23)	64	<b>95</b>	98	19	44
Task B Home Systems, Hazen & Sawyer and AET, 2015					
BHS-2 Recirculating Stage 1 Expanded Clay/ Stage 2 Ligno & Elemental Sulfur	36	<b>93</b>	95	76	40
BHS-5 Recirculating Stage 1 Expanded Clay/ Stage 2 Ligno & Elemental Sulfur	86	<b>98</b>	98	90	83
BHS-4 Single Pass Stage 1 Expanded Clay/Stage 2 Ligno & Elemental Sulfur	91	<b>89</b>	93	93	72
BHS-3 In-ground Stage 1 Sand Underlain by Stage 2 Ligno & In-tank Elemental Sulfur	80	<b>96</b>	99	81	96

### 8.3.2 Operation and Maintenance

The high level nitrogen removal options require twice per year maintenance inspection under Florida code. Inspection should include pump operation and electrical connection, general hydraulic inspection including flow distribution to the Stage 1 biofilter, flushing and cleaning of distribution lines, inspection of biofilter media surfaces and measurement of recycle flowrate and adjustment if needed. The high level option requires periodic inspection of the pump and replacement if necessary. Primary tank solids should be removed every three to five years.

### 8.3.3 Permitting and Monitoring Requirements

The Performance Based Treatment System Construction Permit and a Performance Based Treatment System Operating Permit are required by the Florida Department of Health. Once per year water quality monitoring is recommended for TKN, ammonia nitrogen, nitrite + nitrate nitrogen, carbonaceous biochemical oxygen demand and alkalinity.



#### **8.3.4 Life Cycle Cost Analysis**

The PNRS LCCA high level nitrogen removal system planning level results for the example 3 bedroom house of 2,200 ft<sup>2</sup> area are shown in Tables 8-7 and 8-8. Table 8-7 provides the PNRS LCCA for an in-tank PNRS system that includes a Stage 1 biofilter with recirculation and Stage 2 dual media biofilter. Table 8-8 provides the PNRS LCCA for an in-ground PNRS system that includes a Stage 1 biofilter underlain by a Stage 2a lignocellulosic biofilter in a liner and an additional Stage 2b sulfur biofilter tank prior to the STU.



-THIS PAGE INTENTIONALLY LEFT BLANK-



Table 8-7: PNRS LCCA Result for High Level In-tank Nitrogen Removal Option (95%)

PNRS LCCA: Planning Level Life Cycle Cost Analysis Tool for Passive Nitrogen Reduction Systems

LCCA Identification: High Level In-tank

Worksheet

1. LCCA Structure

2. Table of LCCA Worksheets

3. WW Quantity & System Parameters

4. PNRS Process Selection

5. Baseline Design & Cost

6. Baseline Design Cost Summary

7. User Override Costs

8. LCCA Conventional

9. LCCA Total System

10. Design Data

11. Example LCCAs

9. LCCA Total System

Present Worth (2015 dollars)

Installed Capital Cost

Engineering Design & Construction Permit

Operation & Maintenance

Compliance

Installed Capital Cost

Engineering Design & Construction Permit

Operation & Maintenance

Compliance

Installed Capital Cost

Engineering Design & Construction Permit

Operation & Maintenance

Compliance

Installed Capital Cost

Engineering Design & Construction Permit

Operation & Maintenance

Compliance

Conventional System Summary

No. of Bedrooms

3

Building area, square feet

2200

Depth to seasonal high water table (inches)

42

New OSTDS installation or retrofit of existing system

retrofit

Design wastewater flow, gallon/day

300

PNRS System Summary

PNRS System

9

Stage 1: PNRS or proprietary

PNRS

PNRS Stage(s)

Stage 1&2

Stage 1 in-tank or in-ground

Tank

Stage 1 single pass or recirculation

Recirculation

Stage 1 media type

Expanded Clay

Ligno disposition

Tank

Stage 2 media type

Dual: Ligno & sulfur

Construction Complexity

Moderate

Level of nitrogen removal efficiency provided by system

High

Life Cycle Cost Calculations

Project Life (PL), years

30

Interest Rate (IR), %

2.000

Primary tank pump out interval (TI), years

5.0

Pump out analysis life (PL), years

25.0

Stage 2 media replacement interval (MI), years

15.0

Stage 2 media cost analysis life (ML), years

15.0

Equipment replacement interval (EI), years

10.0

Equipment replacement analysis life (EL), years

20.0

Compound Interest Factors

P/A PL/IR

22.396

A/P PL/IR

0.04465

A/F TI

0.19216

P/A PL

19.523

A/F MI

0.05783

P/A ML

12.849

A/F EI

0.09133

P/A EL

16.351

Nitrogen Removal

Mass loading/year, lbs.

27.0

Removal efficiency, %

95.0

Mass removal/year, lbs.

25.66

Life Cycle Cost

Conventional System Installation

Primary treatment tank

1,400.00

62.51

4.1

Pump tank

0.00

0.00

0.0

Conventional system pump

0.00

0.00

0.0

Soil treatment unit

2,625.00

117.21

7.7

Subtotal Conventional

4,025.00

179.72

11.9

Proprietary Stage 1 system

0.00

0.00

0.0

PNRS Installation

Tankage

4,609.29

205.80

13.6

Media

2,226.78

99.43

6.6

PNRS Pump

250.00

11.16

0.7

Control Panel

875.00

39.07

2.6

Piping

289.60

12.93

0.9

Misc. Appurtenance

1,693.00

75.59

5.0

Stage 1 Drip Dispersal System Complete (control panel, valves, tubing, etc.)

0.00

0.00

0.0

Liner

0.00

0.00

0.0

Contractor Fee

5,000.00

223.25

14.7

Subtotal

14,943.67

667.23

44.0

Total System Installation

18,968.67

846.95

55.9

Engineering Design & Construction Permit

Construction permit

660.00

29.47

1.9

Engineering design fees

1,000.00

44.65

2.9

Operation and Maintenance

Annual energy cost

736.23

32.87

2.2

Annual inspection & maintenance

6,718.94

300.00

19.8

Primary tank pump out

937.90

41.88

2.8

Stage 2 media replacement

737.58

32.93

2.2

Equipment replacement

373.33

16.67

1.1

Subtotal

9,503.98

424.35

28.0

Compliance

Operating permit fee

1,119.82

50.00

3.3

Water quality monitoring

2,687.57

120.00

7.9

Subtotal

3,807.40

170.00

11.2

Total

33,940.05

1,515.42

100.00

Installed Capital Cost

Installation

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Installation Cost

Tankage

6,009.29

268.31

31.7

Soil Treatment Unit

2,625.00

117.21

13.8

Proprietary Stage 1 System

0.00

0.00

0.0

Media

2,226.78

99.43

11.7

Pump(s)

250.00

11.16

1.3

Control Panel

875.00

39.07

4.6

Misc. Appurtenance

1,693.00

75.59

8.9

Piping

289.60

12.93

1.5

Drip Dispersal Unit Complete (control panel, valves, tubing, etc.)

0.00

0.00

0.0

Liner

0.00

0.00

0.0

Contractor Fee

5,000.00

223.25

26.4

Total System

18,968.67

846.95

100.0

Life Cycle Cost

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Total Life Cycle Cost

Installed Capital Cost

18,968.67

846.95

55.9

Engineering Design & Construction Permit

1,660.00

74.12

4.9

Operation & Maintenance

9,503.98

424.35

28.0

Compliance

3,807.40

170.00

11.2

Total

33,940.05

1,515.42

100.0

\$/lb nitrogen removed

44.09

59.05

Developed by:

Hazen and Sawyer

Environmental Engineers & Scientists

and

AET

Applied Environmental Technology







Table 8-8: PNRS LCCA Result for High Level In-ground Nitrogen Removal Option (95%)

PNRS LCCA: Planning Level Life Cycle Cost Analysis Tool for Passive Nitrogen Reduction Systems

LCCA Identification: High Level In-ground

Worksheet

1. LCCA Structure

2. Table of LCCA Worksheets

3. WW Quantity & System Parameters

4. PNRS Process Selection

5. Baseline Design & Cost

6. Baseline Design Cost Summary

7. User Override Costs

8. LCCA Conventional

9. LCCA Total System

10. Design Data

11. Example LCCAs

9. LCCA Total System

Present Worth (2015 dollars)

Installed Capital Cost

Engineering Design & Construction Permit

Operation & Maintenance

Compliance

Installed Capital Cost

Tankage

Soil Treatment Unit

Proprietary Stage 1 System

Media

Pump(s)

Control Panel

Misc. Appurtenance

Piping

Drip Dispersal Unit Complete (control panel, valves, tubing, etc.)

Liner

Contractor Fee

Conventional System Summary

No. of Bedrooms

3

Building area, square feet

2200

Depth to seasonal high water table (inches)

42

New OSTDS installation or retrofit of existing system

retrofit

Design wastewater flow, gallon/day

300

PNRS System Summary

PNRS System

18

Stage 1: PNRS or proprietary

PNRS

PNRS Stage(s)

Stage 1&2

Stage 1 in-tank or in-ground

In-ground

Stage 1 single pass or recirculation

Single pass

Stage 1 media type

Native Sand

Ligno disposition

Underlying Stage 1 in-ground liner

Stage 2 media type

Dual: Ligno & sulfur

Construction Complexity

Moderate

Level of nitrogen removal efficiency provided by system

High

Life Cycle Cost Calculations

Project Life (PL), years

30

Interest Rate (IR), %

2.000

Primary tank pump out interval (TI), years

5.0

Pump out analysis life (PL), years

25.0

Stage 2 media replacement interval (MI), years

15.0

Stage 2 media cost analysis life (ML), years

15.0

Equipment replacement interval (EI), years

10.0

Equipment replacement analysis life (EL), years

20.0

Compound Interest Factors

P/A PL/IR

22.396

A/P PL/IR

0.04465

A/F TI

0.19216

P/A PL

19.523

A/F MI

0.05783

P/A ML

12.849

A/F EI

0.09133

P/A EL

16.351

Nitrogen Removal

Mass loading/year, lbs.

27.0

Removal efficiency, %

95.0

Mass removal/year, lbs.

25.66

Life Cycle Cost

Conventional System Installation

Primary treatment tank

1,400.00

62.51

4.1

Pump tank

0.00

0.00

0.0

Conventional system pump

0.00

0.00

0.0

Soil treatment unit

2,625.00

117.21

7.8

Subtotal Conventional

4,025.00

179.72

11.9

PNRS Installation

Tankage

1,200.00

53.58

3.5

Media

3,219.84

143.77

9.5

PNRS Pump

250.00

11.16

0.7

Control Panel

875.00

39.07

2.6

Piping

289.60

12.93

0.9

Misc. Appurtenance

1,693.00

75.59

5.0

Stage 1 Drip Dispersal System Complete (control panel, valves, tubing, etc.)

0.00

0.00

0.0

Liner

2,925.00

130.60

8.6

Contractor Fee

5,000.00

223.25

14.8

Subtotal

15,452.44

689.95

45.7

Total System Installation

19,477.44

869.67

57.6

Engineering Design & Construction Permit

Construction permit

660.00

29.47

2.0

Engineering design fees

1,000.00

44.65

3.0

Operation and Maintenance

Annual energy cost

184.06

8.22

0.5

Annual inspection & maintenance

6,718.94

300.00

19.9

Primary tank pump out

937.90

41.88

2.8

Stage 2 media replacement

682.53

30.47

2.0

Equipment replacement

373.33

16.67

1.1

Subtotal

8,896.75

397.24

26.3

Compliance

Operating permit fee

1,119.82

50.00

3.3

Water quality monitoring

2,687.57

120.00

7.9

Subtotal

3,807.40

170.00

11.3

Total

33,841.59

1,511.02

100.00

Installed Capital Cost

Installation

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Installation Cost

Tankage

2,600.00

116.09

13.3

Soil Treatment Unit

2,625.00

117.21

13.5

Proprietary Stage 1 System

0.00

0.00

0.0

Media

3,219.84

143.77

16.5

Pump(s)

250.00

11.16

1.3

Control Panel

875.00

39.07

4.5

Misc. Appurtenance

1,693.00

75.59

8.7

Piping

289.60

12.93

1.5

Drip Dispersal Unit Complete (control panel, valves, tubing, etc.)

0.00

0.00

0.0

Liner

2,925.00

130.60

15.0

Contractor Fee

5,000.00

223.25

25.7

Total System

19,477.44

869.67

100.0

Life Cycle Cost

Cost Item

Present Worth, \$

Uniform Annual Cost, \$

% of Total Life Cycle Cost

Installed Capital Cost

19,477.44

869.67

57.6

Engineering Design & Construction Permit

1,660.00

74.12

4.9

Operation & Maintenance

8,896.75

397.24

26.3

Compliance

3,807.40

170.00

11.3

Total

33,841.59

1,511.02

100.0

\$/lb nitrogen removed

43.96

58.88

Developed by:

HAZEN AND SAWYER

Environmental Engineers & Scientists

and

AET

Applied Environmental Technology

H&S Project No. 44237-003  
August 2015

8-14

HAZEN AND SAWYER  
Environmental Engineers & Scientists




## 8.4 Comparison of Recommended Nitrogen Removal System Costs

Comparison of the PNRS LCCA planning level results for the three residential onsite wastewater nitrogen removal levels is shown in Table 8-9 and Figure 8-1. As the nitrogen removal level of the recommended systems proceeds from low to medium to high, construction costs, total present worth of life cycle costs and lbs. per year of nitrogen removed increase. The present worth cost per pound of nitrogen removed is lowest for the low level options (conventional treatment), however they also remove much less nitrogen than the PNRS options. The high level treatment options have lower cost per pound of nitrogen removed than the medium level options. Construction costs, operation and maintenance costs and compliance costs are all significantly higher for the medium and high nitrogen removal level options than for conventional OSTDS.

**Table 8-9 Comparison of PNRS LCCA Results for Recommended Nitrogen Removal Systems**

Nitrogen Removal Level	System	Present Worth, \$					Lbs/year Nitrogen removed	\$ PW/ lb. Nitrogen Removed
		Total	Construction	Engineering Design and Permit	Operation and Maintenance	Compliance		
Low (25-35%)	Conventional: primary treatment + soil treatment unit	5,542.90	4,025.00	580.00	937.90	0.00	8.1	22.80
Medium (50-70%)	Conventional + In-tank PNRS Stage 1 + R tank	27,837.86	13,604.07	1,660.00	8,766.39	3,807.40	18.9	49.07
	Conventional + PNRS In-ground Stage 1 underlain by Stage 2	29,015.47	15,333.85	1,660.00	8,214.22	3,807.40	18.9	51.15
High (85-95%)	Conventional + PNRS In-tank Stage 1 + PNRS In-tank Stage 2	33,940.05	18,968.67	1,660.00	9,503.98	3,807.40	25.7	44.09
	Conventional + PNRS In-ground Stage 1&2a + PNRS In-tank Stage 2b	33,841.59	19,477.44	1,660.00	8,896.75	3,807.40	25.7	43.96

**Figure 8-1 Total Present Worth of Life Cycle Costs and Construction Costs  
for Three Recommended Nitrogen Removal Systems**



## **9 Conclusions and Recommendations**

This report provides a summary of the full scale passive nitrogen reduction system (PNRS) prototype development, design, installation and testing under Task B of the Florida Onsite Sewage Nitrogen Reduction Strategies (FOSNRS) Project. It provides a summary background of the FOSNRS project and the goals and objectives of the full-scale prototype evaluations (Sections 1 & 2). Section 3 provides the background leading to the selection of the passive nitrogen reduction system treatment processes that were tested, and the basic design concepts that were used to design the full scale prototype systems. The prototype PNRS that were designed, constructed and tested are described in Section 4, along with the test sites chosen and monitoring methods used. Section 5 presents the results of the full scale prototype PNRS testing and evaluations based on the monitoring reports developed earlier in Task B. An analysis of the monitoring data collected and discussion of the results is provided in Section 6. Section 7 presents the Life Cycle Cost Analysis of full scale PNRS based on the PNRS LCCA tool developed earlier in Task B. Based on the results and experience gained from the full scale testing of prototype PNRS, recommended treatment processes for onsite wastewater nitrogen reduction in Florida are presented in Section 8. The recommended PNRS are organized by technologies that can provide low, medium or high levels of nitrogen removal from residential onsite wastewater, depending on the nitrogen sensitivity of the receiving waters. Finally, this section (Section 9) summarizes conclusions drawn from the prototype PNRS evaluations and provides recommendations for next steps in moving forward with PNRS in Florida.

### **9.1 PNRS Technologies and Performance**

Based on a review, prioritization and ranking of available onsite wastewater nitrogen removal technologies in Task A of the FOSNRS project, nitrogen removal by two-stage biofiltration was selected as the most operationally simple, effective and applicable nitrogen removal process for development of Passive Nitrogen Reduction Systems (PNRS) for onsite wastewater treatment. A unique pilot scale test facility was therefore designed and constructed at the UF Gulf Coast Research and Education Center to test numerous design concepts for two-stage biofiltration and to develop further design criteria for implementation of full scale PNRS for testing in FOSNRS Task B. Based on approximately two years of pilot study results, seven full scale prototype two-stage biofilter based PNRS were designed and constructed for evaluation at existing homes in Florida.

The seven prototype single family home PNRS evaluated in FOSNRS Task B encompassed a variety of designs of passive two-stage biofiltration systems for onsite nitrogen removal. Construction of each PNRS was evaluated for cost and ease of construction, and the systems were subsequently monitored over an approximately 2 year period with water quality sampling conducted bi-monthly over 18 months. The prototype systems have performed very well over multiple years in real onsite conditions. Nitrogen

removal performance of the full scale PNRS confirmed the results of previous PNRS pilot testing and established the two-stage biofiltration process as an effective and viable technology for onsite nitrogen removal. The prototype system demonstrations provide valuable guidance for future PNRS design for individual homesites and for planning level analysis to achieve nitrogen reduction goals in Florida. The prototype PNRS performance was such that, with relatively minor design refinements, several of the system designs could be configured for innovative systems permitting. Several other systems showed considerable potential as PNRS, but need further design refinements and testing. The results of individual home PNRS testing revealed:

- The prototype PNRS Stage 1 biofilters were all very effective in nitrifying organic and ammonia nitrogen to nitrate+nitrite (NO<sub>x</sub>) nitrogen (Table 6-1). Mean ammonia removal efficiencies for the seven prototype PNRS Stage 1 biofilters ranged from 88 to 100%, which provided a Stage 1 effluent (Stage 2 influent) suitable for denitrification and high total nitrogen removal efficiency.
- All seven Stage 1 biofilters also achieved some level of denitrification and total nitrogen (TN) removal (Table 6-1). Mean TN removal efficiency by the Stage 1 biofilters ranged from 18 to 61%, with the highest efficiency achieved in system BHS-2 by recycling a portion of the nitrified effluent to a recirculation tank for significant pre-denitrification.
- The PNRS Stage 2 biofilters were very effective in denitrifying NO<sub>x</sub> nitrogen to gaseous N forms, thus reducing Total Nitrogen in the system effluent. Mean NO<sub>x</sub>-N removal efficiency for the Stage 2 lignocellulosic biofilters ranged from 41 to 100%, with the lower performance from system BHS-6 which experienced hydraulic problems and malfunctioned on several occasions (Table 6-3). Mean NO<sub>x</sub>-N removal efficiency for the Stage 2 elemental sulfur biofilters ranged from 74 to 100% (Table 6-5). Since all Stage 2 sulfur biofilters were preceded by a lignocellulosic biofilter, there was often very little NO<sub>x</sub> reaching the sulfur media, which influenced the efficiency. Mean NO<sub>x</sub>-N concentrations in sulfur biofilter effluents ranged from below detection limits (0.02 mg N/L) to 4.4 mg NO<sub>x</sub>-N/L for the Stage 2 biofilters containing sulfur media. Excluding system BHS-6 (hydraulic malfunctions), mean Stage 2 effluent from sulfur biofilters was less than 1 mg NO<sub>x</sub>-N/L.
- The mean Total Nitrogen (TN) removal efficiency for the seven full scale prototype passive two-stage nitrogen removal systems ranged from 65 to 98% with an overall mean of 90% for all systems (Table 6-11). However, the nitrogen removal efficiency of the three most refined and best performing prototype systems (BHS-2, BHS-3 and BHS-5) averaged over 95% TN removal. The two lowest performing PNRS (BHS-6 and BHS-7) showed the potential to achieve similar TN removal efficiencies at times, but their performance was hampered by less than optimal design or construction issues.

- The mean effluent Total Nitrogen (TN) concentration for the seven prototype PNRS ranged from 1.8 to 19.1 mg/L (Table 6-10). The highest mean TN effluent concentrations can be attributed to the BHS-7 design issues previously discussed. Once again, the most refined and best performing prototype systems (BHS-2, BHS-3 and BHS-5) produced a mean effluent TN concentration of 2.6 mg/L.
- The mean CBOD<sub>5</sub> removal efficiency for the seven full scale prototype passive two-stage nitrogen removal systems ranged from 36 to 91% with an overall mean of 79% for all systems (Table 6-11). The mean Stage 2 effluent in most of the systems showed an increase in CBOD<sub>5</sub> concentration as compared to the Stage 1 effluent which may be attributed to CBOD<sub>5</sub> release from the lignocellulosic media itself. The BHS-2 system which incorporated a sawdust lignocellulosic media is associated with the highest concentration of Stage 2 CBOD<sub>5</sub>.
- The mean TSS removal efficiency for the seven full scale prototype passive two-stage nitrogen removal systems ranged from 76 to 97% with an overall mean of 89% for all systems (Table 6-11). The mean effluent TSS concentration for all seven systems was below 10 mg/L (Table 6-10).
- The mean Total Phosphorus (TP) removal efficiency for the seven full scale prototype passive two-stage nitrogen removal systems ranged from 12 to 96% with an overall mean of 64% for all systems (Table 6-11). The best performing PNRS were the in-ground systems (BHS-3 and BHS-7). An evaluation of the long term phosphorus adsorption capacity of the evaluated media was not conducted as part of this study, and phosphorus removal may decline at some future point when P adsorption sites become limiting.
- The geomean of effluent fecal coliform concentration for the seven prototype PNRS ranged from 1 to 1,838 ct/100 mL. The highest geomean fecal coliform count can be attributed to the BHS-6 design issues previously discussed. The most refined and best performing prototype systems (BHS-2, BHS-3 and BHS-5) produced an effluent fecal coliform concentration below 60 ct/100 mL.
- The mean effluent sulfate concentration for the five full scale prototype passive two-stage nitrogen removal systems that utilized sulfur media ranged from 37 to 248 mg/L (Table 6-7). Therefore, the mean effluent sulfate levels were below the secondary drinking water guideline of 250 mg/L for all systems utilizing sulfur media.
- Mean electrical consumption of the prototype PNRS was 4.5 kw-hour per 1000 gallons of wastewater flow from the home and ranged from 0 to 28.7 kw-hr/1000 gallon (Table 5-7). The



highest energy usages were for BHS-1 due to a Stage 1 biofilter with a very high recirculation ratio and BHS-3 which included pumping to drip dispersal zones for both Stage 1 STE and final effluent irrigation. Operation of single pass in-tank systems ranged from 0 to 3.2 kw-hour per 1000 gallons, while operation of recirculating in-tank systems (with a 3:1 R ratio) ranged from 1.2 to 2.8 kw-hour per 1000 gallons. This electrical use would equate to a cost of less than \$1.00 per month for a PNRS similar to the single pass or recirculating Stage 1 systems tested.

- Operation and maintenance (O&M) of the prototype PNRS reflected system complexity (Table 5-6). The simplest system O&M was the BHS-7 in-ground PNRS, which has O&M requirements similar to a conventional OSTDS with pressure dosed STU. Slightly more complex were the in-tank PNRS with single pass Stage 1 biofilters. O&M of these PNRS was also relatively simple, adding only the Stage 1 STE distribution system to the O&M requirements. The O&M of the in-tank PNRS with Stage 1 recirculation is only slightly more complex than the single pass systems, in that timed dosing is added to the controls, and the recirculation ratio must be checked and adjusted occasionally. The most complex system was BHS-3, and this complexity was due to the use of drip dispersal for both STE application in Stage 1 and irrigation of final treated effluent to turf grass, all with one pump. This system had O&M requirements similar to more complex PBTS or STE drip systems. However, without the irrigation component, and with STE low pressure distribution instead of drip, this system would be similar to the single pass Stage 1 in-tank systems in O&M complexity.
- The longevity of the PNRS reactive media could not be determined directly in the seven prototype PNRS evaluations due to the very low use of media over the approximately 2 year observation period. Theoretical calculations and literature experience with both lignocellulosic and sulfur Stage 2 biofilters suggests that it would not be difficult to design systems for media life of 25 years or longer (Tables 6-8 and 6-9). It would also be relatively easy to add reactive media to the in-tank Stage 2 biofilters, and sizing of these systems could potentially be reduced if routine media additions were made during the life of the system.

## 9.2 PNRS Cost

A life cycle cost analysis (LCCA) tool for PNRS (PNRS LCCA) was developed as part of the FOSNRS project. The PNRS LCCA can be used as a planning level tool using default performance parameters or for evaluation of specific treatment technologies incorporating known performance data. In addition, the PNRS LCCA can be used to evaluate a user defined nitrogen removal efficiency for non-PNRS. The PNRS LCCA was used to develop life cycle costs based on the seven prototype PNRS and for other advanced onsite wastewater treatment systems for comparison purposes (Section 7). The PNRS LCCA tool provides an output report summarizing the life cycle cost analysis.

- A comparison of estimated construction costs between PNRS LCCA and the actual construction costs for the seven prototype systems showed good agreement, with a relative percent error between the two costs of approximately 11%.
- The mean estimated as-built construction cost for the seven PNRS was \$17,726 and ranged from \$10,399 to \$32,116. One of the lowest estimated construction cost was for the BHS-7 in-ground PNRS, which was also the simplest system. While this system's performance was less than optimal, design revisions to the Stage 2 liner module could potentially make it the most cost effective of all systems. Highest construction cost was for BHS-3, a dual drip dispersal PNRS with turf grass irrigation. Construction costs of in-tank 2 stage biofilter PNRS were in the middle of the range with construction costs of \$18,000 to \$20,000. It should be noted that all seven prototype PNRS were installed at existing homes, which required additional construction time and restoration of property, increasing costs as compared to a new home installation. Additionally, these were prototype systems (with the exception of the proprietary BHS-1) that were unfamiliar to contractors and which had not been designed and constructed in Florida previously. Costs for PNRS would most likely come down with more standard designs and widespread implementation.
- The average total present worth of PNRS LCCA for the seven prototype PNRS was \$35,836 and ranged from \$24,838 to 53,253 (Table 7-9). Highest Present Worth was for the BHS-3 dual drip dispersal system, while the simpler designs had lower Present Worth.
- Of key importance is that non-construction costs accounted for 38 to 57% of the total present worth of the prototype PNRS (46% mean). In general order of higher to lower cost, these items included annual inspection and maintenance fees, water quality monitoring, primary tank solids removal, operating permit fees, energy costs and media and equipment replacement.
- The average Present Worth cost per pound of nitrogen removal for the seven prototype PNRS was \$41.95 /lb. N, and ranged from \$29 to \$52 /lb. N (Figure 7-5). A comparison with the

Maryland Bay Restoration Fund (BRF) data indicated that the prototype PNRS operated at a lower present worth cost per pound of nitrogen removal than the PBTS evaluated by Maryland BRF, and at significantly greater effluent TN removal efficiencies (Figure 7-6).

### 9.3 Recommended Treatment Process Framework and Level of Treatment Expectations

The nutrient sensitivity of Florida watersheds varies greatly, and includes areas of extremely high sensitivity to nitrogen loading and other areas where nitrogen loading from OSTDS may be less critical. To accommodate this variability, three operational levels of nitrogen removal efficiency were established as part of an onsite nutrient reduction strategy related to treatment technologies (Section 8):

- Low level residential onsite wastewater nitrogen removal was defined as a system which achieves a 25 to 35 percent reduction in total nitrogen reaching the water table below the OSTDS. Assuming primary treatment followed by a STU, a 30% reduction is used as the basis for planning level nitrogen load reduction calculations at the low level (Table 8-1).
- Medium level residential onsite wastewater nitrogen removal was defined as a wastewater treatment system which achieves a 50 to 70 percent reduction in total nitrogen prior to discharge to a STU. Assuming discharge of the effluent to a STU, a 70% reduction in total nitrogen reaching the water table below the OSTDS is used as the basis for planning level nitrogen load reduction calculations at the medium level. Technologies for medium level nitrogen removal include in-tank Stage 1 biofilters with recirculation for pre-denitrification or an in-ground single pass Stage 1 unsaturated biofilter over a Stage 2 lignocellulosic/fine sand media mix contained in a liner. Table 8-3 provides references for the performance of such treatment technologies; the STU following the medium level nitrogen removal treatment technology would provide additional water quality treatment.
- High level residential onsite wastewater nitrogen removal was defined as a wastewater treatment system which achieves an 85 to 95 percent reduction in total nitrogen prior to discharge to a STU. Assuming discharge of the effluent to a STU, a 95% reduction in total nitrogen reaching the water table below the OSTDS is used as the basis for planning level nitrogen load reduction calculations at the high level. Technologies for high level nitrogen removal include:
  - single pass unsaturated biofilters followed by denitrification biofilters with lignocellulosic media
  - single pass unsaturated biofilters followed by denitrification biofilters with sulfur media

- single pass unsaturated biofilters followed by denitrification biofilters with lignocellulosic and sulfur media (dual media)
- recirculating unsaturated biofilters followed by denitrification biofilters with sulfur media
- recirculating unsaturated biofilters followed by denitrification biofilters with lignocellulosic and sulfur media (dual media)

References for the performance of such treatment technologies are provided in Table 8-6; the STU following the high level nitrogen removal treatment technology would provide additional water quality treatment.

#### **9.4 Technical Recommendations**

The FOSNRS project has demonstrated that passive nitrogen removal systems (PNRS) can provide effective and resilient nitrogen removal from onsite wastewater. Prior to moving ahead with PNRS implementation however, further technical refinements will be required of the prototype systems developed and tested in this project. The following technical recommendations are made based on the experience and results obtained during the FOSNRS project.

- The prototype PNRS installed as part of this study have operated for approximately 2 years as of this writing. While this period was long enough to establish the treatment performance of the systems, long term performance and reliability of the systems is unknown. Therefore, it is recommended that FDOH establish long term monitoring of these home systems. This would provide invaluable knowledge of continued system performance, the longevity of media, further guidance for system designs and the long term needs for maintenance and monitoring.
- The prototype systems installed were designed and constructed based on available equipment and materials, to establish the process and performance basis for PNRS designs. Some of the equipment, tanks and media required for the PNRS were not readily available and existing materials were customized to meet the needs of the project, adding difficulty and expense. Therefore, the systems as currently designed and constructed are not ready for widespread implementation.
- Prior to implementation at the State level, detailed PNRS design criteria need to be developed. To kick start PNRS implementation, several standardized PNRS designs could be established with technical specifications for system sizing and for all system components. Innovative system

permits (or other new type of permit) should be developed for these initial PNRS. Other designs would eventually evolve if widespread implementation of onsite nitrogen removal was required.

- Specifications should be established for biofilter tankage and other system tankage to be used in PNRS, including tanks spaced across a range of sizes pertinent to single home PNRS. Specifications should include specific tank designations, source, materials, dimensions, strength requirements and pre-approved suppliers.
- Specifications should be established for tank lids and covers that provide full and easy access to media within PNRS biofilters, including pre-approved suppliers, specific tank designations, source, materials, dimensions and technical specifications.
- Specifications should be established for liners used for in-ground PNRS including pre-approved suppliers, specific liner designations, source and technical specifications.
- Specifications should be established for PNRS media including pre-approved suppliers, specific media size designations, media description, source and technical specifications.

## **9.5 Recommendations for PNRS Implementation**

Passive nitrogen removal systems (PNRS) can provide effective nitrogen removal from onsite wastewater and are a practical and resilient technology. Substantial benefits can accrue to the State of Florida through proper and judicious application of PNRS where necessary. There are also challenges to PNRS implementation that must be addressed. If the benefits of PNRS are to be realized in practice, the State must prepare for the implementation of PNRS by addressing several issues:

- Watershed/water body sensitivity to nitrogen varies widely across the state. Determination of necessary nutrient reductions to protect or improve water quality by watershed and GIS mapping of nutrient sensitive zones would allow determination of which level of nitrogen reduction is required for implementation in a given location. Nitrogen load reductions from onsite wastewater should not be required everywhere, and in many locations upgrading existing OSTDS to current standards may be enough.
- Uniform guidance for regulation and permitting specific to PNRS need to be established, and should be streamlined. The existing permitting structure as applied to the new PNRS technology may become cumbersome, leading to lack of implementation, delay and administrative burden. Generic permitting of the initial pre-approved designs for several PNRS could speed implementation of PNRS while insuring the effective performance of installed systems.

- Uniform requirements for inspecting and maintaining PNRS should be established and updated as necessary. FDOH should establish a uniform policy for inspection and maintenance of PNRS through private or public maintenance entities.
- Uniform requirements for performance and performance monitoring of PNRS should be established and updated as necessary. FDOH should establish a uniform policy for treatment requirements and performance monitoring of PNRS.
- FDOH should implement technology transfer and training on PNRS implementation for state personnel, county regulators, industry contractors, environmental engineers and scientists.
- Sufficient staffing by FDOH is crucial for PNRS implementation. Review and permitting of PNRS should be conducted by engineers with education and experience in onsite wastewater treatment and by or under the supervision of a licensed Professional Engineer with similar experience.



-THIS PAGE INTENTIONALLY LEFT BLANK-



## 10 References

- Anderson, D. L. (1998). Natural denitrification in groundwater impacted by onsite wastewater treatment systems. Proceedings of On-Site Wastewater Treatment - Eighth International Symposium on Individual and Small Community Sewage Systems. Orlando, Florida, ASAE. 8: 336-345.
- Anderson, D. L., J. Hirst, et al. (2014). Full-scale performance of a two-stage biofiltration system for reduction of nitrogen. Paper presented at Annual Conference, National Onsite Wastewater Recycling Association (NOWRA)/Colorado Professionals in Onsite Wastewater (CPOW), Denver, CO, November 2014.
- Anderson, D.L. and R.J. Otis (2000). Integrated wastewater management in growing urban environments. American Society of Agronomy, Crop Science Society of America, Soil Science Society of America, Madison, WI. 39: 199-250.
- Anderson, D.L. and A.J. Janicki (2010). Linking receiving water impacts to sources and to water quality management decisions: using nutrients as an initial case study. Project Report WERF 3C10, Water Environment Research Foundation ([www.werf.org](http://www.werf.org)), Alexandria, VA.
- Anderson, D.L.; R.J. Otis, J.I. McNeillie, and R.A. Apfel (1994). In-situ lysimeter investigation of pollutant attenuation in the vadose zone of a fine sand. Proceedings of the On-Site Wastewater Treatment - Seventh National Symposium on Individual and Small Community Sewage Systems, ASAE, St. Joseph, MI. 7: 209-218.
- Batchelor, B. and A.W. Lawrence (1978). Autotrophic denitrification using elemental sulfur. Journal WPCF. 50, 8: 1986-2001.
- Boyle, W. C., R. J. Otis, et al. (1994). Nitrogen removal from domestic wastewater in unsewered areas. Proceedings of On-Site Wastewater Treatment - Seventh International Symposium on Individual and Small Community Sewage Systems. E. Collins. Atlanta, Georgia, ASAE. 7: 485-498.
- Cameron, S.G. and L.A. Schipper (2010). Nitrate removal and hydraulic performance of organic carbon for use in denitrification beds. Ecological Engineering, 36: 1588-1595.
- Cameron, S.G. and L.A. Schipper (2012). Hydraulic properties, hydraulic efficiency and nitrate removal of organic carbon media for use in denitrification beds. Ecological Engineering. 41: 1-7.
- Hazen & Sawyer, AET and OEC (2009a). Literature review of nitrogen reduction technologies for onsite sewage treatment systems, FOSNRS Task A.2, Submitted to the Florida Department of Health, Tallahassee, Florida, August 2009.
- Hazen & Sawyer, AET and OEC (2009b). Classification, ranking and prioritization of technologies final report, FOSNRS Task A.7, A.8 and A.9, Submitted to the Florida Department of Health, Tallahassee, Florida, September 2009.

- Hazen & Sawyer and AET (2010). Quality assurance project plan, FOSNRS Task B.5, Submitted to the Florida Department of Health, Tallahassee, Florida, October 2010.
- Hazen & Sawyer and AET (2014). PNRS II test facility final report, FOSNRS Task A.28, Submitted to the Florida Department of Health, Tallahassee, Florida, April 2014.
- Hazen & Sawyer and AET (2015). Passive nitrogen reduction system life cycle cost analysis tool (PNRS LCCA) user guide, FOSNRS Task B.12, Submitted to the Florida Department of Health, Tallahassee, Florida, revised June 2015.
- Hazen & Sawyer and CSM (2014). Task D simple soil tools white paper, FOSNRS Task D.7, Submitted to the Florida Department of Health, Tallahassee, Florida, revised May 2014.
- Hazen & Sawyer and CSM (2015). Task D report and STUMOD-FL-HPS user's guide draft report, FOSNRS Task D.16, Submitted to the Florida Department of Health, Tallahassee, Florida, June 2015.
- Hirst, J. and D. Anderson (2015). Backyard BNR a passive nitrogen reduction system shows promising results for onsite wastewater treatment. Water Environment and Technology. 27(3): 40-43.
- Hirst, J., D. Anderson, and D. Smith (2014). Florida pilot study of two-stage biofiltration for reduction of nitrogen from OWS. Paper presented at Annual Conference, National Onsite Wastewater Recycling Association (NOWRA)/Colorado Professionals in Onsite Wastewater (CPOW), Denver, CO, November 2014.
- Long, T. (1995). Methodology to predict nitrogen loading from on-site sewage treatment systems. University of Washington, Seattle, WA, College of Engineering, University of Washington, Seattle, WA.
- Long, L., L. Schipper, and D. Bruesewitz (2011). Long-term nitrate removal in a denitrification wall. Ecological Engineering. 140: 514-520.
- Kanter, R. D., E. J. Tyler, and J.C. Converse (1998). A denitrification system for domestic wastewater using sulfur oxidizing bacteria. Proceedings of On-Site Wastewater Treatment - Eighth National Symposium on Individual and Small Community Sewage Systems, Orlando, Florida, ASAE. 8: 509-519.
- Maryland Department of the Environment (2015). Bay restoration fund ranking documentation 2015. from: [http://www.mde.state.md.us/programs/Water/BayRestorationFund/OnsiteDisposalSystems/Pages/water/cbwrf/osds/brf\\_bat.aspx](http://www.mde.state.md.us/programs/Water/BayRestorationFund/OnsiteDisposalSystems/Pages/water/cbwrf/osds/brf_bat.aspx)
- Moorman T.B., et al. (2010). "Denitrification activity, wood loss, and N<sub>2</sub>O emissions over 9 years from a wood chip bioreactor. Ecological Engineering, 36:11 1567-1574.
- Osesek, S., B. Shaw, and J. Graham (1994). Design and optimization of two recirculating sand filter systems for nitrogen removal. Proceedings of On-Site Wastewater Treatment - Seventh International Symposium on Individual and Small Community Sewage Systems. E. Collins. Atlanta, Georgia, ASAE. 7: 319-328.

- Piluk, R. J. and E. C. Peters (1994). Small recirculating sand filters for individual homes. Proceedings of On-Site Wastewater Treatment - Seventh International Symposium on Individual and Small Community Sewage Systems. E. Collins. Atlanta, Georgia, ASAE. 7: 310-318.
- Robertson, W. D. and J. A. Cherry (1995). In situ denitrification of septic-system nitrate using reactive porous media barriers: field trials. Ground Water 33:1 99-111.
- Robertson, W. D., D. W. Blowes, et al. (2000). Long-term performance of in situ reactive barriers for nitrate remediation. Ground Water 38:5 689-695.
- Robertson, W., J.L. Vogan and P.S. Lombardo (2008). Nitrate removal rates in a 15-year-old permeable reactive barrier treating septic system nitrate. Ground Water Monitoring and Remediation 28:3 65-72.
- Robertson, W. D. (2010). Nitrate removal rates in woodchip media of varying age. Ecological Engineering, 36: 1581-1587.
- Schipper L. and M. Vojvodic-Vokuvic (1998). Nitrate removal from groundwater using a denitrification wall amended with sawdust: field trial. J. Environ. Qual. 27: 664-668.
- Schipper L. and M. Vojvodic-Vokuvic (2001). Five years of nitrate removal, denitrification and carbon dynamics in a denitrification wall. Wat. Res. 35:14 3473-3477.
- Schipper, L., S. Cameron, and S. Warneke (2010a). Nitrate removal from three different effluents using large-scale denitrification beds. Ecological Engineering. 36:11 1552-1557.
- Schipper, L.A, et al. (2010b). Denitrifying bioreactors – An approach for reducing nitrate loads to receiving waters. Ecological Engineering, 36:11 1532-1543.
- Schmidt, C.A. and M.W. Clark (2012). Efficacy of a denitrification wall to treat continuously high nitrate loads. Ecological Engineering, 42: 203-211.
- Schmidt, C.A. and M.W. Clark (2013). Deciphering and modeling the physicochemical drivers of denitrification rates in bioreactors. Ecological Engineering, 60: 276-288.
- Sengupta, S. and S. Ergas (2006). Autotrophic biological denitrification for complete removal of nitrogen from septic system wastewater. Water, Air and Soil Pollution.
- Shao, M., T. Zhang and H. HP. Fang (2010). Sulfur-driven autotrophic denitrification: diversity, biochemistry, and engineering applications. Appl. Microbiol. Biotechnol., 88: 1027-1042
- Siegrist R.L. and P.D. Jenssen (1989). Nitrogen removal during wastewater infiltration as affected by design and environmental factors. Presented at the 6<sup>th</sup> Onsite Waste Treatment Shortcourse, University of Washington, Seattle, September 1989.
- Smith, D. (2009a). Modular nitrogen removal in distributed sanitation water treatment systems. Environmental Engineer, Spring, American Academy of Environmental Engineers, Annapolis, MD.
- Smith, D. (2009b). Sanitation water nitrogen reduction with two-stage biofiltration. Presented at Water Environment Federation Technical Exhibition and Conference (WEFTEC), Orlando, Florida, October 2009.



- Smith, D. (2012). Onsite wastewater nitrogen reduction with expanded media and elemental sulfur biofiltration. Water Science & Technology, 65.4: 750-756.
- Smith, D., R. Otis, and M. Flint (2008). Florida passive nitrogen removal study final report. Submitted to the Florida Department of Health, Tallahassee, Florida, June 2008.
- Venhuizen, D., J. H. Wiersma, and J. A. Williams (1998). Washington island project: evolution of the denitrifying sand filter concept. Proceedings of On-Site Wastewater Treatment - Eighth International Symposium on Individual and Small Community Sewage Systems. Orlando, Florida, ASAE. 8: 470-479.